

802-T-224 SIGN, GROUND MOUNTED, RESET

(Adopted 02-20-20)

The Standard Specifications are revised as follows:

SECTION 802, AFTER LINE 7, INSERT AS FOLLOWS:

*Existing ground mounted signs to be reset shall be removed without damage, stored and re-installed as shown on the plans.*

SECTION 802, BEGIN LINE 229, INSERT AS FOLLOWS:

**802.09 Removal, *Resetting*, or Relocation of Signs or Support Assemblies**

Signs to be relocated shall be installed in accordance with the MUTCD and on new posts. *Signs to be reset shall be installed in accordance with the MUTCD and on existing posts.*

SECTION 802, AFTER LINE 280, INSERT AS FOLLOWS:

*Existing ground mounted signs reset will be measured by the number of signs removed and reinstalled, complete in place.*

SECTION 802, BEGIN LINE 305, INSERT AS FOLLOWS:

*Existing ground mounted signs reset will be paid for at the contract unit price per each.*

SECTION 802, AFTER LINE 332, INSERT AS FOLLOWS:

*Sign, Ground Mounted, Reset ..... EACH*

SECTION 802, AFTER LINE 384, INSERT AS FOLLOWS:

*The cost of existing ground mounted sign removal, existing post removal, and storage shall be included in the cost of sign resetting. Existing signs or posts that are damaged by the Contractor shall be replaced with no additional payment.*

