

601-R-146 REMOVAL OF GUARDRAIL

(Revised 05-01-25)

The Standard Specifications are revised as follows:

SECTION 601, BEGIN LINE 203, DELETE AND INSERT AS FOLLOWS:

601.10 Removal of Existing Guardrail

Removal of existing guardrail shall be in accordance with the applicable requirements of 202 and these requirements. The locations shall be as shown on the plans. ~~When it is specified that~~ The removed guardrail is to become the property of the Department. The rail elements, posts, and blockouts shall be removed without being damaged. The removed material shall be stored as directed.
