

## 801-R-471 MATERIAL USED FOR TEMPORARY INGRESS/EGRESS TO PROPERTIES

(Revised 05-23-13)

**Description**

This work shall consist of constructing temporary access drives to properties shown on the plans where access is affected by work on the contract.

**Materials**

Materials shall be in accordance with the following:

Coarse Aggregate, Size No. 53.....904.03

**Construction Requirements**

A good, well-maintained approach shall be provided to homes and businesses affected by the work on the project. An undistributed quantity of material has been assigned to this item and shall be used as determined in the field when needed so that all approaches are well maintained. The Contractor shall inform the Engineer when materials are being placed for this purpose. The Contractor shall provide the Engineer with material delivery tickets.

As driveways are completed, excess material shall be removed. If the Engineer determines that the removed material is still acceptable, the Engineer may direct the Contractor to use the material for other temporary access drives currently being maintained on the contract. The Contractor may also choose to incorporate excess material in other portions of the work if the Engineer agrees that the material is not out of specification by being too contaminated. Disposal of any excess material shall be in accordance with 203.08.

**Method of Measurement**

Compacted aggregate No. 53, Temporary for Driveways will be measured by the ton based on the quantity delivered to the jobsite and used for that purpose.

**Basis of Payment**

The accepted quantities of compacted aggregate No. 53, Temporary for Driveways will be paid for at the contract price per ton.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit Symbol</b>
-----------------	------------------------

Compacted Aggregate No. 53, Temporary for Driveways.....	TON
--	-----

The cost of removal of the material is included in the cost of this pay item. The cost of disposal of the material is included in the cost of this pay item.

The cost of removing and re-placing the material at another location in accordance with this provision is included in the cost of this pay item.