

## 801-T-235 MAINTAINING TRAFFIC FOR IDIQ

(Adopted 06-15-23)

**Description**

This work shall consist of maintaining traffic for completing the scope of work set forth in the Work Order in accordance with 105.03 and 801.

**Materials**

Materials shall be in accordance with 801.02.

**Construction Requirements**

At the time of the Joint Scoping Meeting and discussion of the work order, the Engineer and the Contractor will determine the needs for maintaining traffic to complete the work order scope of work. This shall include, but not be limited to, drums, set up, adjustment and tear down of drums or other traffic devices, and shift differentials to accommodate limitations on when the work shall occur as needed.

Maintenance of traffic shall be in accordance with the applicable portions of 801.

**Method of Measurement**

Maintenance of traffic will be measured in accordance with 801.17.

**Basis of Payment**

Payment for maintaining traffic will be calculated based on the needs to complete the scope of work for the work order at the time of the joint scoping meeting and when the Work Order Request Form has been completed by the Contractor.

Payment will be made under:

**Pay Item****Pay Unit Symbol**

Maintaining Traffic, IDIQ ..... DOL

The costs of material, transportation, placement, and all incidentals shall be included in the cost of the pay item.