

PROPOSAL

FIRE FACILITIES INC.

314 WILBURN ROAD
SUN PRAIRIE, WI 53590-9401



"ASK BEFORE YOU BUY" - THE ONLY MAJOR STEEL FIRE TRAINING TOWER MANUFACTURED IN THE UNITED STATES



To:	From:	
Indiana Department of Homeland Security Bid: 385-22-68491 Mobile Class A Live Fire Training Trailer Proposal # 5261	John Schauf Regional Manager	Date: September 14, 2021 Phone: 1-800-929-3726 or (608) 327-4100 Fax: 1-866-639-7012 or (608) 834-1843 E-mail: jschauf@firefacilities.com

Remarks:

This proposal is regarding the price requested for Indianapolis, IN.
The total estimated weight for these materials is 23,336.74 lbs.
The total price for this fire tower or parts, F.O.B. destination is \$180,289.00 as described below: * See tax note below
Freight: \$1,801.00

Freight + Material Price: \$182,090.00

Custom Painted Wesco Model MBR-25 (Mobile Trainee) w/ 2-5/16" Ball Receiver

Galv. Stairs And Railings Meet OSHA Standards For Private Use And Do Not Meet Building Code Requirements For Public Use

Total Price Above Includes The Following Itemized List:

- (1) Scout temp. meter (data logging, alarms, and Bluetooth enabled): \$3,590.00; 19 #'s
- Basement Trainer On Front Of Trailer With Removable Ext. Ladder and Fixed Interior Stair: \$13,724.00; 1642 #'s
- (1) Burn Crib - 1/8" S.S. Class A Burn Prop (35"x49"x6" High) w/Caster Wheels (See Exception #4): \$1,256.00; 102 #'s
- Dividing Wall w/ 3'-0" x 7'-0" Framed Opening Splitting the Burn Room into (2) Rooms: \$5,520.00; 1,010 #'s
- (1) Combination Lock Box for Trailer Keys: \$95.00; 5 #'s
- (6) Sets of Keys: N/A (Provided by Others; see Exception #1)
- (1) 12' Alco-lite Double Hook Ladders (Customer to Field Cut to Size): \$570.00; 50 #'s
- (1) 4'-0" x 8'-0" Adjustable Pitch Roof Chopout Prop Frame with 3'-0" x 3'-0" Chopout: \$1,140.00; 300 #'s
- (1) Brass Siamese Fire Dept. Conn. (NST Thread) With Galv. 3" Dia. Riser (Approx. 6 ft. high): \$3,545.00; 290 #'s
- Foldable Roof Rail: \$14,832.00; 1,308 #'s
- Customer Logo Panels - 3' x 5': N/A (Supplied by Customer, installation Included in Trailer Cost)
- Floor Mounted Stainless Steel D-Ring Tie Down Points Spaced at 4'-0" O.C. Along both Side Walls: \$479.00; 12 #'s
- Drain Holes in Burn Room(s): N/A (Included in Trailer Cost)
- Generator: N/A (Supplied by Customer)
- (1) Cellular Texting Alarm(s) For Use With The Scout Temp. Meter: \$479.00; 7 #'s

Total Price Above Also Includes The Following:

- (2) Stabilizing Scissor Jacks for Rear of Trailer
 - (2) 3'-0" x 3'-0" Vent Roof Hatches w/ Lifiable Covers From Ground Level
- All Shutters to have Drywall Holders (for 3/4" thickness of drywall) and Stainless Steel Sill Trims
Shutters and Burn Room Doors Have An Interior and Exterior Operating Lever Latch
Travel Expenses for Pre Delivery Inspection for (4) People

Exceptions:

- Padlocks and Keys are By Others
- Pitched Roof Prop is 4' x 8' and Will Adjust to 3:12, 4:12 and 6:12 Pitch Only
- 3' x 3' Steel Roof Hatches in Lieu of the 2' x 2' Specified
- 3' Rack for Burn Prop is By Others
- Doors are Not Push Open; Level Latch Operation Only
- Roof Hatches are Approximately 3'-2" from ends; not 6'-0"
- Floor Mounted D-Rings are Not Recessed & Are Stainless Steel for Heat and Corrosion Resistance
- Temperature Monitoring Controls are Located on the Back of the Trailer for Ease of Access

Per Drawings REVISED August 9, 2021

Ship date is 10-14 weeks upon receipt of signed contract. Payment is due in full, 30 days from ship date. Prices quoted in U.S. Dollars. Prices include the design, materials, fabrication, and freight only - foundation and erection labor prices only if shown.

3004.eff.0320

Applicable taxes may need to be added based on location. Prices effective 180 days from proposal due date of September 17, 2021.

1 of 1