

Schedule of Pay Items Letting Date February 15, 2024 Letting ID 240215

Call: 130

Contract: R -40890-B

Section No.: 1

NEW ROAD CONSTRUCTION

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
	0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
	0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
	0013	202-52710	SIDEWALK CONCRETE, REMOVE	111.00	SYS
	0014	203-02000	EXCAVATION, COMMON	13063.00	CYS
	0015	203-02010	EXCAVATION, ROCK	80.00	CYS
	0016	203-02070	BORROW	6890.00	CYS
	0017	204-08552	VIBRATING WIRE SETTLEMENT SYSTEM	6.00	EACH
	0018	204-08553	DATA LOGGING SYSTEM	12.00	EACH
	0019	204-11633	VIBRATING WIRE PIEZOMETER	3.00	EACH
	0020	205-12108	STORMWATER MANAGEMENT BUDGET	24480.00	DOL
	0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0022	205-12618	SWQCP PREPARATION	1.00	LS
	0023	206-51215	EXCAVATION, X	8.00	CYS
	0024	207-08262	SUBGRADE TREATMENT, TYPE I	3583.00	SYS
	0025	207-08264	SUBGRADE TREATMENT, TYPE II	1028.00	SYS
	0026	207-08266	SUBGRADE TREATMENT, TYPE III	1761.00	SYS
	0027	207-08268	SUBGRADE TREATMENT, TYPE IV	1128.00	SYS
	0028	211-02050	B BORROW	1395.00	CYS
	0029	211-09264	STRUCTURE BACKFILL, TYPE 1	908.00	CYS
	0030	211-09266	STRUCTURE BACKFILL, TYPE 3	37310.00	CYS
	0031	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	2.00	CYS

0032	214-11796	GEOGRID, TYPE IB	1028.00	SYS
0033	214-12237	GEOTEXTILE FOR PAVEMENT, TYPE 1B	270.00	SYS
0034	217-11917	DRYING SOILS FOR EMBANKMENT	102.00	TON
0035	301-12234	COMPACTED AGGREGATE, NO. 53	1436.00	CYS
0036	302-06464	SUBBASE FOR PCCP	92.00	CYS
0037	302-07455	DENSE GRADED SUBBASE	172.00	CYS
0038	303-05738	AGGREGATE, NO. 5	135.00	TON
0039	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	75.00	TON
0040	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	395.00	TON
0041	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	658.00	TON
0042	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	1951.00	TON
0043	401-10258	JOINT ADHESIVE, SURFACE	1255.00	LFT
0044	401-10259	JOINT ADHESIVE, INTERMEDIATE	1255.00	LFT
0045	401-11785	LIQUID ASPHALT SEALANT	1255.00	LFT
0046	402-07452	HMA WEDGE AND LEVEL, TYPE C	10.00	TON
0047	406-05520	ASPHALT FOR TACK COAT	3.00	TON
0048	502-11543	PCCP, 4 IN.	49.00	SYS
0049	503-05240	D-1 CONTRACTION JOINT	446.00	LFT
0050	503-12477	TERMINAL JOINT, TYPE HMA	98.00	LFT
0051	601-09146	IMPACT ATTENUATOR, CR1-W1, TL-2	4.00	EACH
0052	602-06729	BARRIER DELINEATOR	27.00	EACH
0053	602-11938	CONCRETE BARRIER, MODIFIED SECTION	178.60	CYS
0054	603-01159	FENCE, CHAIN LINK, PVC COATED, 42 IN.	140.00	LFT
0055	604-05528	HMA FOR SIDEWALK	453.00	TON
0056	604-06070	SIDEWALK, CONCRETE	14.00	SYS
0057	604-08086	CURB RAMP, CONCRETE	236.00	SYS
0058	604-12083	DETECTABLE WARNING SURFACES	23.00	SYS
0059	604-95344	HANDRAIL, PEDESTRIAN	821.00	LFT
0060	605-02278	CURB, REMOVE	747.00	LFT
0061	605-06145	CURB AND GUTTER, TYPE B, CONCRETE	189.00	LFT
0062	605-06150	CURB AND GUTTER, TYPE C, CONCRETE	628.00	LFT
0063	605-52807	CURB AND GUTTER, COMBINED	443.00	LFT
0064	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	408.00	SYS
0065	610-09108	PCCP FOR APPROACHES, 9 IN.	1028.00	SYS
0066	615-06490	RIGHT-OF-WAY MARKER	33.00	EACH
0067	616-05688	RIPRAP, CLASS 1	4.00	TON
0068	616-06405	RIPRAP, REVETMENT	7.00	TON

0069	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	13.00	SYS
0070	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0071	621-06545	FERTILIZER	1.00	TON
0072	621-06554	SEED MIXTURE, TYPE U	284.00	LBS
0073	621-06565	MULCHING MATERIAL	3.00	TON
0074	621-06567	WATER	2.00	KGAL
0075	621-06575	SODDING, NURSERY	434.00	SYS
0076	622-52436	SIGN, "DO NOT MOW OR SPRAY"	9.00	EACH
0077	622-98200	SIGN, "DO NOT DISTURB"	9.00	EACH
0078	628-09403	FIELD OFFICE, TYPE C	20.00	MOS
0079	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0080	628-11977	COMPUTER SYSTEM	1.00	EACH
0081	629-12029	PLANT GROWTH LAYER	7215.00	SYS
0082	701-08253	PILE, SLEEVES	28.00	EACH
0083	701-09558	TEST PILE, INDICATOR, PRODUCTION	124.00	LFT
0084	701-09560	TEST PILE, INDICATOR, RESTRIKE	2.00	EACH
0085	701-09683	PILE SHOE, HP 12 X 74	28.00	EACH
0086	701-95780	PILE, STEEL H, HP 12 X 74	1352.00	LFT
0087	702-51015	CONCRETE, B, FOOTINGS	1.00	CYS
0088	703-06029	REINFORCING BARS, EPOXY COATED	216440.00	LBS
0089	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	48.00	EACH
0090	704-51002	CONCRETE, C, SUPERSTRUCTURE	389.30	CYS
0091	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TYPE TPF-1	2.00	EACH
0092	706-08496	REINFORCED CONCRETE MOMENT SLAB, 12 IN.	920.00	SYS
0093	706-11404	RAILING, STEEL TYPE PF-1	1144.00	LFT
0094	706-11418	RAILING, STEEL TYPE PS-1	182.00	LFT
0095	706-11455	BRIDGE RAILING PEDESTRIAN FENCE	172.00	LFT
0096	706-11455	BRIDGE RAILING PEDESTRIAN FENCE	171.00	LFT
0097	706-11601	RAILING, CONCRETE TYPE FT	3.60	CYS
0098	706-11602	RAILING, CONCRETE TYPE PF-1	70.10	CYS
0099	706-11604	RAILING, CONCRETE TYPE PS-1	10.70	CYS
0100	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFT	2.00	EACH
0101	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFT	2.00	EACH
0102	709-07110	SEAL COAT GRAFFITI RESISTANT	33572.00	SFT
0103	709-51821	SURFACE SEAL	1.00	LS
0104	709-51821	SURFACE SEAL	1.00	LS
0105	711-07857	INCLINOMETER	3.00	EACH

0106	711-51038	STRUCTURAL STEEL	1.00	LS
0107	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	2771.00	LFT
0108	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	432.00	LFT
0109	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	449.00	LFT
0110	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	103.00	LFT
0111	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	674.00	LFT
0112	715-09064	VIDEO INSPECTION FOR PIPE	1658.00	LFT
0113	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00	EACH
0114	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	2771.00	LFT
0115	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	2088.00	SYS
0116	718-52610	AGGREGATE FOR UNDERDRAINS	525.00	CYS
0117	720-09079	INLET, TYPE HA5, MODIFIED	8.00	EACH
0118	720-12797	CASTING, INLET, ADJUST TO GRADE	1.00	EACH
0119	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	1.00	EACH
0120	720-45042	INLET, TYPE HA5	8.00	EACH
0121	720-45410	MANHOLE, TYPE C4	11.00	EACH
0122	720-98174	INLET, TYPE B15	1.00	EACH
0123	720-98555	INLET, TYPE C15	2.00	EACH
0124	722-12732	LONGITUDINAL GROOVING	944.00	SYS
0125	731-93945	FACE PANELS, CONCRETE	52126.00	SFT
0126	731-93946	WALL ERECTION	52126.00	SFT
0127	731-93947	LEVELING PAD, CONCRETE	1884.00	LFT
0128	732-11770	AGGREGATE FOR DRAINAGE FILL	43.00	CYS
0129	732-11810	MODULAR BLOCK WALL	1060.00	SFT
0130	732-11811	MODULAR BLOCK WALL ERECTION	1060.00	SFT
0131	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00	EACH
0132	801-06640	CONSTRUCTION SIGN, TYPE A	7.00	EACH
0133	801-06645	CONSTRUCTION SIGN, TYPE B	4.00	EACH
0134	801-06775	MAINTAINING TRAFFIC	1.00	LS
0135	801-07118	BARRICADE, TYPE III-A	72.00	LFT
0136	801-07119	BARRICADE, TYPE III-B	40.00	LFT
0137	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	28.00	LFT
0138	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	10.00	SFT
0139	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	53.00	SFT
0140	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	56.00	SFT
0141	804-06770	DELINEATOR POST	3.00	EACH
0142	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	4.00	EACH

0143	805-01842	HANDHOLE, SIGNAL, TYPE 1	4.00 EACH
0144	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	694.00 LFT
0145	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	8.00 EACH
0146	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	4.00 EACH
0147	805-07767	SIGNAL CABLE, CONTROL, COPPER, 12C/14 GAUGE	576.00 LFT
0148	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	3.00 EACH
0149	805-11817	PEDESTRIAN PUSH BUTTON, APS	8.00 EACH
0150	805-78109	CONTROLLER AND CABINET, SECONDARY MENU DRIVEN, 8 PHASE	1.00 EACH
0151	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	8.00 EACH
0152	805-78225	TRAFFIC SIGNAL HEAD, NO. 4 SECTION, 12 IN.	2.00 EACH
0153	805-78415	SPAN, CATENARY, AND TETHER	4.00 EACH
0154	805-78420	DISCONNECT HANGER	4.00 EACH
0155	805-78445	SIGNAL SERVICE	1.00 EACH
0156	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	22.00 LFT
0157	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	2090.00 LFT
0158	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GAUGE	1125.00 LFT
0159	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	1472.00 LFT
0160	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	63.00 LFT
0161	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	743.00 LFT
0162	805-78785	SIGNAL DETECTOR HOUSING	5.00 EACH
0163	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	617.00 LFT
0164	805-78925	CONTROLLER CABINET FOUNDATION, TYPE P1	1.00 EACH
0165	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	4.00 EACH
0166	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	4.00 EACH
0167	807-02782	LUMINAIRE MAST ARM, 12 FT	4.00 EACH
0168	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	296.00 LFT
0169	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	370.00 LFT
0170	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	4.00 EACH
0171	807-86805	SERVICE POINT, TYPE I	1.00 EACH
0172	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	304.00 LFT
0173	807-86910	CONNECTOR KIT, UNFUSED	4.00 EACH
0174	807-86915	CONNECTOR KIT, FUSED	4.00 EACH
0175	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	12.00 EACH
0176	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	8.00 EACH
0177	807-86930	INSULATION LINK, NON-WATERPROOFED	8.00 EACH
0178	807-86935	INSULATION LINK, WATERPROOFED	16.00 EACH
0179	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	410.00 LFT

0180	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	6.00	SYS
0181	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4033.00	LFT
0182	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	504.00	LFT
0183	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	504.00	LFT
0184	808-06716	LINE, REMOVE	1640.00	LFT
0185	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	52.00	LFT
0186	808-11960	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 24 IN.	63.00	LFT
0187	808-12273	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, WHITE, 4 IN.	423.00	LFT
0188	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5295.00	LFT
0189	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	114.00	LFT
0190	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	4.00	EACH
0191	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	2.00	EACH
0192	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	28.00	EACH

Call: 140

Contract: R -41318-C

Section No.: 1

BIKE AND PEDESTRIAN FACILITIES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-02255	TREE, 18 IN., REMOVE	4.00	EACH
0013	201-02260	TREE, 30 IN., REMOVE	1.00	EACH
0014	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0015	202-02240	PAVEMENT REMOVAL	1242.00	SYS
0016	202-02278	CURB, CONCRETE, REMOVE	3788.00	LFT
0017	202-05545	REGULATED MATERIALS, DISPOSE, TYPE C	45.00	CYS
0018	202-05550	REGULATED MATERIALS, REMOVE, TYPE C	45.00	CYS
0019	202-05555	REGULATED MATERIALS, TRANSPORT, TYPE C	45.00	CYS
0020	202-05571	TESTING FOR WASTES, TYPE	3.00	EACH
0021	202-52710	SIDEWALK CONCRETE, REMOVE	2330.00	SYS
0022	203-02000	EXCAVATION, COMMON	1120.00	CYS
0023	203-02070	BORROW	965.00	CYS
0024	205-12108	STORMWATER MANAGEMENT BUDGET	10652.00	DOL
0025	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0026	205-12618	SWQCP PREPARATION	1.00	LS
0027	207-08264	SUBGRADE TREATMENT, TYPE II	648.00	SYS
0028	207-08266	SUBGRADE TREATMENT, TYPE III	1781.00	SYS
0029	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	3.00	CYS
0030	214-11796	GEOGRID, TYPE IB	566.00	SYS
0031	301-12234	COMPACTED AGGREGATE, NO. 53	351.00	CYS

0032	302-07455	DENSE GRADED SUBBASE	110.00	CYS
0033	305-95873	BRICK PAVEMENT, REMOVE AND SALVAGE	189.00	SYS
0034	306-08034	MILLING, ASPHALT, 1 1/2 IN.	242.00	SYS
0035	306-08039	MILLING, ASPHALT REMOVAL	62.00	SYS
0036	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	40.00	TON
0037	401-10258	JOINT ADHESIVE, SURFACE	493.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	493.00	LFT
0039	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0040	502-06627	PCCP, 6 IN.	387.00	SYS
0041	502-11543	PCCP, 4 IN.	2824.00	SYS
0042	506-06333	PCCP PATCHING, FULL DEPTH	252.00	SYS
0043	604-03643	BRICK PAVERS	62.00	SYS
0044	604-06070	SIDEWALK, CONCRETE	1179.00	SYS
0045	604-08086	CURB RAMP, CONCRETE	662.00	SYS
0046	604-12083	DETECTABLE WARNING SURFACES	99.00	SYS
0047	605-06120	CURB, CONCRETE	558.00	LFT
0048	605-06121	CURB, CONCRETE, TYPE B	3102.00	LFT
0049	605-06245	CENTER CURB, B CONCRETE	29.00	SYS
0050	610-08446	PCCP FOR APPROACHES, 6 IN.	78.00	SYS
0051	610-09108	PCCP FOR APPROACHES, 9 IN.	570.00	SYS
0052	611-06497	MAILBOX ASSEMBLY, SINGLE	2.00	EACH
0053	621-06575	SODDING, NURSERY	1499.00	SYS
0054	621-09908	SOIL	59.00	CYS
0055	621-09908	SOIL	1369.00	CYS
0056	622-04648	TREE GRATE	6.00	EACH
0057	622-05652	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 3.5 IN.	39.00	EACH
0058	628-09403	FIELD OFFICE, TYPE C	18.00	MOS
0059	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0060	715-04596	WATER SERVICE	21.00	EACH
0061	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	1172.00	LFT
0062	715-09064	VIDEO INSPECTION FOR PIPE	1229.00	LFT
0063	715-92537	PIPE PVC, 8 IN.	58.00	LFT
0064	715-94530	ADJUST WATER VALVE TO GRADE	4.00	EACH
0065	720-01092	MANHOLE, TYPE J15, MODIFIED	5.00	EACH
0066	720-07309	TRENCH DRAIN	37.00	LFT
0067	720-11721	CASTING TRENCH DRAIN	37.00	LFT
0068	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	11.00	EACH

0069	720-44015	CASTING, TYPE 2, FURNISH AND ADJUST TO GRADE	6.00 EACH
0070	720-44025	CASTING, TYPE 4, FURNISH AND ADJUST TO GRADE	6.00 EACH
0071	720-45275	PIPE CATCH BASIN, 24 IN.	14.00 EACH
0072	720-45410	MANHOLE, TYPE C4	3.00 EACH
0073	720-96999	FIRE HYDRANT ASSEMBLY	4.00 EACH
0074	720-98174	INLET, TYPE B15	11.00 EACH
0075	720-98555	INLET, TYPE C15	7.00 EACH
0076	732-11810	MODULAR BLOCK WALL	551.00 SFT
0077	801-04308	ROAD CLOSURE SIGN ASSEMBLY	15.00 EACH
0078	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	76.00 LFT
0079	801-06625	DETOUR ROUTE MARKER ASSEMBLY	59.00 EACH
0080	801-06640	CONSTRUCTION SIGN, TYPE A	55.00 EACH
0081	801-06645	CONSTRUCTION SIGN, TYPE B	50.00 EACH
0082	801-06775	MAINTAINING TRAFFIC	1.00 LS
0083	801-07118	BARRICADE, TYPE III-A	144.00 LFT
0084	801-07119	BARRICADE, TYPE III-B	108.00 LFT
0085	801-11990	TEMPORARY CURB RAMP	12.00 EACH
0086	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	14.00 SYS
0087	802-04089	SIGN, SHEET, REMOVE	5.00 EACH
0088	802-07060	SIGN, SHEET, RELOCATE	28.00 EACH
0089	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	131.00 SFT
0090	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	239.00 SFT
0091	802-91122	SIGN, GROUND MOUNTED, RESET	4.00 EACH
0092	802-93494	POST, ROUND, GALVANIZED	256.00 LFT
0093	805-01842	HANDHOLE, SIGNAL, TYPE 1	13.00 EACH
0094	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	2684.00 LFT
0095	805-02079	CONTROLLER CABINET FOUNDATION, TYPE A	2.00 EACH
0096	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	8.00 EACH
0097	805-02445	CONTROLLER AND CABINET, TYPE P1	2.00 EACH
0098	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	6.00 EACH
0099	805-04133	SIGNAL POLE, PEDESTAL, 12 FT	4.00 EACH
0100	805-11375	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 25 FT	4.00 EACH
0101	805-11383	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, TYPE A	4.00 EACH
0102	805-11496	PEDESTRIAN HYBRID BEACON	8.00 EACH
0103	805-11799	RECTANGULAR RAPID FLASHING BEACON	2.00 EACH
0104	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	900.00 LFT
0105	805-11817	PEDESTRIAN PUSH BUTTON, APS	6.00 EACH

0106	805-78445	SIGNAL SERVICE	3.00 EACH
0107	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	360.00 LFT
0108	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	630.00 LFT
0109	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	390.00 LFT
0110	807-02191	HANDHOLE, LIGHTING	25.00 EACH
0111	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	1562.00 LFT
0112	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	11.00 SYS
0113	808-06368	TRANSVERSE MARKING, REMOVE	34.00 LFT
0114	808-06716	LINE, REMOVE	1124.00 LFT
0115	808-09314	LINE, PAINT, SOLID, BLUE, 4 IN.	348.00 LFT
0116	808-09450	CROSSWALK, DECORATIVE THERMOPLASTIC	140.00 SFT
0117	808-09968	PAVEMENT MARKING	721.00 SFT
0118	808-11698	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 27 IN.	45.00 LFT
0119	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	200.00 LFT
0120	808-75274	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 8 IN.	271.00 LFT
0121	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	292.00 LFT
0122	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	546.00 LFT
0123	808-97222	PAVEMENT MESSAGE MARKING, PAINT, ADA ACCESSIBLE SYMBOL	2.00 EACH

Call: 160

Contract: R -41852-A

Section No.: 1 ROAD RECONSTRUCTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02271	HEADWALL, REMOVE	1.00	EACH
0013	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00	LS
0014	202-74035	SIGN, REMOVE	19.00	EACH
0015	202-91385	INLET, REMOVE	2.00	EACH
0016	202-96133	PIPE, REMOVE	714.00	LFT
0017	202-99187	FENCE, FARM FIELD, REMOVE	130.00	LFT
0018	203-02000	EXCAVATION, COMMON	38302.00	CYS
0019	203-02070	BORROW	10234.00	CYS
0020	205-12108	STORMWATER MANAGEMENT BUDGET	120900.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	205-12618	SWQCP PREPARATION	1.00	LS
0023	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	510.00	CYS
0024	207-08264	SUBGRADE TREATMENT, TYPE II	272.00	SYS
0025	207-12498	SUBGRADE TREATMENT, TYPE ID	10602.00	SYS
0026	207-12636	SUBGRADE TREATMENT, TYPE IBL	26163.00	SYS
0027	211-02050	B BORROW	1180.00	CYS
0028	211-09264	STRUCTURE BACKFILL, TYPE 1	316.00	CYS
0029	211-09265	STRUCTURE BACKFILL, TYPE 2	103.00	CYS
0030	211-09268	STRUCTURE BACKFILL, TYPE 5	325.00	CYS
0031	214-12237	GEOTEXTILE FOR PAVEMENT, TYPE 1B	27115.00	SYS

0032	217-11917	DRYING SOILS FOR EMBANKMENT	710.00 TON
0033	301-12233	COMPACTED AGGREGATE, NO. 8	18.00 CYS
0034	301-12234	COMPACTED AGGREGATE, NO. 53	3599.00 CYS
0035	303-01180	COMPACTED AGGREGATE, NO. 53	5697.00 TON
0036	303-08210	COMPACTED AGGREGATE, NO. 53, TEMPORARY FOR DRIVEWAYS	5.00 TON
0037	304-07493	WIDENING WITH HMA, TYPE B	27.00 TON
0038	306-08034	MILLING, ASPHALT, 1 1/2 IN.	123.00 SYS
0039	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2712.00 TON
0040	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	4509.00 TON
0041	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	4475.00 TON
0042	401-10258	JOINT ADHESIVE, SURFACE	11982.00 LFT
0043	401-10259	JOINT ADHESIVE, INTERMEDIATE	11982.00 LFT
0044	401-11785	LIQUID ASPHALT SEALANT	11982.00 LFT
0045	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	4068.00 TON
0046	401-12169	INERTIAL PROFILER, HMA	1.00 LS
0047	406-05520	ASPHALT FOR TACK COAT	25.00 TON
0048	601-05999	CURVED TERMINAL END	6.00 EACH
0049	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	75.00 LFT
0050	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	19086.00 LFT
0051	610-07487	HMA FOR APPROACHES, TYPE B	88.00 TON
0052	611-06497	MAILBOX ASSEMBLY, SINGLE	3.00 EACH
0053	615-06490	RIGHT-OF-WAY MARKER	115.00 EACH
0054	615-06505	MONUMENT, TYPE B	12.00 EACH
0055	615-06527	MONUMENT, SECTION CORNER	3.00 EACH
0056	616-06405	RIPRAP, REVETMENT	88.00 TON
0057	616-06451	RIPRAP, UNIFORM	1226.00 TON
0058	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	2542.00 SYS
0059	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	112.00 SYS
0060	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00 EACH
0061	621-06545	FERTILIZER	8.00 TON
0062	621-06553	SEED MIXTURE, TYPE R	3038.00 LBS
0063	621-06565	MULCHING MATERIAL	30.00 TON
0064	621-06567	WATER	12.00 KGAL
0065	621-06574	SODDING	2477.00 SYS
0066	621-06575	SODDING, NURSERY	710.00 SYS
0067	628-09403	FIELD OFFICE, TYPE C	10.00 MOS
0068	629-12029	PLANT GROWTH LAYER	69952.00 SYS

0069	702-51005	CONCRETE, A, SUBSTRUCTURE	63.40	CYS
0070	703-06028	REINFORCING BARS	3804.00	LBS
0071	714-11186	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 12 FT X 4 FT	84.00	LFT
0072	715-02397	SAFETY METAL END SECTION, 4:1, DIAMETER 36 IN.	2.00	EACH
0073	715-02628	SAFETY METAL END SECTION, 6:1, DIAMETER 15 IN.	20.00	EACH
0074	715-04612	PIPE	2.00	LFT
0075	715-05019	PIPE, TYPE 1, CIRCULAR, DIAMETER 36 IN.	61.00	LFT
0076	715-05024	PIPE, TYPE 2, CIRCULAR, DIAMETER 36 IN.	119.00	LFT
0077	715-05032	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	312.00	LFT
0078	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	12290.00	LFT
0079	715-05049	PIPE, TYPE 4, CIRCULAR, DIAMETER 8 IN.	148.00	LFT
0080	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	1266.00	LFT
0081	715-05119	PIPE, TYPE 1, CIRCULAR, DIAMETER 15 IN.	108.00	LFT
0082	715-05147	PIPE, TYPE 2, CIRCULAR, DIAMETER 8 IN.	14.00	LFT
0083	715-05168	PIPE, TYPE 3, CIRCULAR, DIAMETER 12 IN.	134.00	LFT
0084	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	632.00	LFT
0085	715-09064	VIDEO INSPECTION FOR PIPE	131.00	LFT
0086	715-46000	PIPE END SECTION, DIAMETER 12 IN.	8.00	EACH
0087	718-06528	OUTLET PROTECTOR, TYPE 1	27.00	EACH
0088	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	3000.00	LFT
0089	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	8856.00	SYS
0090	718-52610	AGGREGATE FOR UNDERDRAINS	1104.00	CYS
0091	719-05440	PIPE, DRAIN TILE TERMINAL SECTION, DIAMETER 8 IN.	50.00	LFT
0092	720-08239	MANHOLE, TYPE J7, MODIFIED	2.00	EACH
0093	720-45066	INLET, TYPE N12, MODIFIED	1.00	EACH
0094	720-45130	INLET, TYPE E7, MODIFIED	2.00	EACH
0095	720-45135	INLET, TYPE F7, MODIFIED	4.00	EACH
0096	720-45410	MANHOLE, TYPE C4	2.00	EACH
0097	721-43000	AUTOMATIC DRAINAGE GATE, DIAMETER 12 IN.	2.00	EACH
0098	721-43005	AUTOMATIC DRAINAGE GATE, DIAMETER 15 IN.	4.00	EACH
0099	801-04308	ROAD CLOSURE SIGN ASSEMBLY	22.00	EACH
0100	801-06625	DETOUR ROUTE MARKER ASSEMBLY	72.00	EACH
0101	801-06640	CONSTRUCTION SIGN, TYPE A	46.00	EACH
0102	801-06645	CONSTRUCTION SIGN, TYPE B	15.00	EACH
0103	801-06775	MAINTAINING TRAFFIC	1.00	LS
0104	801-07119	BARRICADE, TYPE III-B	830.00	LFT
0105	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	446.00	LFT

0106	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	48.00	LFT
0107	802-07060	SIGN, SHEET, RELOCATE	2.00	EACH
0108	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	213.00	SFT
0109	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	61.00	SFT
0110	804-06770	DELINEATOR POST	28.00	EACH
0111	805-11965	SOLAR POWERED FLASHING LED SIGN ASSEMBLY	4.00	EACH
0112	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0113	808-12032	GROOVING FOR PAVEMENT MARKINGS	19425.00	LFT
0114	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	16580.00	LFT
0115	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	9055.00	LFT
0116	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	80.00	LFT
0117	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	184.00	LFT
0118	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	2.00	EACH
0119	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	1.00	EACH
0120	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	4875.00	LFT

Call: 170

Contract: R -41927-A

Section No.: 1 SIGNS, LIGHTING, SIGNALS, AND MARKINGS

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	8536.00	SYS
0014	202-02278	CURB, CONCRETE, REMOVE	2245.00	LFT
0015	202-02279	CURB AND GUTTER, REMOVE	4745.00	LFT
0016	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0017	202-52710	SIDEWALK CONCRETE, REMOVE	3228.00	SYS
0018	202-74080	OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	3.00	EACH
0019	202-99626	FOUNDATION FOR SIGNING, REMOVE	3.00	EACH
0020	203-02000	EXCAVATION, COMMON	17885.00	CYS
0021	203-02070	BORROW	905.00	CYS
0022	205-11626	PUMP AROUND	1.00	EACH
0023	205-12108	STORMWATER MANAGEMENT BUDGET	72400.00	DOL
0024	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0025	205-12618	SWQCP PREPARATION	1.00	LS
0026	207-08264	SUBGRADE TREATMENT, TYPE II	3543.00	SYS
0027	207-09935	SUBGRADE TREATMENT, TYPE IC	30589.00	SYS
0028	211-09265	STRUCTURE BACKFILL, TYPE 2	3993.00	CYS
0029	211-09268	STRUCTURE BACKFILL, TYPE 5	4036.00	CYS
0030	214-11796	GEOGRID, TYPE IB	3075.00	SYS
0031	214-12238	GEOTEXTILE FOR PAVEMENT, TYPE 2A	4337.00	SYS

0032	301-12232	COMPACTED AGGREGATE, NO. 5	2266.00	CYS
0033	301-12234	COMPACTED AGGREGATE, NO. 53	3878.00	CYS
0034	302-07455	DENSE GRADED SUBBASE	461.00	CYS
0035	303-08210	COMPACTED AGGREGATE, NO. 53, TEMPORARY FOR DRIVEWAYS	395.00	TON
0036	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	547.00	TON
0037	306-08034	MILLING, ASPHALT, 1 1/2 IN.	11602.00	SYS
0038	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	2679.00	TON
0039	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	3469.00	TON
0040	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	10223.00	TON
0041	401-10258	JOINT ADHESIVE, SURFACE	22057.00	LFT
0042	401-10259	JOINT ADHESIVE, INTERMEDIATE	21369.00	LFT
0043	401-11785	LIQUID ASPHALT SEALANT	22057.00	LFT
0044	406-05520	ASPHALT FOR TACK COAT	19.80	TON
0045	502-11543	PCCP, 4 IN.	14.00	SYS
0046	601-06234	IMPACT ATTENUATOR, R1-W1, TL-2	1.00	EACH
0047	603-06045	FENCE, CHAIN LINK, 48 IN.	296.00	LFT
0048	604-06070	SIDEWALK, CONCRETE	5261.00	SYS
0049	604-08086	CURB RAMP, CONCRETE	1351.00	SYS
0050	604-12083	DETECTABLE WARNING SURFACES	155.00	SYS
0051	605-06120	CURB, CONCRETE	1197.00	LFT
0052	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	8461.00	LFT
0053	605-06255	CENTER CURB, D CONCRETE	28.00	SYS
0054	605-97937	CURB AND GUTTER, ROLL CURB	353.00	LFT
0055	610-08446	PCCP FOR APPROACHES, 6 IN.	597.00	SYS
0056	610-09108	PCCP FOR APPROACHES, 9 IN.	2054.00	SYS
0057	611-06497	MAILBOX ASSEMBLY, SINGLE	4.00	EACH
0058	611-06498	MAILBOX ASSEMBLY, DOUBLE	2.00	EACH
0059	615-06490	RIGHT-OF-WAY MARKER	18.00	EACH
0060	615-06505	MONUMENT, TYPE B	16.00	EACH
0061	616-03096	RIVER ROCK	25.00	TON
0062	616-06405	RIPRAP, REVETMENT	153.00	TON
0063	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	153.00	SYS
0064	621-06567	WATER	23.50	KGAL
0065	621-06575	SODDING, NURSERY	9221.00	SYS
0066	622-05648	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER	12.00	EACH
0067	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0068	628-12683	FIELD OFFICE, TYPE D	30.00	MOS

0069	706-11404	RAILING, STEEL TYPE PF-1	14.00	LFT
0070	714-11145	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 12 FT X 7 FT	282.00	LFT
0071	715-05024	PIPE, TYPE 2, CIRCULAR, DIAMETER 36 IN.	2793.00	LFT
0072	715-05147	PIPE, TYPE 2, CIRCULAR, DIAMETER 8 IN.	36.00	LFT
0073	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	4624.00	LFT
0074	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	786.00	LFT
0075	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	498.00	LFT
0076	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	612.00	LFT
0077	715-05156	PIPE, TYPE 2, CIRCULAR, DIAMETER 30 IN.	2406.00	LFT
0078	715-05159	PIPE, TYPE 2, CIRCULAR, DIAMETER 42 IN.	291.00	LFT
0079	715-05161	PIPE, TYPE 2, CIRCULAR, DIAMETER 48 IN.	564.00	LFT
0080	715-05417	PIPE, SANITARY SEWER, DIAMETER 30 IN.	59.00	LFT
0081	715-06561	PIPE EXTENSION, CIRCULAR, DIAMETER 4 IN.	40.00	LFT
0082	715-06566	PIPE EXTENSION, CIRCULAR, DIAMETER 6 IN.	40.00	LFT
0083	715-09843	BYPASS PUMPING	1.00	LS
0084	715-26728	GRATED BOX END SECTION, TYPE II, 4:1, DIAMETER 12 IN.	2.00	EACH
0085	715-46040	PIPE END SECTION, DIAMETER 36 IN.	1.00	EACH
0086	720-02810	INLET, TYPE B5	7.00	EACH
0087	720-04467	INLET, TYPE C5	5.00	EACH
0088	720-45045	INLET, TYPE J10	2.00	EACH
0089	720-45075	INLET, TYPE R13	3.00	EACH
0090	720-45130	INLET, TYPE E7, MODIFIED	1.00	EACH
0091	720-45135	INLET, TYPE F7, MODIFIED	1.00	EACH
0092	720-45410	MANHOLE, TYPE C4	3.00	EACH
0093	720-45510	MANHOLE, TYPE C4, MODIFIED	3.00	EACH
0094	720-91110	MANHOLE, TYPE N4	4.00	EACH
0095	720-92884	MANHOLE, TYPE K4, MODIFIED	7.00	EACH
0096	720-93501	MANHOLE, TYPE L4	4.00	EACH
0097	720-94612	MANHOLE, TYPE K4	7.00	EACH
0098	720-95409	MANHOLE, TYPE J4, MODIFIED	13.00	EACH
0099	720-95422	MANHOLE, TYPE J4	5.00	EACH
0100	720-98174	INLET, TYPE B15	59.00	EACH
0101	720-98555	INLET, TYPE C15	80.00	EACH
0102	720-98869	MANHOLE, TYPE L4, MODIFIED	2.00	EACH
0103	801-01506	TEMPORARY PAVEMENT MESSAGE MARKING, (R X R)	1.00	EACH
0104	801-03291	CONSTRUCTION SIGN, TYPE D	4.00	EACH
0105	801-04308	ROAD CLOSURE SIGN ASSEMBLY	27.00	EACH

0106	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	6206.00	LFT
0107	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2923.00	LFT
0108	801-06213	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (RXR)	1.00	EACH
0109	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	198.00	LFT
0110	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	170.00	LFT
0111	801-06625	DETOUR ROUTE MARKER ASSEMBLY	56.00	EACH
0112	801-06640	CONSTRUCTION SIGN, TYPE A	59.00	EACH
0113	801-06645	CONSTRUCTION SIGN, TYPE B	83.00	EACH
0114	801-06775	MAINTAINING TRAFFIC	1.00	LS
0115	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	1.00	EACH
0116	801-07118	BARRICADE, TYPE III-A	231.00	LFT
0117	801-07119	BARRICADE, TYPE III-B	486.00	LFT
0118	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	300.00	LFT
0119	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	170.00	LFT
0120	801-11990	TEMPORARY CURB RAMP	3.00	EACH
0121	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	214.00	SYS
0122	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	564.00	LFT
0123	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	757.00	LFT
0124	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	369.00	SFT
0125	802-09839	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	58.00	SFT
0126	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	76.00	SFT
0127	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	34.00	SFT
0128	802-11648	SIGN POST, TYPE	8.00	EACH
0129	802-76100	OVERHEAD SIGN STRUCTURE, MONOTUBE	2.00	EACH
0130	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	3.00	EACH
0131	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	28.00	EACH
0132	805-02445	CONTROLLER AND CABINET, TYPE P1	3.00	EACH
0133	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	13.00	EACH
0134	805-04133	SIGNAL POLE, PEDESTAL, 12 FT	13.00	EACH
0135	805-04782	VIDEO VEHICLE DETECTOR SYSTEM	3.00	EACH
0136	805-07245	ETHERNET	3.00	EACH
0137	805-08244	CELLULAR MODEM KIT	3.00	EACH
0138	805-11383	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, TYPE A	3.00	EACH
0139	805-11384	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, TYPE B	9.00	EACH
0140	805-11744	HANDHOLE, SIGNAL, TYPE 2	22.00	EACH
0141	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	2126.00	LFT
0142	805-11817	PEDESTRIAN PUSH BUTTON, APS	27.00	EACH

0143	805-12958	SIGNAL SUPPORT, ORNAMENTAL	1.00 EACH
0144	805-12958	SIGNAL SUPPORT, ORNAMENTAL	1.00 EACH
0145	805-12958	SIGNAL SUPPORT, ORNAMENTAL	1.00 EACH
0146	805-12958	SIGNAL SUPPORT, ORNAMENTAL	1.00 EACH
0147	805-12958	SIGNAL SUPPORT, ORNAMENTAL	3.00 EACH
0148	805-12958	SIGNAL SUPPORT, ORNAMENTAL	2.00 EACH
0149	805-12958	SIGNAL SUPPORT, ORNAMENTAL	3.00 EACH
0150	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	25.00 EACH
0151	805-78225	TRAFFIC SIGNAL HEAD, NO. 4 SECTION, 12 IN.	4.00 EACH
0152	805-78445	SIGNAL SERVICE	3.00 EACH
0153	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	68.00 LFT
0154	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GAUGE	2793.00 LFT
0155	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	5758.00 LFT
0156	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	1645.00 LFT
0157	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	694.00 LFT
0158	805-78925	CONTROLLER CABINET FOUNDATION, TYPE P1	3.00 EACH
0159	807-02191	HANDHOLE, LIGHTING	11.00 EACH
0160	807-02783	LUMINAIRE, MAST ARM, 15 FT	2.00 EACH
0161	807-03758	LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING, 24 IN. X 24 IN. X 96 IN.	27.00 EACH
0162	807-03950	LUMINAIRE, ORNAMENTAL	27.00 EACH
0163	807-03951	LIGHT POLE, ORNAMENTAL	27.00 EACH
0164	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	461.00 LFT
0165	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	2494.00 LFT
0166	807-11593	CABLE, POLE CIRCUIT, XHHW, NO. 6 COPPER, STRANDED, 2 1/C	810.00 LFT
0167	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	2.00 EACH
0168	807-86805	SERVICE POINT, TYPE I	1.00 EACH
0169	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	2430.00 LFT
0170	807-86910	CONNECTOR KIT, UNFUSED	27.00 EACH
0171	807-86915	CONNECTOR KIT, FUSED	27.00 EACH
0172	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	83.00 EACH
0173	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	4.00 EACH
0174	807-86930	INSULATION LINK, NON-WATERPROOFED	83.00 EACH
0175	807-86935	INSULATION LINK, WATERPROOFED	15.00 EACH
0176	807-95889	WIRE, NO. 10 COPPER, 1/C	912.00 LFT
0177	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	461.00 LFT
0178	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	1708.00 LFT
0179	808-05929	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 8 IN.	2363.00 LFT

0180	808-06540	TRANSVERSE MARKING, PREFORMED PLASTIC, CROSSWALK LINE, WHITE, 12 IN.	890.00	LFT
0181	808-06716	LINE, REMOVE	690.00	LFT
0182	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0183	808-09450	CROSSWALK, DECORATIVE THERMOPLASTIC	3662.00	SFT
0184	808-11650	LINE, THERMOPLASTIC, DOTTED, WHITE, 6 IN.	51.00	LFT
0185	808-12273	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, WHITE, 4 IN.	2184.00	LFT
0186	808-12274	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, BLUE 4 IN.	230.00	LFT
0187	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	1310.00	LFT
0188	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	12236.00	LFT
0189	808-75256	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 8 IN.	703.00	LFT
0190	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	27.00	LFT
0191	808-75274	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 8 IN.	283.00	LFT
0192	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	137.00	LFT
0193	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	749.00	LFT
0194	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	49.00	EACH
0195	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	11.00	EACH
0196	808-75340	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, RXR	1.00	EACH
0197	808-94435	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, STOP	2.00	EACH
0198	808-95933	CURB, PAINTING, YELLOW	939.00	LFT
0199	808-96075	LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN.	127.00	LFT
0200	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	576.00	LFT
0201	808-97664	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ADA ACCESSIBLE SYMBOL	6.00	EACH

Call: 180

Contract: R -41989-A

Section No.: 1 ROAD REHABILITATION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT-OF-WAY	1.00 LS
0013	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00 LS
0014	203-02000	EXCAVATION, COMMON	15067.00 CYS
0015	203-02070	BORROW	1200.00 CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	65000.00 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	205-12618	SWQCP PREPARATION	1.00 LS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	10827.00 SYS
0020	207-08266	SUBGRADE TREATMENT, TYPE III	5295.00 SYS
0021	207-08268	SUBGRADE TREATMENT, TYPE IV	1013.00 SYS
0022	207-12635	SUBGRADE TREATMENT, TYPE IBC	31117.00 SYS
0023	211-02050	B BORROW	82.00 CYS
0024	211-09264	STRUCTURE BACKFILL, TYPE 1	1174.00 CYS
0025	214-11796	GEOGRID, TYPE IB	2260.00 SYS
0026	217-11917	DRYING SOILS FOR EMBANKMENT	340.00 TON
0027	301-12234	COMPACTED AGGREGATE, NO. 53	598.00 CYS
0028	302-07455	DENSE GRADED SUBBASE	213.00 CYS
0029	303-01180	COMPACTED AGGREGATE, NO. 53	5847.00 TON
0030	303-08210	COMPACTED AGGREGATE, NO. 53, TEMPORARY FOR DRIVEWAYS	200.00 TON
0031	304-07493	WIDENING WITH HMA, TYPE B	3231.00 TON

0032	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	306.00 TON
0033	306-11872	MILLING, PROFILE	18506.00 SYS
0034	401-07384	QC/QA-HMA, 2, 76, INTERMEDIATE, 12.5 mm	3711.00 TON
0035	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	863.00 TON
0036	401-10258	JOINT ADHESIVE, SURFACE	9767.00 LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	9767.00 LFT
0038	401-11785	LIQUID ASPHALT SEALANT	9767.00 LFT
0039	402-07452	HMA WEDGE AND LEVEL, TYPE C	180.00 TON
0040	402-10086	HMA FOR TEMPORARY PAVEMENT, TYPE C	193.00 TON
0041	406-05520	ASPHALT FOR TACK COAT	21.00 TON
0042	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	3.00 TON
0043	410-10128	QC/QA-HMA, 3, 76, SURFACE, 9.5 mm - SMA	4818.00 TON
0044	502-11564	PCCP, 7 IN.	245.00 SYS
0045	503-05240	D-1 CONTRACTION JOINT	135.00 LFT
0046	603-91714	FENCE RAIL, WOOD	135.00 LFT
0047	604-05528	HMA FOR SIDEWALK	1343.00 TON
0048	604-08086	CURB RAMP, CONCRETE	210.00 SYS
0049	604-12083	DETECTABLE WARNING SURFACES	44.00 SYS
0050	605-06125	CURB, CONCRETE, MODIFIED	199.00 LFT
0051	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	1786.00 LFT
0052	605-06160	CURB AND GUTTER, TYPE B, CONCRETE, MODIFIED	264.00 LFT
0053	605-06245	CENTER CURB, B CONCRETE	255.00 SYS
0054	610-07487	HMA FOR APPROACHES, TYPE B	1657.00 TON
0055	610-08446	PCCP FOR APPROACHES, 6 IN.	1273.00 SYS
0056	611-06497	MAILBOX ASSEMBLY, SINGLE	40.00 EACH
0057	615-06490	RIGHT-OF-WAY MARKER	32.00 EACH
0058	615-06527	MONUMENT, SECTION CORNER	2.00 EACH
0059	616-06405	RIPRAP, REVETMENT	85.00 TON
0060	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	156.00 SYS
0061	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.00 EACH
0062	621-02770	EROSION CONTROL BLANKET	492.00 SYS
0063	621-06545	FERTILIZER	4.00 TON
0064	621-06553	SEED MIXTURE, TYPE R	1600.00 LBS
0065	621-06565	MULCHING MATERIAL	19.00 TON
0066	628-09403	FIELD OFFICE, TYPE C	24.00 MOS
0067	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0068	715-05024	PIPE, TYPE 2, CIRCULAR, DIAMETER 36 IN.	983.00 LFT

0069	715-05119	PIPE, TYPE 1, CIRCULAR, DIAMETER 15 IN.	120.00	LFT
0070	715-05121	PIPE, TYPE 1, CIRCULAR, DIAMETER 18 IN.	67.00	LFT
0071	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	335.00	LFT
0072	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	16.00	LFT
0073	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	299.00	LFT
0074	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	97.00	LFT
0075	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	203.00	LFT
0076	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	203.00	LFT
0077	715-05156	PIPE, TYPE 2, CIRCULAR, DIAMETER 30 IN.	3.00	LFT
0078	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	111.00	LFT
0079	715-05171	PIPE, TYPE 3, CIRCULAR, DIAMETER 18 IN.	1303.00	LFT
0080	715-05331	PIPE, TYPE 2, DEFORMED, MIN. AREA 3.3 SFT	52.00	LFT
0081	715-06471	PIPE END SECTION, MIN. AREA 3.3 SFT	3.00	EACH
0082	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	59.00	TON
0083	715-09064	VIDEO INSPECTION FOR PIPE	3824.00	LFT
0084	715-46000	PIPE END SECTION, DIAMETER 12 IN.	6.00	EACH
0085	715-46005	PIPE END SECTION, DIAMETER 15 IN.	66.00	EACH
0086	715-46010	PIPE END SECTION, DIAMETER 18 IN.	4.00	EACH
0087	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00	EACH
0088	715-46040	PIPE END SECTION, DIAMETER 36 IN.	3.00	EACH
0089	720-02367	MANHOLE, TYPE J10	1.00	EACH
0090	720-02367	MANHOLE, TYPE J10	1.00	EACH
0091	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	1.00	EACH
0092	720-45030	INLET, TYPE E7	5.00	EACH
0093	720-45030	INLET, TYPE E7	2.00	EACH
0094	720-45045	INLET, TYPE J10	5.00	EACH
0095	720-45055	INLET, TYPE M10	2.00	EACH
0096	720-45375	PIPE CATCH BASIN, 24 IN., MODIFIED	2.00	EACH
0097	720-45410	MANHOLE, TYPE C4	1.00	EACH
0098	720-45410	MANHOLE, TYPE C4	3.00	EACH
0099	720-45605	STRUCTURE, MANHOLE, RECONSTRUCTED	2.00	LFT
0100	720-90129	MANHOLE, TYPE J2	2.00	EACH
0101	720-90984	MANHOLE, TYPE C2	2.00	EACH
0102	720-91973	MANHOLE, TYPE H4	3.00	EACH
0103	720-94208	MANHOLE, TYPE C10	1.00	EACH
0104	720-94612	MANHOLE, TYPE K4	2.00	EACH
0105	720-95422	MANHOLE, TYPE J4	4.00	EACH

0106	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00 EACH
0107	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	12855.00 LFT
0108	801-06625	DETOUR ROUTE MARKER ASSEMBLY	47.00 EACH
0109	801-06640	CONSTRUCTION SIGN, TYPE A	39.00 EACH
0110	801-06645	CONSTRUCTION SIGN, TYPE B	48.00 EACH
0111	801-06775	MAINTAINING TRAFFIC	1.00 LS
0112	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	4.00 EACH
0113	801-07118	BARRICADE, TYPE III-A	60.00 LFT
0114	801-07119	BARRICADE, TYPE III-B	108.00 LFT
0115	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	620.00 LFT
0116	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00 EACH
0117	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	877.00 LFT
0118	802-09837	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	13.00 SFT
0119	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	427.00 SFT
0120	802-09839	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	11.00 SFT
0121	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	78.00 SFT
0122	805-06600	CONDUIT, PVC, 3 IN.	20.00 LFT
0123	807-02191	HANDHOLE, LIGHTING	2.00 EACH
0124	807-04654	LIGHT POLE	12.00 EACH
0125	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	145.00 LFT
0126	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1221.00 LFT
0127	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	12.00 EACH
0128	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE, WITH GROUNDING	12.00 EACH
0129	807-86805	SERVICE POINT, TYPE I	1.00 EACH
0130	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	1080.00 LFT
0131	807-86910	CONNECTOR KIT, UNFUSED	12.00 EACH
0132	807-86915	CONNECTOR KIT, FUSED	12.00 EACH
0133	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	27.00 EACH
0134	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	12.00 EACH
0135	807-86930	INSULATION LINK, NON-WATERPROOFED	37.00 EACH
0136	807-86935	INSULATION LINK, WATERPROOFED	16.00 EACH
0137	808-02977	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	27.00 EACH
0138	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	192.00 LFT
0139	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	31870.00 LFT
0140	808-06716	LINE, REMOVE	5250.00 LFT
0141	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0142	808-10118	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 24 IN.	60.00 LFT

0143	808-11478	LINE, THERMOPLASTIC, DOTTED, WHITE, 8 IN.	27.00	LFT
0144	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	260.00	LFT
0145	808-12032	GROOVING FOR PAVEMENT MARKINGS	48833.00	LFT
0146	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1136.00	LFT
0147	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1540.00	LFT
0148	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	239.00	LFT
0149	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	615.00	LFT
0150	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	57.00	EACH
0151	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	126.00	EACH

Call: 200

Contract: R -42199-A

Section No.: 1 SLIDE CORRECTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	15.00	SYS
0013	202-02272	PAVED SIDE DITCH, REMOVE	317.00	LFT
0014	202-91385	INLET, REMOVE	1.00	EACH
0015	202-96133	PIPE, REMOVE	222.00	LFT
0016	203-02000	EXCAVATION, COMMON	2388.00	CYS
0017	203-02020	EXCAVATION, UNCLASSIFIED	9622.00	CYS
0018	203-02588	LAGGING, PRECAST CONCRETE	1337.00	SYS
0019	203-02590	PIER, DRILL IN BEDROCK SOCKET	1176.00	LFT
0020	203-02592	PIER, NONFORMED, DRILL ABOVE BEDROCK SOCKET	3628.00	LFT
0021	205-11626	PUMP AROUND	1.00	EACH
0022	205-12108	STORMWATER MANAGEMENT BUDGET	78403.25	DOL
0023	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0024	205-12618	SWQCP PREPARATION	1.00	LS
0025	207-09935	SUBGRADE TREATMENT, TYPE IC	1520.00	SYS
0026	211-09264	STRUCTURE BACKFILL, TYPE 1	55.00	CYS
0027	211-09265	STRUCTURE BACKFILL, TYPE 2	693.00	CYS
0028	211-09266	STRUCTURE BACKFILL, TYPE 3	2843.00	CYS
0029	214-07202	GEOGRID, TYPE IA	486.00	SYS
0030	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	758.00	SYS
0031	301-12233	COMPACTED AGGREGATE, NO. 8	21.00	CYS

0032	301-12234	COMPACTED AGGREGATE, NO. 53	101.00	CYS
0033	303-01180	COMPACTED AGGREGATE, NO. 53	671.00	TON
0034	304-07493	WIDENING WITH HMA, TYPE B	23.00	TON
0035	306-08034	MILLING, ASPHALT, 1 1/2 IN.	3634.00	SYS
0036	306-08043	MILLING, TRANSITION	1046.00	SYS
0037	306-10163	MILLING, ASPHALT, 2 1/2 IN.	232.00	SYS
0038	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	518.00	TON
0039	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	78.00	TON
0040	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	518.00	TON
0041	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	355.00	TON
0042	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	55.00	TON
0043	401-10258	JOINT ADHESIVE, SURFACE	2926.00	LFT
0044	401-10259	JOINT ADHESIVE, INTERMEDIATE	1299.00	LFT
0045	401-11785	LIQUID ASPHALT SEALANT	2926.00	LFT
0046	404-05514	SEAL COAT, TYPE 5	510.00	SYS
0047	406-05520	ASPHALT FOR TACK COAT	6.00	TON
0048	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	0.10	TON
0049	601-06035	GUARDRAIL, RESET	75.00	LFT
0050	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	225.00	LFT
0051	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00	EACH
0052	610-07487	HMA FOR APPROACHES, TYPE B	3.00	TON
0053	615-06490	RIGHT-OF-WAY MARKER	13.00	EACH
0054	615-06505	MONUMENT, TYPE B	4.00	EACH
0055	616-05688	RIPRAP, CLASS 1	11052.00	TON
0056	616-05689	RIPRAP, CLASS 2	3104.00	TON
0057	616-06405	RIPRAP, REVETMENT	6493.00	TON
0058	616-06451	RIPRAP, UNIFORM	684.00	TON
0059	616-09395	GEOMEMBRANE	825.00	SYS
0060	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	1593.00	SYS
0061	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	15333.00	SYS
0062	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	7.00	EACH
0063	621-02770	EROSION CONTROL BLANKET	1493.00	SYS
0064	621-06545	FERTILIZER	3.12	TON
0065	621-06553	SEED MIXTURE, TYPE R	698.00	LBS
0066	621-06559	MULCHED SEEDING, TYPE R	2739.00	SYS
0067	621-06565	MULCHING MATERIAL	9.20	TON
0068	621-06574	SODDING	1086.00	SYS

0069	628-09403	FIELD OFFICE, TYPE C	24.00	MOS
0070	702-51005	CONCRETE, A, SUBSTRUCTURE	1.20	CYS
0071	702-51015	CONCRETE, B, FOOTINGS	83.00	CYS
0072	702-90915	CONCRETE, A	52.00	CYS
0073	703-06028	REINFORCING BARS	8640.00	LBS
0074	711-51038	STRUCTURAL STEEL	1.00	LS
0075	715-01471	PIPE END SECTION, PRECAST CONCRETE, DIAMETER 15 IN.	1.00	EACH
0076	715-03475	SAFETY METAL END SECTION, 4:1, DIAMETER 15 IN.	2.00	EACH
0077	715-05032	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	59.00	LFT
0078	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	250.00	LFT
0079	715-05052	PIPE, TYPE 4, CIRCULAR, DIAMETER 12 IN.	1023.00	LFT
0080	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	10.00	LFT
0081	715-05127	PIPE, TYPE 1, CIRCULAR, DIAMETER 42 IN.	156.00	LFT
0082	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	23.00	LFT
0083	715-05842	CONCRETE ANCHOR, DIAMETER 42 IN.	2.00	EACH
0084	715-06566	PIPE EXTENSION, CIRCULAR, DIAMETER 6 IN.	15.00	LFT
0085	715-06566	PIPE EXTENSION, CIRCULAR, DIAMETER 6 IN.	26.00	LFT
0086	715-12872	GEOTEXTILE FOR PIPE TYPE 2B	5.00	SYS
0087	716-09396	PIPE INSTALLATION, TRENCHLESS, 2 IN.	2350.00	LFT
0088	718-06529	OUTLET PROTECTOR, TYPE 2	2.00	EACH
0089	718-12308	GEOTEXTILE FOR UNDERDRAINS, TYPE 2B	195.00	SYS
0090	718-52610	AGGREGATE FOR UNDERDRAINS	22.00	CYS
0091	720-45030	INLET, TYPE E7	1.00	EACH
0092	801-03290	CONSTRUCTION SIGN, TYPE C	2.00	EACH
0093	801-04308	ROAD CLOSURE SIGN ASSEMBLY	14.00	EACH
0094	801-06625	DETOUR ROUTE MARKER ASSEMBLY	97.00	EACH
0095	801-06640	CONSTRUCTION SIGN, TYPE A	59.00	EACH
0096	801-06645	CONSTRUCTION SIGN, TYPE B	12.00	EACH
0097	801-06775	MAINTAINING TRAFFIC	1.00	LS
0098	801-07118	BARRICADE, TYPE III-A	84.00	LFT
0099	801-07119	BARRICADE, TYPE III-B	168.00	LFT
0100	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0101	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	10.00	LFT
0102	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	2155.00	LFT
0103	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	2124.00	LFT
0104	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1.00	EACH
0105	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1.00	EACH

Call: 210

Contract: R -42200-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0013	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0014	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0015	203-02000	EXCAVATION, COMMON	8380.00	CYS
0016	203-02070	BORROW	1390.00	CYS
0017	205-12108	STORMWATER MANAGEMENT BUDGET	13300.00	DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0019	205-12618	SWQCP PREPARATION	1.00	LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	469.00	SYS
0021	207-12635	SUBGRADE TREATMENT, TYPE IBC	16316.00	SYS
0022	211-02050	B BORROW	1035.00	CYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	799.00	CYS
0024	301-12234	COMPACTED AGGREGATE, NO. 53	2475.00	CYS
0025	302-07455	DENSE GRADED SUBBASE	383.00	CYS
0026	303-01180	COMPACTED AGGREGATE, NO. 53	520.00	TON
0027	304-07494	WIDENING WITH HMA, TYPE C	29.00	TON
0028	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1275.00	TON
0029	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	2098.00	TON
0030	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	2996.00	TON
0031	401-10258	JOINT ADHESIVE, SURFACE	9658.00	LFT

0032	401-10259	JOINT ADHESIVE, INTERMEDIATE	9658.00	LFT
0033	401-11785	LIQUID ASPHALT SEALANT	9658.00	LFT
0034	406-05520	ASPHALT FOR TACK COAT	16.00	TON
0035	502-06457	PCCP, 9 IN.	416.00	SYS
0036	502-06627	PCCP, 6 IN.	927.00	SYS
0037	503-05240	D-1 CONTRACTION JOINT	240.00	LFT
0038	603-11002	FENCE GATE, CHAIN LINK, 72 IN. X 24 FT	1.00	EACH
0039	603-92636	FENCE, CHAIN LINK, 72 IN.	455.00	LFT
0040	605-06125	CURB, CONCRETE, MODIFIED	271.00	LFT
0041	605-06145	CURB AND GUTTER, TYPE B, CONCRETE	364.00	LFT
0042	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	4403.00	LFT
0043	610-08446	PCCP FOR APPROACHES, 6 IN.	376.00	SYS
0044	611-06497	MAILBOX ASSEMBLY, SINGLE	3.00	EACH
0045	615-06490	RIGHT-OF-WAY MARKER	26.00	EACH
0046	615-06505	MONUMENT, TYPE B	14.00	EACH
0047	615-06510	MONUMENT, TYPE C	3.00	EACH
0048	615-06515	MONUMENT, TYPE D	12.00	EACH
0049	615-06527	MONUMENT, SECTION CORNER	1.00	EACH
0050	616-06405	RIPRAP, REVETMENT	74.00	TON
0051	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	144.00	SYS
0052	616-51367	SLOPEWALL, CONCRETE, 4 IN.	278.00	SYS
0053	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0054	621-06545	FERTILIZER	1.00	TON
0055	621-06559	MULCHED SEEDING, TYPE R	15809.00	SYS
0056	621-06570	TOPSOIL	202.00	CYS
0057	621-08538	MULCH	51.00	CYS
0058	622-05639	PLANT, DECIDUOUS SHRUB, 18 IN. TO 24 IN.	70.00	EACH
0059	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. TO 2 IN.	50.00	EACH
0060	622-05653	PLANT, GROUND COVER	193.00	EACH
0061	622-05654	PLANT, PERENNIAL	112.00	EACH
0062	628-09403	FIELD OFFICE, TYPE C	24.00	MOS
0063	715-05119	PIPE, TYPE 1, CIRCULAR, DIAMETER 15 IN.	75.00	LFT
0064	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	1515.00	LFT
0065	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	434.00	LFT
0066	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	682.00	LFT
0067	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	229.00	LFT
0068	715-05173	PIPE, TYPE 3, CIRCULAR, DIAMETER 24 IN.	201.00	LFT

0069	720-01092	MANHOLE, TYPE J15, MODIFIED	3.00 EACH
0070	720-45075	INLET, TYPE R13	3.00 EACH
0071	720-90984	MANHOLE, TYPE C2	1.00 EACH
0072	720-98174	INLET, TYPE B15	18.00 EACH
0073	720-98555	INLET, TYPE C15	18.00 EACH
0074	801-04308	ROAD CLOSURE SIGN ASSEMBLY	26.00 EACH
0075	801-06625	DETOUR ROUTE MARKER ASSEMBLY	73.00 EACH
0076	801-06640	CONSTRUCTION SIGN, TYPE A	30.00 EACH
0077	801-06775	MAINTAINING TRAFFIC	1.00 LS
0078	801-07118	BARRICADE, TYPE III-A	96.00 LFT
0079	801-07119	BARRICADE, TYPE III-B	72.00 LFT
0080	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	274.00 LFT
0081	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	144.00 LFT
0082	802-07057	SIGN, PANEL, WITH LEGEND	338.00 SFT
0083	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	64.00 SFT
0084	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	196.00 SFT
0085	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	20.00 SFT
0086	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, TYPE A	8.00 EACH
0087	802-76095	STRUCTURAL STEEL, BREAKAWAY	1249.00 LBS
0088	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	460.00 LFT
0089	807-02191	HANDHOLE, LIGHTING	7.00 EACH
0090	807-02618	WIRE, NO. 2 COPPER, 3 1/C	100.00 LFT
0091	807-03758	LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING, 24 IN. X 24 IN. X 96 IN.	19.00 EACH
0092	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	3850.00 LFT
0093	807-12199	LUMINAIRE, HIGH LUMEN ROADWAY	19.00 EACH
0094	807-85762	LIGHT POLE, 40 FT E.M.H., 15 FT MAST ARM, BREAKAWAY BASE	19.00 EACH
0095	807-86810	SERVICE POINT, TYPE II	1.00 EACH
0096	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	3600.00 LFT
0097	807-86910	CONNECTOR KIT, UNFUSED	19.00 EACH
0098	807-86915	CONNECTOR KIT, FUSED	19.00 EACH
0099	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	33.00 EACH
0100	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	48.00 EACH
0101	807-86930	INSULATION LINK, NON-WATERPROOFED	46.00 EACH
0102	807-86935	INSULATION LINK, WATERPROOFED	68.00 EACH
0103	807-86950	SIGN, UNDERPASS, AND ROADWAY LIGHTING, LOCATION IDENTIFICATION	19.00 EACH
0104	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	490.00 LFT
0105	808-10039	LINE, MULTI-COMPONENT, SOLID, WHITE, 12 IN.	556.00 LFT

0106	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	2648.00	LFT
0107	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	807.00	LFT
0108	808-10058	LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN.	2926.00	LFT
0109	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	237.00	LFT
0110	808-10077	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, LANE INDICATION ARROW	8.00	EACH
0111	808-11691	LINE, THERMOPLASTIC, DOTTED, WHITE, 12 IN.	126.00	LFT
0112	808-11776	TRANSVERSE MARKING, MULTI-COMPONENT, YIELD LINE, WHITE, 24 IN.	60.00	LFT
0113	808-12032	GROOVING FOR PAVEMENT MARKINGS	7372.00	LFT
0114	808-12353	LINE, MULTI-COMPONENT, DOTTED, WHITE, 6 IN.	72.00	LFT

Call: 230

Contract: R -42254-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	6715.00	SYS
0013	202-62420	BRIDGE RAILING, REMOVE	63.00	LFT
0014	202-92953	CURB AND GUTTER TURNOUT, REMOVE	13.00	SYS
0015	202-93741	GUARDRAIL END TREATMENT, REMOVE	4.00	EACH
0016	203-02000	EXCAVATION, COMMON	8881.00	CYS
0017	203-08607	LINEAR GRADING	120.00	LFT
0018	205-12108	STORMWATER MANAGEMENT BUDGET	36642.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	205-12618	SWQCP PREPARATION	1.00	LS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	14969.00	SYS
0022	211-09264	STRUCTURE BACKFILL, TYPE 1	155.00	CYS
0023	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	998.00	SYS
0024	301-12234	COMPACTED AGGREGATE, NO. 53	172.00	CYS
0025	302-06464	SUBBASE FOR PCCP	74.00	CYS
0026	303-01180	COMPACTED AGGREGATE, NO. 53	1010.00	TON
0027	304-07493	WIDENING WITH HMA, TYPE B	286.00	TON
0028	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1058.00	TON
0029	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	24.00	TON
0030	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1809.00	TON
0031	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	40.00	TON

0032	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	4498.00	TON
0033	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	178.00	TON
0034	401-10258	JOINT ADHESIVE, SURFACE	9583.00	LFT
0035	401-10259	JOINT ADHESIVE, INTERMEDIATE	9583.00	LFT
0036	401-11785	LIQUID ASPHALT SEALANT	9583.00	LFT
0037	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0038	406-05520	ASPHALT FOR TACK COAT	12.00	TON
0039	503-12477	TERMINAL JOINT, TYPE HMA	88.00	LFT
0040	601-02241	GUARDRAIL, REMOVE	690.00	LFT
0041	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	181.25	LFT
0042	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	3.00	EACH
0043	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	1.00	EACH
0044	601-94689	GUARDRAIL END TREATMENT, TYPE OS	4.00	EACH
0045	605-06125	CURB, CONCRETE, MODIFIED	60.00	LFT
0046	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	6826.00	LFT
0047	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	334.40	SYS
0048	615-06505	MONUMENT, TYPE B	2.00	EACH
0049	615-06527	MONUMENT, SECTION CORNER	1.00	EACH
0050	616-06405	RIPRAP, REVETMENT	22.00	TON
0051	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	29.00	SYS
0052	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	7.00	EACH
0053	621-02770	EROSION CONTROL BLANKET	210.00	SYS
0054	621-06559	MULCHED SEEDING, TYPE R	6451.00	SYS
0055	628-09409	MOBILE INTERNET SERVICE	19.00	MOS
0056	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0057	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0058	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0059	628-11977	COMPUTER SYSTEM	1.00	EACH
0060	628-12683	FIELD OFFICE, TYPE D	19.00	MOS
0061	628-12923	CELLULAR TELEPHONE SERVICE, UNLIMITED MINUTES	19.00	MOS
0062	702-51863	FIELD DRILLED HOLE IN CONCRETE	46.00	EACH
0063	703-06029	REINFORCING BARS, EPOXY COATED	21171.00	LBS
0064	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	4.00	EACH
0065	709-51821	SURFACE SEAL	1.00	LS
0066	709-51821	SURFACE SEAL	1.00	LS
0067	709-51821	SURFACE SEAL	1.00	LS
0068	715-05019	PIPE, TYPE 1, CIRCULAR, DIAMETER 36 IN.	186.00	LFT

0069	715-09064	VIDEO INSPECTION FOR PIPE	186.00	LFT
0070	715-46040	PIPE END SECTION, DIAMETER 36 IN.	2.00	EACH
0071	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	150.00	SFT
0072	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	421.00	SFT
0073	738-12855	WARRANTED POLYMER OVERLAY, BRIDGE DECK	1698.00	SYS
0074	738-12856	POLYMER OVERLAY, OTHER CONCRETE SURFACE	386.00	SYS
0075	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00	EACH
0076	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2140.00	LFT
0077	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	3325.00	LFT
0078	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	9820.00	LFT
0079	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	46.00	LFT
0080	801-06625	DETOUR ROUTE MARKER ASSEMBLY	53.00	EACH
0081	801-06640	CONSTRUCTION SIGN, TYPE A	86.00	EACH
0082	801-06645	CONSTRUCTION SIGN, TYPE B	8.00	EACH
0083	801-06775	MAINTAINING TRAFFIC	1.00	LS
0084	801-07118	BARRICADE, TYPE III-A	144.00	LFT
0085	801-07119	BARRICADE, TYPE III-B	192.00	LFT
0086	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0087	801-12042	TRUCK MOUNTED ATTENUATOR	36.00	DAY
0088	801-12081	PORTABLE SIGNAL	1.00	LS
0089	801-12081	PORTABLE SIGNAL	1.00	LS
0090	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	435.00	LFT
0091	802-05703	SIGN POST, SQUARE, TYPE 3, REINFORCED ANCHOR BASE	60.00	LFT
0092	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	108.00	SFT
0093	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	4.00	EACH
0094	808-06724	PAVEMENT MESSAGE MARKING, PAINT, ONLY	2.00	EACH
0095	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	42.00	LFT
0096	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	557.00	LFT
0097	808-12844	LINE, PAINT, DOTTED, WHITE, 10 IN.	285.00	LFT
0098	808-12973	LINE, PAINT, SOLID, WHITE, 10 IN.	782.00	LFT
0099	808-12977	TRANSVERSE MARKING, PAINT, YIELD LINE, WHITE, 27 IN.	32.00	LFT
0100	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	6483.00	LFT
0101	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	3698.00	LFT
0102	808-75060	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, WHITE, 12 IN.	228.00	LFT
0103	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	66.00	EACH

Call: 240

Contract: R -42278-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-02250	TREE, 10 IN., REMOVE	8.00	EACH
0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	1941.00	SYS
0014	202-02271	HEADWALL, REMOVE	2.00	EACH
0015	202-06580	CONTAMINATED SOIL, REMOVE	10.00	CYS
0016	202-07553	REGULATED MATERIALS, REMOVE, TYPE Y	10.00	CYS
0017	202-07554	REGULATED MATERIALS, TRANSPORT, TYPE Y	10.00	CYS
0018	202-07555	REGULATED MATERIALS, DISPOSE, TYPE Y	10.00	CYS
0019	202-91385	INLET, REMOVE	2.00	EACH
0020	202-96133	PIPE, REMOVE	305.00	LFT
0021	203-02000	EXCAVATION, COMMON	4348.00	CYS
0022	203-02000	EXCAVATION, COMMON	310.00	CYS
0023	205-12108	STORMWATER MANAGEMENT BUDGET	7094.00	DOL
0024	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0025	205-12618	SWQCP PREPARATION	1.00	LS
0026	207-08264	SUBGRADE TREATMENT, TYPE II	756.00	SYS
0027	207-12635	SUBGRADE TREATMENT, TYPE IBC	6199.00	SYS
0028	211-02050	B BORROW	310.00	CYS
0029	211-09264	STRUCTURE BACKFILL, TYPE 1	610.00	CYS
0030	301-12234	COMPACTED AGGREGATE, NO. 53	706.00	CYS
0031	302-07455	DENSE GRADED SUBBASE	95.00	CYS

0032	306-08034	MILLING, ASPHALT, 1 1/2 IN.	759.00	SYS
0033	401-07327	QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	412.00	TON
0034	401-07397	QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	542.00	TON
0035	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	829.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	1160.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	1160.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	1160.00	LFT
0039	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	751.00	TON
0040	406-05520	ASPHALT FOR TACK COAT	5.00	TON
0041	502-11564	PCCP, 7 IN.	428.00	SYS
0042	503-05240	D-1 CONTRACTION JOINT	214.00	LFT
0043	604-08086	CURB RAMP, CONCRETE	58.00	SYS
0044	604-12083	DETECTABLE WARNING SURFACES	6.00	SYS
0045	605-02278	CURB, REMOVE	571.00	LFT
0046	605-06120	CURB, CONCRETE	185.00	LFT
0047	605-06121	CURB, CONCRETE, TYPE B	362.00	LFT
0048	605-06140	CURB AND GUTTER, CONCRETE	1685.00	LFT
0049	605-06255	CENTER CURB, D CONCRETE	294.00	SYS
0050	610-07488	HMA FOR APPROACHES, TYPE C	46.00	TON
0051	610-08446	PCCP FOR APPROACHES, 6 IN.	180.00	SYS
0052	610-09108	PCCP FOR APPROACHES, 9 IN.	393.00	SYS
0053	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0054	615-06525	CASTING ADJUST TO GRADE, MONUMENT	1.00	EACH
0055	616-06405	RIPRAP, REVETMENT	2.00	TON
0056	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	6.00	SYS
0057	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0058	621-06560	MULCHED SEEDING, TYPE U	2964.00	SYS
0059	621-06567	WATER	4.00	KGAL
0060	621-06574	SODDING	889.00	SYS
0061	628-09403	FIELD OFFICE, TYPE C	12.00	MOS
0062	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	2364.00	LFT
0063	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	214.00	LFT
0064	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	238.00	LFT
0065	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	289.00	LFT
0066	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	47.00	LFT
0067	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	38.00	LFT
0068	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	240.00	LFT

0069	715-05153	PIPE, TYPE 2, CIRCULAR, DIAMETER 21 IN.	56.00	LFT
0070	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	521.00	LFT
0071	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	256.00	LFT
0072	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	2364.00	LFT
0073	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	1640.00	SYS
0074	718-52610	AGGREGATE FOR UNDERDRAINS	166.00	CYS
0075	720-12797	CASTING, INLET, ADJUST TO GRADE	4.00	EACH
0076	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	7.00	EACH
0077	720-45045	INLET, TYPE J10	9.00	EACH
0078	720-45055	INLET, TYPE M10	8.00	EACH
0079	720-45205	CATCH BASIN, TYPE A2	6.00	EACH
0080	720-45410	MANHOLE, TYPE C4	7.00	EACH
0081	720-90984	MANHOLE, TYPE C2	1.00	EACH
0082	720-94208	MANHOLE, TYPE C10	1.00	EACH
0083	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	3.00	EACH
0084	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0085	801-06625	DETOUR ROUTE MARKER ASSEMBLY	57.00	EACH
0086	801-06640	CONSTRUCTION SIGN, TYPE A	23.00	EACH
0087	801-06645	CONSTRUCTION SIGN, TYPE B	7.00	EACH
0088	801-06775	MAINTAINING TRAFFIC	1.00	LS
0089	801-07118	BARRICADE, TYPE III-A	72.00	LFT
0090	801-07119	BARRICADE, TYPE III-B	72.00	LFT
0091	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	8.00	LFT
0092	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	245.00	LFT
0093	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	57.00	LFT
0094	802-07058	SIGN, SHEET ASSEMBLY, RELOCATE	4.00	EACH
0095	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	4.00	EACH
0096	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	66.00	SFT
0097	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	78.00	SFT
0098	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	18.00	SFT
0099	807-02191	HANDHOLE, LIGHTING	4.00	EACH
0100	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	153.00	LFT
0101	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1149.00	LFT
0102	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	14.00	EACH
0103	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE, WITH GROUNDING	14.00	EACH
0104	807-12912	LIGHT POLE, 30 FT E.M.H., 5 FT MAST ARM, ANCHOR BASE	14.00	EACH
0105	807-86810	SERVICE POINT, TYPE II	1.00	EACH

0106	807-86843	WIRE, NO. 4 COPPER, 1/C	612.00	LFT
0107	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	840.00	LFT
0108	807-86910	CONNECTOR KIT, UNFUSED	14.00	EACH
0109	807-86915	CONNECTOR KIT, FUSED	14.00	EACH
0110	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	30.00	EACH
0111	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	4.00	EACH
0112	807-86930	INSULATION LINK, NON-WATERPROOFED	28.00	EACH
0113	807-86935	INSULATION LINK, WATERPROOFED	4.00	EACH
0114	807-86955	CABLE-DUCT MARKER	14.00	EACH
0115	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	210.00	LFT
0116	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	449.00	LFT
0117	808-11478	LINE, THERMOPLASTIC, DOTTED, WHITE, 8 IN.	183.00	LFT
0118	808-12148	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 36 IN.	96.00	LFT
0119	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2135.00	LFT
0120	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	93.00	LFT
0121	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	30.00	LFT
0122	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	13.00	LFT
0123	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	86.00	LFT

Call: 250

Contract: R -42288-A

Section No.: 1 SLIDE CORRECTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-01015	CLEARING AND GRUBBING	1.00	LS
0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0013	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0014	202-93741	GUARDRAIL END TREATMENT, REMOVE	6.00	EACH
0015	202-96133	PIPE, REMOVE	460.00	LFT
0016	202-97009	FIRE HYDRANT ASSEMBLY, REMOVE	1.00	EACH
0017	202-98488	PIPE END SECTION, REMOVE	2.00	EACH
0018	203-02000	EXCAVATION, COMMON	650.00	CYS
0019	205-11626	PUMP AROUND	1.00	EACH
0020	205-12108	STORMWATER MANAGEMENT BUDGET	25000.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	205-12618	SWQCP PREPARATION	1.00	LS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	1392.00	SYS
0024	211-09265	STRUCTURE BACKFILL, TYPE 2	585.00	CYS
0025	301-12231	COMPACTED AGGREGATE, NO. 2	42.00	CYS
0026	301-12234	COMPACTED AGGREGATE, NO. 53	21.00	CYS
0027	303-01180	COMPACTED AGGREGATE, NO. 53	482.00	TON
0028	304-07493	WIDENING WITH HMA, TYPE B	276.00	TON
0029	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1354.00	SYS
0030	306-11872	MILLING, PROFILE	1106.00	SYS
0031	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	291.00	TON

0032	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	65.00 TON
0033	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	154.00 TON
0034	401-10258	JOINT ADHESIVE, SURFACE	1117.00 LFT
0035	401-10259	JOINT ADHESIVE, INTERMEDIATE	150.00 LFT
0036	401-11785	LIQUID ASPHALT SEALANT	1117.00 LFT
0037	401-12169	INERTIAL PROFILER, HMA	1.00 LS
0038	402-07451	HMA WEDGE AND LEVEL, TYPE B	122.00 TON
0039	406-05520	ASPHALT FOR TACK COAT	2.00 TON
0040	601-02241	GUARDRAIL, REMOVE	937.00 LFT
0041	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	1125.00 LFT
0042	601-94689	GUARDRAIL END TREATMENT, TYPE OS	4.00 EACH
0043	615-06505	MONUMENT, TYPE B	3.00 EACH
0044	616-05689	RIPRAP, CLASS 2	26401.00 TON
0045	616-06405	RIPRAP, REVETMENT	91.00 TON
0046	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	10600.00 SYS
0047	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0048	621-02770	EROSION CONTROL BLANKET	4054.00 SYS
0049	621-06545	FERTILIZER	1.00 TON
0050	621-06553	SEED MIXTURE, TYPE R	210.00 LBS
0051	621-06565	MULCHING MATERIAL	1.00 TON
0052	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00 EACH
0053	628-12683	FIELD OFFICE, TYPE D	24.00 MOS
0054	713-04643	TEMPORARY ACCESS LANE	1.00 LS
0055	714-11168	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 7 FT X 7 FT	88.00 LFT
0056	715-01354	CLEAN EXISTING PIPE	49.00 LFT
0057	715-04964	WATER MAIN	20.00 LFT
0058	715-04995	LINE STOP	2.00 EACH
0059	715-06050	CAP	2.00 EACH
0060	715-06050	CAP	4.00 EACH
0061	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00 EACH
0062	715-90853	TAPPING SLEEVE WITH VALVE	2.00 EACH
0063	715-93911	WATER MAIN, 4 IN.	430.00 LFT
0064	716-11716	PIPE INSTALLATION, TRENCHLESS	250.00 LFT
0065	720-96999	FIRE HYDRANT ASSEMBLY	1.00 EACH
0066	732-05538	TESTING AND DISINFECTION	1.00 LS
0067	801-03291	CONSTRUCTION SIGN, TYPE D	1.00 EACH
0068	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00 EACH

0069	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	610.00	LFT
0070	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	3930.00	LFT
0071	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	20.00	LFT
0072	801-06625	DETOUR ROUTE MARKER ASSEMBLY	35.00	EACH
0073	801-06640	CONSTRUCTION SIGN, TYPE A	31.00	EACH
0074	801-06645	CONSTRUCTION SIGN, TYPE B	9.00	EACH
0075	801-06775	MAINTAINING TRAFFIC	1.00	LS
0076	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00	EACH
0077	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0078	801-07119	BARRICADE, TYPE III-B	60.00	LFT
0079	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	984.00	LFT
0080	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0081	801-12081	PORTABLE SIGNAL	1.00	LS
0082	801-12482	DRIVEWAY ASSISTANCE DEVICE	1.00	EACH
0083	801-97643	TEMPORARY BUZZ STRIPS	840.00	LFT
0084	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	6.00	EACH
0085	802-91122	SIGN, GROUND MOUNTED, RESET	6.00	EACH
0086	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	12.00	LFT
0087	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	157.00	LFT
0088	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	1863.00	LFT
0089	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	1095.00	LFT

Call: 260

Contract: R -42290-A

Section No.: 1 SLIDE CORRECTION

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-01015	CLEARING AND GRUBBING	1.00	LS
	0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
	0012	202-02271	HEADWALL, REMOVE	2.00	EACH
	0013	202-02637	PIPE ABANDON AND GROUT FILL	49.00	LFT
	0014	202-04890	WELL	5.00	EACH
	0015	202-06541	REMOVE	2.00	EACH
	0016	202-93741	GUARDRAIL END TREATMENT, REMOVE	1.00	EACH
	0017	202-96133	PIPE, REMOVE	25.00	LFT
	0018	203-02000	EXCAVATION, COMMON	8375.00	CYS
	0019	203-02070	BORROW	199.00	CYS
	0020	203-02133	EXPLORATORY CORES	499.00	LFT
	0021	203-02590	PIER, DRILL IN BEDROCK SOCKET	288.00	LFT
	0022	203-02591	PIER, FORMED, DRILL ABOVE BEDROCK SOCKET	2059.00	LFT
	0023	203-02592	PIER, NONFORMED, DRILL ABOVE BEDROCK SOCKET	3967.00	LFT
	0024	203-02594	TIEBACK	48.00	EACH
	0025	203-08607	LINEAR GRADING	421.00	LFT
	0026	204-02586	CREEP TEST	4.00	EACH
	0027	204-02593	PROOF TEST	44.00	EACH
	0028	205-11626	PUMP AROUND	1.00	EACH
	0029	205-12108	STORMWATER MANAGEMENT BUDGET	25000.00	DOL
	0030	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0031	205-12618	SWQCP PREPARATION	1.00	LS

0032	207-08264	SUBGRADE TREATMENT, TYPE II	1230.00	SYS
0033	207-12498	SUBGRADE TREATMENT, TYPE ID	3393.00	SYS
0034	211-09265	STRUCTURE BACKFILL, TYPE 2	69.00	CYS
0035	211-09266	STRUCTURE BACKFILL, TYPE 3	2810.00	CYS
0036	214-07202	GEOGRID, TYPE IA	1454.00	SYS
0037	301-12231	COMPACTED AGGREGATE, NO. 2	475.00	CYS
0038	301-12234	COMPACTED AGGREGATE, NO. 53	38.00	CYS
0039	303-01180	COMPACTED AGGREGATE, NO. 53	474.00	TON
0040	303-08210	COMPACTED AGGREGATE, NO. 53, TEMPORARY FOR DRIVEWAYS	68.00	TON
0041	304-07493	WIDENING WITH HMA, TYPE B	90.00	TON
0042	306-08034	MILLING, ASPHALT, 1 1/2 IN.	707.00	SYS
0043	306-11872	MILLING, PROFILE	50.00	SYS
0044	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	307.00	TON
0045	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	382.00	TON
0046	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	929.00	TON
0047	401-10258	JOINT ADHESIVE, SURFACE	1499.00	LFT
0048	401-10259	JOINT ADHESIVE, INTERMEDIATE	1603.00	LFT
0049	401-11785	LIQUID ASPHALT SEALANT	1499.00	LFT
0050	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0051	402-07451	HMA WEDGE AND LEVEL, TYPE B	6.00	TON
0052	402-10084	HMA FOR TEMPORARY PAVEMENT, TYPE B	559.00	TON
0053	406-05520	ASPHALT FOR TACK COAT	4.00	TON
0054	601-02241	GUARDRAIL, REMOVE	838.00	LFT
0055	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	812.50	LFT
0056	601-94689	GUARDRAIL END TREATMENT, TYPE OS	1.00	EACH
0057	610-07487	HMA FOR APPROACHES, TYPE B	48.00	TON
0058	611-06497	MAILBOX ASSEMBLY, SINGLE	2.00	EACH
0059	611-06498	MAILBOX ASSEMBLY, DOUBLE	1.00	EACH
0060	615-06505	MONUMENT, TYPE B	3.00	EACH
0061	616-05689	RIPRAP, CLASS 2	119.00	TON
0062	616-06405	RIPRAP, REVETMENT	2859.00	TON
0063	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	8111.00	SYS
0064	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0065	621-06560	MULCHED SEEDING, TYPE U	3089.00	SYS
0066	621-12612	SEED MIXTURE, FLOODPLAIN	5.00	LBS
0067	621-52448	SIGN, "DO NOT SPRAY"	4.00	EACH
0068	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH

0069	628-12683	FIELD OFFICE, TYPE D	24.00	MOS
0070	702-02925	WATERPROOFING MEMBRANE SYSTEM	350.00	SFT
0071	702-04325	TEMPORARY SHORING	1.00	LS
0072	711-07857	INCLINOMETER	3.00	EACH
0073	715-04995	LINE STOP	3.00	EACH
0074	715-05024	PIPE, TYPE 2, CIRCULAR, DIAMETER 36 IN.	74.00	LFT
0075	715-06050	CAP	1.00	EACH
0076	715-06050	CAP	3.00	EACH
0077	715-90853	TAPPING SLEEVE WITH VALVE	2.00	EACH
0078	715-91739	WATER SERVICE LINE, 0.75 IN.	55.00	LFT
0079	715-93403	WATER SERVICE CONNECTION, 0.75 IN.	3.00	EACH
0080	715-93911	WATER MAIN, 4 IN.	20.00	LFT
0081	715-93912	WATER MAIN, 6 IN.	1200.00	LFT
0082	720-45066	INLET, TYPE N12, MODIFIED	1.00	EACH
0083	720-96999	FIRE HYDRANT ASSEMBLY	1.00	EACH
0084	732-05538	TESTING AND DISINFECTION	1.00	LS
0085	732-09163	TEST	5.00	EACH
0086	734-10240	CUT-WALL, NO.	257.00	SFT
0087	734-10240	CUT-WALL, NO.	222.00	SFT
0088	801-03290	CONSTRUCTION SIGN, TYPE C	2.00	EACH
0089	801-03291	CONSTRUCTION SIGN, TYPE D	6.00	EACH
0090	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0091	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	1496.00	LFT
0092	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	12295.00	LFT
0093	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	44.00	LFT
0094	801-06640	CONSTRUCTION SIGN, TYPE A	19.00	EACH
0095	801-06645	CONSTRUCTION SIGN, TYPE B	20.00	EACH
0096	801-06775	MAINTAINING TRAFFIC	1.00	LS
0097	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	8.00	EACH
0098	801-07119	BARRICADE, TYPE III-B	64.00	LFT
0099	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1164.00	LFT
0100	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0101	801-12081	PORTABLE SIGNAL	1.00	LS
0102	801-12482	DRIVEWAY ASSISTANCE DEVICE	6.00	EACH
0103	801-97643	TEMPORARY BUZZ STRIPS	924.00	LFT
0104	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	3.00	EACH
0105	808-06716	LINE, REMOVE	3094.00	LFT

0106	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	270.00	LFT
0107	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	2150.00	LFT
0108	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	9.00	EACH

Call: 270

Contract: R -42293-A

Section No.: 1

SMALL STRUCTURE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	4.00	EACH
	0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0004	109-08360	CONTRACT LIENS	1.00	DOL
	0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
	0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
	0013	202-02271	HEADWALL, REMOVE	2.00	EACH
	0014	202-96133	PIPE, REMOVE	165.00	LFT
	0015	203-02000	EXCAVATION, COMMON	251.00	CYS
	0016	203-02070	BORROW	119.00	CYS
	0017	205-11626	PUMP AROUND	2.00	EACH
	0018	205-12108	STORMWATER MANAGEMENT BUDGET	15541.00	DOL
	0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0020	207-09935	SUBGRADE TREATMENT, TYPE IC	1055.00	SYS
	0021	211-09264	STRUCTURE BACKFILL, TYPE 1	144.00	CYS
	0022	211-09265	STRUCTURE BACKFILL, TYPE 2	93.00	CYS
	0023	211-09268	STRUCTURE BACKFILL, TYPE 5	100.00	CYS
	0024	301-12234	COMPACTED AGGREGATE, NO. 53	43.00	CYS
	0025	303-01180	COMPACTED AGGREGATE, NO. 53	232.00	TON
	0026	304-07494	WIDENING WITH HMA, TYPE C	235.00	TON
	0027	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1681.00	SYS
	0028	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	203.00	TON
	0029	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	38.00	TON
	0030	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	118.00	TON
	0031	401-10258	JOINT ADHESIVE, SURFACE	2172.00	LFT

0032	401-10259	JOINT ADHESIVE, INTERMEDIATE	80.00	LFT
0033	401-11785	LIQUID ASPHALT SEALANT	2172.00	LFT
0034	406-05520	ASPHALT FOR TACK COAT	2.00	TON
0035	615-06490	RIGHT-OF-WAY MARKER	26.00	EACH
0036	615-06505	MONUMENT, TYPE B	4.00	EACH
0037	616-05688	RIPRAP, CLASS 1	64.00	TON
0038	616-05689	RIPRAP, CLASS 2	79.00	TON
0039	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	176.00	SYS
0040	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0041	621-06559	MULCHED SEEDING, TYPE R	1209.00	SYS
0042	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0043	628-12683	FIELD OFFICE, TYPE D	6.00	MOS
0044	714-11191	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 5 FT X 4 FT	42.00	LFT
0045	715-05032	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	97.00	LFT
0046	715-05133	PIPE, TYPE 1, CIRCULAR, DIAMETER 60 IN.	45.00	LFT
0047	715-12871	GEOTEXTILE FOR PIPE TYPE 2A	80.00	SYS
0048	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0049	720-45410	MANHOLE, TYPE C4	1.00	EACH
0050	801-04308	ROAD CLOSURE SIGN ASSEMBLY	14.00	EACH
0051	801-06625	DETOUR ROUTE MARKER ASSEMBLY	71.00	EACH
0052	801-06640	CONSTRUCTION SIGN, TYPE A	14.00	EACH
0053	801-06775	MAINTAINING TRAFFIC	1.00	LS
0054	801-07119	BARRICADE, TYPE III-B	144.00	LFT
0055	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	10.00	LFT
0056	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1268.00	LFT
0057	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	80.00	LFT
0058	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1.00	EACH
0059	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1.00	EACH

Call: 280

Contract: R -42334-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-91840	FENCE, CHAIN LINK, REMOVE	267.00	LFT
0013	202-96133	PIPE, REMOVE	184.00	LFT
0014	203-02000	EXCAVATION, COMMON	1872.00	CYS
0015	203-02070	BORROW	9682.00	CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	15000.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	328.00	SYS
0020	207-08266	SUBGRADE TREATMENT, TYPE III	306.00	SYS
0021	207-08268	SUBGRADE TREATMENT, TYPE IV	5665.00	SYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	1544.00	CYS
0023	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	9.00	CYS
0024	301-12233	COMPACTED AGGREGATE, NO. 8	41.00	CYS
0025	301-12234	COMPACTED AGGREGATE, NO. 53	92.00	CYS
0026	303-01180	COMPACTED AGGREGATE, NO. 53	381.00	TON
0027	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	17.00	TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	461.00	SYS
0029	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	401.00	TON
0030	401-07397	QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	604.00	TON
0031	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	2071.00	TON

0032	401-10258	JOINT ADHESIVE, SURFACE	1141.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	1141.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	1141.00	LFT
0035	406-05520	ASPHALT FOR TACK COAT	5.00	TON
0036	502-06999	PCCP, 8 IN.	360.00	SYS
0037	502-11543	PCCP, 4 IN.	306.00	SYS
0038	503-05240	D-1 CONTRACTION JOINT	302.00	LFT
0039	604-06070	SIDEWALK, CONCRETE	143.00	SYS
0040	604-08086	CURB RAMP, CONCRETE	180.00	SYS
0041	604-12083	DETECTABLE WARNING SURFACES	37.00	SYS
0042	605-06120	CURB, CONCRETE	1022.00	LFT
0043	605-06255	CENTER CURB, D CONCRETE	11.00	SYS
0044	605-52807	CURB AND GUTTER, COMBINED	1294.00	LFT
0045	605-97937	CURB AND GUTTER, ROLL CURB	264.00	LFT
0046	610-07487	HMA FOR APPROACHES, TYPE B	37.00	TON
0047	610-08446	PCCP FOR APPROACHES, 6 IN.	138.00	SYS
0048	611-06497	MAILBOX ASSEMBLY, SINGLE	3.00	EACH
0049	615-06490	RIGHT-OF-WAY MARKER	20.00	EACH
0050	615-06527	MONUMENT, SECTION CORNER	1.00	EACH
0051	616-06405	RIPRAP, REVETMENT	105.00	TON
0052	616-12247	GEOTEXTILE FOR RIPRAP, TYPE 1B	140.00	SYS
0053	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	76.00	SYS
0054	621-06570	TOPSOIL	80.00	CYS
0055	621-06575	SODDING, NURSERY	5759.00	SYS
0056	628-09401	FIELD OFFICE, TYPE A	12.00	MOS
0057	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0058	715-05024	PIPE, TYPE 2, CIRCULAR, DIAMETER 36 IN.	242.00	LFT
0059	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	1568.00	LFT
0060	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	124.00	LFT
0061	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	420.00	LFT
0062	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	86.00	LFT
0063	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	244.00	LFT
0064	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	232.00	LFT
0065	715-05161	PIPE, TYPE 2, CIRCULAR, DIAMETER 48 IN.	178.00	LFT
0066	715-05168	PIPE, TYPE 3, CIRCULAR, DIAMETER 12 IN.	32.00	LFT
0067	715-09064	VIDEO INSPECTION FOR PIPE	1402.00	LFT
0068	715-46000	PIPE END SECTION, DIAMETER 12 IN.	3.00	EACH

0069	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00 EACH
0070	715-46040	PIPE END SECTION, DIAMETER 36 IN.	2.00 EACH
0071	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	1568.00 LFT
0072	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	1433.00 SYS
0073	718-52610	AGGREGATE FOR UNDERDRAINS	141.00 CYS
0074	720-03757	MANHOLE, TYPE C15	2.00 EACH
0075	720-45010	INLET, TYPE A3	1.00 EACH
0076	720-45235	CATCH BASIN, TYPE E7	3.00 EACH
0077	720-45265	PIPE CATCH BASIN, 15 IN.	1.00 EACH
0078	720-45270	PIPE CATCH BASIN, 18 IN.	1.00 EACH
0079	720-45410	MANHOLE, TYPE C4	4.00 EACH
0080	720-91352	CATCH BASIN, TYPE F7	3.00 EACH
0081	720-92884	MANHOLE, TYPE K4, MODIFIED	2.00 EACH
0082	720-93501	MANHOLE, TYPE L4	3.00 EACH
0083	720-94612	MANHOLE, TYPE K4	1.00 EACH
0084	720-95422	MANHOLE, TYPE J4	2.00 EACH
0085	720-98174	INLET, TYPE B15	5.00 EACH
0086	720-98555	INLET, TYPE C15	1.00 EACH
0087	720-99417	CATCH BASIN, TYPE C15	3.00 EACH
0088	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00 EACH
0089	801-06625	DETOUR ROUTE MARKER ASSEMBLY	30.00 EACH
0090	801-06640	CONSTRUCTION SIGN, TYPE A	21.00 EACH
0091	801-06645	CONSTRUCTION SIGN, TYPE B	1.00 EACH
0092	801-06775	MAINTAINING TRAFFIC	1.00 LS
0093	801-07118	BARRICADE, TYPE III-A	72.00 LFT
0094	801-07119	BARRICADE, TYPE III-B	120.00 LFT
0095	802-04089	SIGN, SHEET, REMOVE	16.00 EACH
0096	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	294.00 LFT
0097	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	76.00 LFT
0098	802-07060	SIGN, SHEET, RELOCATE	1.00 EACH
0099	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	141.00 SFT
0100	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	51.00 SFT
0101	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	640.00 LFT
0102	805-95568	CONDUIT, PVC, 4 IN.	232.00 LFT
0103	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	370.00 LFT
0104	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1233.00 LFT
0105	808-11478	LINE, THERMOPLASTIC, DOTTED, WHITE, 8 IN.	45.00 LFT

0106	808-12032	GROOVING FOR PAVEMENT MARKINGS	3350.00	LFT
0107	808-12148	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 36 IN.	78.00	LFT
0108	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2520.00	LFT
0109	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	27.00	EACH

Call: 300

Contract: R -42426-A

Section No.: 1 INTERSECTION IMPROVEMENT WITH ADDED TURN LANES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	3.00	EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	3.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0013	202-01261	TESTING FOR ASBESTOS	1.00	EACH
0014	202-01502	LIGHT STANDARD, REMOVE	1.00	EACH
0015	202-02240	PAVEMENT REMOVAL	7367.00	SYS
0016	202-02637	PIPE ABANDON AND GROUT FILL	240.00	LFT
0017	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00	LS
0018	202-03135	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	9.00	SFT
0019	202-06580	CONTAMINATED SOIL, REMOVE	10.00	CYS
0020	202-07603	TESTING FOR WASTES, TYPE C	2.00	EACH
0021	202-52710	SIDEWALK CONCRETE, REMOVE	30.00	SYS
0022	202-91385	INLET, REMOVE	14.00	EACH
0023	202-91840	FENCE, CHAIN LINK, REMOVE	82.00	LFT
0024	202-93047	MANHOLE, REMOVE	2.00	EACH
0025	202-96133	PIPE, REMOVE	929.00	LFT
0026	202-98488	PIPE END SECTION, REMOVE	7.00	EACH
0027	202-99187	FENCE, FARM FIELD, REMOVE	550.00	LFT
0028	203-02000	EXCAVATION, COMMON	23825.00	CYS
0029	203-02010	EXCAVATION, ROCK	2896.00	CYS
0030	205-12108	STORMWATER MANAGEMENT BUDGET	100001.00	DOL
0031	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS

0032	205-12618	SWQCP PREPARATION	1.00	LS
0033	207-08264	SUBGRADE TREATMENT, TYPE II	1598.00	SYS
0034	207-09935	SUBGRADE TREATMENT, TYPE IC	12504.00	SYS
0035	207-12635	SUBGRADE TREATMENT, TYPE IBC	9180.00	SYS
0036	208-02046	GRADING IN GORE AREA	1.00	EACH
0037	211-02050	B BORROW	8405.00	CYS
0038	211-09265	STRUCTURE BACKFILL, TYPE 2	5364.00	CYS
0039	211-09266	STRUCTURE BACKFILL, TYPE 3	9966.00	CYS
0040	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	21024.00	SYS
0041	301-12234	COMPACTED AGGREGATE, NO. 53	2395.00	CYS
0042	303-01180	COMPACTED AGGREGATE, NO. 53	1312.00	TON
0043	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	210.00	TON
0044	306-08034	MILLING, ASPHALT, 1 1/2 IN.	205.00	SYS
0045	306-08036	MILLING, ASPHALT, 2 IN.	1701.00	SYS
0046	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2286.00	TON
0047	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	2885.00	TON
0048	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	733.00	TON
0049	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	7815.00	TON
0050	401-10258	JOINT ADHESIVE, SURFACE	14504.00	LFT
0051	401-10259	JOINT ADHESIVE, INTERMEDIATE	14504.00	LFT
0052	401-11785	LIQUID ASPHALT SEALANT	14504.00	LFT
0053	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	2333.00	TON
0054	406-05520	ASPHALT FOR TACK COAT	40.00	TON
0055	503-05240	D-1 CONTRACTION JOINT	659.00	LFT
0056	509-12191	JOINT REPAIR, PARTIAL DEPTH	450.00	SFT
0057	601-01626	GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, TYPE 2	1.00	EACH
0058	601-02241	GUARDRAIL, REMOVE	329.00	LFT
0059	601-06238	IMPACT ATTENUATOR, R1-W1, TL-3	1.00	EACH
0060	601-06246	IMPACT ATTENUATOR, R2-W1, TL-3	3.00	EACH
0061	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	50.00	LFT
0062	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	1.00	EACH
0063	601-12291	GUARDRAIL TRANSITION, MGS WITH CURB	1.00	EACH
0064	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	1.00	EACH
0065	601-12294	GUARDRAIL, MGS W-BEAM, CABLE TERMINAL ANCHOR	1.00	EACH
0066	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00	EACH
0067	602-01064	CONCRETE BARRIER	2305.00	LFT
0068	602-06729	BARRIER DELINEATOR	29.00	EACH

0069	603-06045	FENCE, CHAIN LINK, 48 IN.	1790.00	LFT
0070	604-06070	SIDEWALK, CONCRETE	159.00	SYS
0071	604-08086	CURB RAMP, CONCRETE	36.00	SYS
0072	604-12083	DETECTABLE WARNING SURFACES	7.00	SYS
0073	605-06140	CURB AND GUTTER, CONCRETE	917.00	LFT
0074	605-06160	CURB AND GUTTER, TYPE B, CONCRETE, MODIFIED	128.00	LFT
0075	605-06255	CENTER CURB, D CONCRETE	104.00	SYS
0076	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	222.00	LFT
0077	607-06175	GUTTER, CONCRETE, TYPE A	18.00	LFT
0078	607-06335	PAVED SIDE DITCH, TYPE A	370.00	LFT
0079	607-06350	PAVED SIDE DITCH, TYPE D	632.00	LFT
0080	607-06370	PAVED SIDE DITCH, TYPE H	450.00	LFT
0081	610-07487	HMA FOR APPROACHES, TYPE B	611.00	TON
0082	611-08232	MAILBOX ASSEMBLY, RESET, SINGLE	1.00	EACH
0083	615-06505	MONUMENT, TYPE B	8.00	EACH
0084	616-05689	RIPRAP, CLASS 2	70.00	TON
0085	616-06405	RIPRAP, REVETMENT	698.00	TON
0086	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	1085.00	SYS
0087	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0088	621-06545	FERTILIZER	2.00	TON
0089	621-06554	SEED MIXTURE, TYPE U	970.00	LBS
0090	621-06565	MULCHING MATERIAL	10.00	TON
0091	621-06574	SODDING	3584.00	SYS
0092	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0093	628-12683	FIELD OFFICE, TYPE D	18.00	MOS
0094	702-51015	CONCRETE, B, FOOTINGS	319.00	CYS
0095	703-06029	REINFORCING BARS, EPOXY COATED	43684.00	LBS
0096	706-08496	REINFORCED CONCRETE MOMENT SLAB, 12 IN.	1121.00	SYS
0097	706-08496	REINFORCED CONCRETE MOMENT SLAB, 12 IN.	172.00	SYS
0098	706-11601	RAILING, CONCRETE TYPE FT	122.00	CYS
0099	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFT	4.00	EACH
0100	709-51821	SURFACE SEAL	1.00	LS
0101	715-03475	SAFETY METAL END SECTION, 4:1, DIAMETER 15 IN.	1.00	EACH
0102	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	7230.00	LFT
0103	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	244.00	LFT
0104	715-05119	PIPE, TYPE 1, CIRCULAR, DIAMETER 15 IN.	115.00	LFT
0105	715-05121	PIPE, TYPE 1, CIRCULAR, DIAMETER 18 IN.	110.00	LFT

0106	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	399.00	LFT
0107	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	1159.00	LFT
0108	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	398.00	LFT
0109	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	430.00	LFT
0110	715-05161	PIPE, TYPE 2, CIRCULAR, DIAMETER 48 IN.	293.00	LFT
0111	715-06004	CONCRETE ANCHOR, DIAMETER 48 IN.	2.00	EACH
0112	715-09920	PIPE, TYPE 3, DEFORMED, MIN. AREA 4.1 SFT	150.00	LFT
0113	715-11629	GRATED BOX END SECTION, I, 4:1, MIN. AREA 5.10 SFT	2.00	EACH
0114	715-46005	PIPE END SECTION, DIAMETER 15 IN.	5.00	EACH
0115	715-46010	PIPE END SECTION, DIAMETER 18 IN.	3.00	EACH
0116	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00	EACH
0117	718-06528	OUTLET PROTECTOR, TYPE 1	12.00	EACH
0118	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	5686.00	SYS
0119	718-52610	AGGREGATE FOR UNDERDRAINS	1031.00	CYS
0120	720-08658	MANHOLE, TYPE J5	1.00	EACH
0121	720-08660	MANHOLE, TYPE J5, MODIFIED	2.00	EACH
0122	720-45042	INLET, TYPE HA5	16.00	EACH
0123	720-45042	INLET, TYPE HA5	3.00	EACH
0124	720-45045	INLET, TYPE J10	5.00	EACH
0125	720-45145	INLET, TYPE J10, MODIFIED	1.00	EACH
0126	720-93411	INLET, TYPE C15, MODIFIED	1.00	EACH
0127	720-94612	MANHOLE, TYPE K4	3.00	EACH
0128	731-93945	FACE PANELS, CONCRETE	13298.00	SFT
0129	731-93946	WALL ERECTION	13298.00	SFT
0130	731-93947	LEVELING PAD, CONCRETE	875.00	LFT
0131	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0132	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	24631.00	LFT
0133	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	198.00	LFT
0134	801-06640	CONSTRUCTION SIGN, TYPE A	69.00	EACH
0135	801-06645	CONSTRUCTION SIGN, TYPE B	36.00	EACH
0136	801-06710	FLASHING ARROW SIGN	1080.00	DAY
0137	801-06775	MAINTAINING TRAFFIC	1.00	LS
0138	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.00	EACH
0139	801-07118	BARRICADE, TYPE III-A	196.00	LFT
0140	801-07119	BARRICADE, TYPE III-B	48.00	LFT
0141	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	505.00	LFT
0142	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH

0143	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	24.00	LFT
0144	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	295.667	LFT
0145	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	63.00	LFT
0146	802-07057	SIGN, PANEL, WITH LEGEND	346.00	SFT
0147	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	109.25	SFT
0148	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	226.153	SFT
0149	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	30.00	SFT
0150	802-12223	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, TYPE B	8.00	EACH
0151	802-76095	STRUCTURAL STEEL, BREAKAWAY	1667.00	LBS
0152	804-11353	LANE SEPARATOR	225.00	LFT
0153	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	875.00	LFT
0154	807-02191	HANDHOLE, LIGHTING	6.00	EACH
0155	807-02603	LIGHT STANDARD, RELOCATE	1.00	EACH
0156	807-04654	LIGHT POLE	3.00	EACH
0157	807-04654	LIGHT POLE	16.00	EACH
0158	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	229.00	LFT
0159	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	4541.00	LFT
0160	807-11941	LIGHT POLE, 30 FT E.M.H., 5 FT MAST ARM, BREAKAWAY BASE	1.00	EACH
0161	807-12199	LUMINAIRE, HIGH LUMEN ROADWAY	20.00	EACH
0162	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE, WITH GROUNDING	18.00	EACH
0163	807-86810	SERVICE POINT, TYPE II	2.00	EACH
0164	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	2552.00	LFT
0165	807-86910	CONNECTOR KIT, UNFUSED	21.00	EACH
0166	807-86915	CONNECTOR KIT, FUSED	21.00	EACH
0167	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	50.00	EACH
0168	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	12.00	EACH
0169	807-86930	INSULATION LINK, NON-WATERPROOFED	48.00	EACH
0170	807-86935	INSULATION LINK, WATERPROOFED	24.00	EACH
0171	807-86955	CABLE-DUCT MARKER	5.00	EACH
0172	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	48.00	LFT
0173	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	764.00	LFT
0174	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	7581.00	LFT
0175	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	10.00	EACH
0176	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	5808.00	LFT
0177	808-10063	LINE, MULTI-COMPONENT, DOTTED, YELLOW, 6 IN.	116.00	LFT
0178	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	1879.00	LFT
0179	808-10077	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, LANE INDICATION ARROW	15.00	EACH

0180	808-12032	GROOVING FOR PAVEMENT MARKINGS	18551.00	LFT
0181	808-12781	LINE, MULTI-COMPONENT, SOLID, WHITE, 10 IN.	1980.00	LFT
0182	808-12851	LINE, MULTI-COMPONENT, DOTTED, WHITE, 10 IN.	464.00	LFT
0183	808-12859	LINE, MULTI-COMPONENT, SOLID, YELLOW, 10 IN.	550.00	LFT
0184	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	268.00	LFT
0185	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	257.00	LFT
0186	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	116.00	LFT
0187	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	133.00	EACH
0188	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	108.00	EACH

Call: 330

Contract: R -42710-A

Section No.: 1 TRAFFIC SIGNAL VISIBILITY IMPROVEMENTS

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	202-04435	DELINEATOR POST, REMOVE	9.00	EACH
0013	202-06542	RELOCATE	2.00	EACH
0014	202-93741	GUARDRAIL END TREATMENT, REMOVE	9.00	EACH
0015	202-96133	PIPE, REMOVE	265.00	LFT
0016	203-02000	EXCAVATION, COMMON	690.00	CYS
0017	205-11626	PUMP AROUND	2.00	EACH
0018	205-12108	STORMWATER MANAGEMENT BUDGET	5787.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	1565.00	SYS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	200.00	SYS
0022	211-09268	STRUCTURE BACKFILL, TYPE 5	251.00	CYS
0023	214-11796	GEOGRID, TYPE IB	1565.00	SYS
0024	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	200.00	SYS
0025	301-12233	COMPACTED AGGREGATE, NO. 8	30.00	CYS
0026	301-12234	COMPACTED AGGREGATE, NO. 53	1.00	CYS
0027	303-01180	COMPACTED AGGREGATE, NO. 53	9297.00	TON
0028	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	1033.00	TON
0029	304-12626	HMA PATCHING, PARTIAL DEPTH, TYPE C	700.00	TON
0030	306-08034	MILLING, ASPHALT, 1 1/2 IN.	339566.00	SYS
0031	306-08432	MILLING, APPROACH	6723.00	SYS

0032	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	28015.00	TON
0033	401-10258	JOINT ADHESIVE, SURFACE	248925.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	248925.00	LFT
0035	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0036	406-05520	ASPHALT FOR TACK COAT	120.00	TON
0037	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	288.00	SFT
0038	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	9.00	EACH
0039	601-94689	GUARDRAIL END TREATMENT, TYPE OS	9.00	EACH
0040	604-08086	CURB RAMP, CONCRETE	18.00	SYS
0041	604-12083	DETECTABLE WARNING SURFACES	4.00	SYS
0042	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	160476.00	LFT
0043	610-07488	HMA FOR APPROACHES, TYPE C	555.00	TON
0044	615-06520	MONUMENT, RE-ESTABLISH	28.00	EACH
0045	616-06405	RIPRAP, REVETMENT	20.20	TON
0046	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	43.00	SYS
0047	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	161.00	SYS
0048	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0049	621-06545	FERTILIZER	1.00	TON
0050	621-06553	SEED MIXTURE, TYPE R	55.00	LBS
0051	621-06565	MULCHING MATERIAL	1.00	TON
0052	621-06570	TOPSOIL	145.00	CYS
0053	628-09403	FIELD OFFICE, TYPE C	12.00	MOS
0054	702-04325	TEMPORARY SHORING	1.00	LS
0055	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	8.00	LFT
0056	715-05239	PIPE, TYPE 1, DEFORMED, MIN. AREA 7.4 SFT	126.00	LFT
0057	715-07780	SAFETY METAL END SECTION, 4:1, MIN. AREA 5.1 SFT	2.00	EACH
0058	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	132.00	TON
0059	715-08447	PIPE, TYPE 1, DEFORMED, MIN. AREA 5.1 SFT	124.00	LFT
0060	715-08455	SAFETY METAL END SECTION, 4:1, MIN. AREA 7.4 SFT	2.00	EACH
0061	720-12797	CASTING, INLET, ADJUST TO GRADE	16.00	EACH
0062	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	226166.00	LFT
0063	801-06640	CONSTRUCTION SIGN, TYPE A	45.00	EACH
0064	801-06645	CONSTRUCTION SIGN, TYPE B	27.00	EACH
0065	801-06710	FLASHING ARROW SIGN	120.00	DAY
0066	801-06775	MAINTAINING TRAFFIC	1.00	LS
0067	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	3.00	EACH
0068	801-07118	BARRICADE, TYPE III-A	60.00	LFT

0069	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	82.00	LFT
0070	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	2030.00	LFT
0071	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0072	801-11990	TEMPORARY CURB RAMP	1.00	EACH
0073	801-12042	TRUCK MOUNTED ATTENUATOR	120.00	DAY
0074	801-12324	LAW ENFORCEMENT OFFICER	600.00	HRS
0075	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	45.00	LFT
0076	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	4.00	EACH
0077	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	15.00	SFT
0078	804-11920	DELINEATOR POST, FLEXIBLE, TYPE I	9.00	EACH
0079	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.00	EACH
0080	805-01842	HANDHOLE, SIGNAL, TYPE 1	12.00	EACH
0081	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	1.00	EACH
0082	805-07767	SIGNAL CABLE, CONTROL, COPPER, 12C/14 GAUGE	600.00	LFT
0083	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	27.00	EACH
0084	805-11814	CONDUIT, HDPE, 2 IN. SCHEDULE 40	3400.00	LFT
0085	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	3750.00	LFT
0086	805-11965	SOLAR POWERED FLASHING LED SIGN ASSEMBLY	4.00	EACH
0087	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	12.00	EACH
0088	805-78225	TRAFFIC SIGNAL HEAD, NO. 4 SECTION, 12 IN.	2.00	EACH
0089	805-78415	SPAN, CATENARY, AND TETHER	6.00	EACH
0090	805-78420	DISCONNECT HANGER	6.00	EACH
0091	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	19650.00	LFT
0092	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	1300.00	LFT
0093	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	200.00	LFT
0094	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	1150.00	LFT
0095	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	18050.00	LFT
0096	805-78785	SIGNAL DETECTOR HOUSING	45.00	EACH
0097	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	7250.00	LFT
0098	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	1.00	EACH
0099	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	750.00	LFT
0100	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	354.00	LFT
0101	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0102	808-12032	GROOVING FOR PAVEMENT MARKINGS	192719.00	LFT
0103	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	94417.00	LFT
0104	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	78750.00	LFT
0105	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	133.00	LFT

0106	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	1069.00	LFT
0107	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	91.00	EACH
0108	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	8.00	EACH
0109	808-75340	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, RXR	1.00	EACH
0110	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1428.00	EACH
0111	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1428.00	EACH
0112	808-96075	LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN.	20170.00	LFT

Call: 350

Contract: R -43409-A

Section No.: 1 INTERSECTION IMPROVEMENT WITH ADDED TURN LANES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-93741	GUARDRAIL END TREATMENT, REMOVE	2.00	EACH
0012	202-93995	SIGNAL POLE FOUNDATION, REMOVE	2.00	EACH
0013	202-93999	SIGNAL POLE, REMOVE	2.00	EACH
0014	202-94747	POST, REMOVE	29.00	EACH
0015	203-02000	EXCAVATION, COMMON	950.00	CYS
0016	203-02070	BORROW	750.00	CYS
0017	205-12108	STORMWATER MANAGEMENT BUDGET	13862.00	DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0019	205-12618	SWQCP PREPARATION	1.00	LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	473.00	SYS
0021	207-08268	SUBGRADE TREATMENT, TYPE IV	3744.00	SYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	91.00	CYS
0023	214-11796	GEOGRID, TYPE IB	299.00	SYS
0024	302-07455	DENSE GRADED SUBBASE	36.00	CYS
0025	303-01180	COMPACTED AGGREGATE, NO. 53	452.00	TON
0026	304-07494	WIDENING WITH HMA, TYPE C	121.00	TON
0027	306-08034	MILLING, ASPHALT, 1 1/2 IN.	5353.00	SYS
0028	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	686.00	TON
0029	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	383.00	TON
0030	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	1282.00	TON
0031	401-10258	JOINT ADHESIVE, SURFACE	9874.00	LFT

0032	401-10259	JOINT ADHESIVE, INTERMEDIATE	4454.00	LFT
0033	401-11785	LIQUID ASPHALT SEALANT	9874.00	LFT
0034	402-10086	HMA FOR TEMPORARY PAVEMENT, TYPE C	37.00	TON
0035	406-05520	ASPHALT FOR TACK COAT	3.00	TON
0036	601-05586	GUARDRAIL TERMINAL SYSTEM, W-BEAM CURVED, TYPE 9	1.00	EACH
0037	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	272.00	LFT
0038	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	3.00	EACH
0039	601-94689	GUARDRAIL END TREATMENT, TYPE OS	3.00	EACH
0040	605-06145	CURB AND GUTTER, TYPE B, CONCRETE	527.00	LFT
0041	610-07488	HMA FOR APPROACHES, TYPE C	96.00	TON
0042	610-09108	PCCP FOR APPROACHES, 9 IN.	216.00	SYS
0043	615-06505	MONUMENT, TYPE B	8.00	EACH
0044	616-06451	RIPRAP, UNIFORM	51.00	TON
0045	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	129.00	SYS
0046	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0047	621-06560	MULCHED SEEDING, TYPE U	64.00	SYS
0048	621-06567	WATER	1.00	KGAL
0049	621-06574	SODDING	131.00	SYS
0050	715-03475	SAFETY METAL END SECTION, 4:1, DIAMETER 15 IN.	2.00	EACH
0051	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	105.00	LFT
0052	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	1.00	EACH
0053	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0054	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	16927.00	LFT
0055	801-06625	DETOUR ROUTE MARKER ASSEMBLY	25.00	EACH
0056	801-06640	CONSTRUCTION SIGN, TYPE A	25.00	EACH
0057	801-06645	CONSTRUCTION SIGN, TYPE B	6.00	EACH
0058	801-06775	MAINTAINING TRAFFIC	1.00	LS
0059	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	7.00	EACH
0060	801-07118	BARRICADE, TYPE III-A	24.00	LFT
0061	801-07119	BARRICADE, TYPE III-B	24.00	LFT
0062	801-07612	TEMPORARY PAVEMENT MARKING, 24 IN.	50.00	LFT
0063	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1235.00	LFT
0064	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	110.00	LFT
0065	801-94295	SIGNAL HEAD RELOCATE	4.00	EACH
0066	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	228.00	LFT
0067	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	21.00	LFT
0068	802-05703	SIGN POST, SQUARE, TYPE 3, REINFORCED ANCHOR BASE	50.00	LFT

0069	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	36.00 EACH
0070	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	140.00 SFT
0071	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	45.00 SFT
0072	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	82.00 SFT
0073	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00 EACH
0074	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	4.00 EACH
0075	805-01842	HANDHOLE, SIGNAL, TYPE 1	10.00 EACH
0076	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	1389.00 LFT
0077	805-02445	CONTROLLER AND CABINET, TYPE P1	1.00 EACH
0078	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	8.00 EACH
0079	805-78225	TRAFFIC SIGNAL HEAD, NO. 4 SECTION, 12 IN.	2.00 EACH
0080	805-78415	SPAN, CATENARY, AND TETHER	4.00 EACH
0081	805-78420	DISCONNECT HANGER	4.00 EACH
0082	805-78445	SIGNAL SERVICE	1.00 EACH
0083	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	107.00 LFT
0084	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	3564.00 LFT
0085	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	663.00 LFT
0086	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	89.00 LFT
0087	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	322.00 LFT
0088	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	1590.00 LFT
0089	805-78785	SIGNAL DETECTOR HOUSING	10.00 EACH
0090	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1202.00 LFT
0091	805-78925	CONTROLLER CABINET FOUNDATION, TYPE P1	1.00 EACH
0092	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	4.00 EACH
0093	808-06368	TRANSVERSE MARKING, REMOVE	162.00 LFT
0094	808-06716	LINE, REMOVE	9050.00 LFT
0095	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	54.00 LFT
0096	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	40.00 LFT
0097	808-12667	LINE, THERMOPLASTIC, SOLID, WHITE, 10 IN.	896.00 LFT
0098	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	3004.00 LFT
0099	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	4466.00 LFT
0100	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	377.00 LFT
0101	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	119.00 LFT
0102	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	7.00 EACH
0103	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	44.00 EACH
0104	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	44.00 EACH

Call: 360

Contract: R -44081-A

Section No.: 1 AUXILIARY LANES, ACCEL AND DECEL OR TURN LANES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	202-02273	CENTER CURB, CONCRETE, REMOVE	437.00	SYS
0011	202-04435	DELINEATOR POST, REMOVE	18.00	EACH
0012	202-86946	HANDHOLE, REMOVE	4.00	EACH
0013	203-02000	EXCAVATION, COMMON	1645.00	CYS
0014	205-12108	STORMWATER MANAGEMENT BUDGET	19500.00	DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	207-08264	SUBGRADE TREATMENT, TYPE II	310.00	SYS
0017	207-08268	SUBGRADE TREATMENT, TYPE IV	6320.00	SYS
0018	211-09264	STRUCTURE BACKFILL, TYPE 1	133.00	CYS
0019	214-11796	GEOGRID, TYPE IB	310.00	SYS
0020	303-01180	COMPACTED AGGREGATE, NO. 53	266.00	TON
0021	304-07493	WIDENING WITH HMA, TYPE B	85.00	TON
0022	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	311.00	TON
0023	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	469.00	TON
0024	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	792.00	TON
0025	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	2625.00	TON
0026	401-10258	JOINT ADHESIVE, SURFACE	6143.00	LFT
0027	401-10259	JOINT ADHESIVE, INTERMEDIATE	6143.00	LFT
0028	401-11785	LIQUID ASPHALT SEALANT	6143.00	LFT
0029	406-05520	ASPHALT FOR TACK COAT	6.00	TON
0030	605-06245	CENTER CURB, B CONCRETE	19.00	SYS
0031	616-06451	RIPRAP, UNIFORM	113.00	TON

0032	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	307.00	SYS
0033	621-06574	SODDING	669.00	SYS
0034	628-09401	FIELD OFFICE, TYPE A	10.00	MOS
0035	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	518.00	LFT
0036	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	163.00	LFT
0037	715-05595	PIPE EXTENSION, CIRCULAR, DIAMETER 15 IN.	20.00	LFT
0038	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0039	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00	EACH
0040	716-07631	PIPE INSTALLATION, TRENCHLESS, 15 IN.	78.00	LFT
0041	720-45042	INLET, TYPE HA5	3.00	EACH
0042	720-45410	MANHOLE, TYPE C4	1.00	EACH
0043	720-45415	MANHOLE, TYPE D4	1.00	EACH
0044	725-11028	LINER PIPE, THERMOPLASTIC, CIRCULAR, 1.2-1.4 SFT	75.00	LFT
0045	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	26964.00	LFT
0046	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	57.00	EACH
0047	801-06212	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (ONLY)	15.00	EACH
0048	801-06640	CONSTRUCTION SIGN, TYPE A	105.00	EACH
0049	801-06645	CONSTRUCTION SIGN, TYPE B	16.00	EACH
0050	801-06710	FLASHING ARROW SIGN	280.00	DAY
0051	801-06775	MAINTAINING TRAFFIC	1.00	LS
0052	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	24.00	EACH
0053	801-07118	BARRICADE, TYPE III-A	564.00	LFT
0054	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	5980.00	LFT
0055	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	40.00	EACH
0056	801-94295	SIGNAL HEAD RELOCATE	18.00	EACH
0057	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	398.00	LFT
0058	802-07060	SIGN, SHEET, RELOCATE	100.00	EACH
0059	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	53.00	SFT
0060	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	18.00	SFT
0061	804-11353	LANE SEPARATOR	466.00	LFT
0062	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	5.00	EACH
0063	805-01842	HANDHOLE, SIGNAL, TYPE 1	6.00	EACH
0064	805-01843	HANDHOLE, SIGNAL, ADJUST TO GRADE	4.00	EACH
0065	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	975.00	LFT
0066	805-78225	TRAFFIC SIGNAL HEAD, NO. 4 SECTION, 12 IN.	4.00	EACH
0067	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	7100.00	LFT
0068	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	830.00	LFT

0069	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	250.00	LFT
0070	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	7110.00	LFT
0071	805-78785	SIGNAL DETECTOR HOUSING	12.00	EACH
0072	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	9730.00	LFT
0073	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	202.00	SYS
0074	808-06368	TRANSVERSE MARKING, REMOVE	307.00	LFT
0075	808-06716	LINE, REMOVE	16703.00	LFT
0076	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	1512.00	LFT
0077	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	5008.00	LFT
0078	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	5636.00	LFT
0079	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	5672.00	LFT
0080	808-12032	GROOVING FOR PAVEMENT MARKINGS	23277.00	LFT
0081	808-12781	LINE, MULTI-COMPONENT, SOLID, WHITE, 10 IN.	5329.00	LFT
0082	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	120.00	LFT
0083	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	273.00	LFT
0084	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	1198.00	LFT
0085	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	60.00	LFT
0086	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	23.00	LFT
0087	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	215.00	LFT
0088	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	16.00	EACH
0089	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	111.00	EACH
0090	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	293.00	EACH

Call: 370

Contract: R -44177-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	6.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0013	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00	LS
0014	203-02000	EXCAVATION, COMMON	2255.00	CYS
0015	203-02070	BORROW	1040.00	CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	20856.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	697.00	SYS
0020	207-12635	SUBGRADE TREATMENT, TYPE IBC	7025.00	SYS
0021	211-02050	B BORROW	230.00	CYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	359.00	CYS
0023	214-11796	GEOGRID, TYPE IB	281.00	SYS
0024	301-12234	COMPACTED AGGREGATE, NO. 53	789.00	CYS
0025	302-07455	DENSE GRADED SUBBASE	117.00	CYS
0026	306-08036	MILLING, ASPHALT, 2 IN.	3473.00	SYS
0027	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	991.00	TON
0028	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	913.00	TON
0029	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	913.00	TON
0030	401-10258	JOINT ADHESIVE, SURFACE	1438.00	LFT
0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	563.00	LFT

0032	401-11785	LIQUID ASPHALT SEALANT	1438.00	LFT
0033	401-11787	QC/QA-HMA, 3, 76, INTERMEDIATE, OG, 19.0 mm	835.00	TON
0034	406-05520	ASPHALT FOR TACK COAT	8.00	TON
0035	502-06457	PCCP, 9 IN.	422.00	SYS
0036	502-07757	PCCP, 18 IN.	19.00	SYS
0037	503-05240	D-1 CONTRACTION JOINT	357.00	LFT
0038	604-06070	SIDEWALK, CONCRETE	739.00	SYS
0039	604-08086	CURB RAMP, CONCRETE	146.00	SYS
0040	604-12083	DETECTABLE WARNING SURFACES	36.00	SYS
0041	605-06120	CURB, CONCRETE	206.00	LFT
0042	605-06140	CURB AND GUTTER, CONCRETE	1913.00	LFT
0043	605-06255	CENTER CURB, D CONCRETE	8.00	SYS
0044	605-97937	CURB AND GUTTER, ROLL CURB	313.00	LFT
0045	610-08446	PCCP FOR APPROACHES, 6 IN.	416.00	SYS
0046	610-09108	PCCP FOR APPROACHES, 9 IN.	281.00	SYS
0047	611-08232	MAILBOX ASSEMBLY, RESET, SINGLE	5.00	EACH
0048	615-06490	RIGHT-OF-WAY MARKER	21.00	EACH
0049	615-06505	MONUMENT, TYPE B	4.00	EACH
0050	615-06527	MONUMENT, SECTION CORNER	2.00	EACH
0051	616-03096	RIVER ROCK	14.00	TON
0052	616-06451	RIPRAP, UNIFORM	3.00	TON
0053	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	7.00	SYS
0054	621-06567	WATER	15.00	KGAL
0055	621-06570	TOPSOIL	186.00	CYS
0056	621-06575	SODDING, NURSERY	3579.00	SYS
0057	621-98038	MULCH, HARDWOOD SHREDDED BARK	43.00	CYS
0058	622-04990	LANDSCAPE EDGING	117.00	LFT
0059	622-05640	PLANT, DECIDUOUS SHRUB, 24 IN. TO 36 IN.	48.00	EACH
0060	622-05654	PLANT, PERENNIAL	799.00	EACH
0061	622-05654	PLANT, PERENNIAL	12.00	EACH
0062	628-09403	FIELD OFFICE, TYPE C	6.00	MOS
0063	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0064	628-11977	COMPUTER SYSTEM	1.00	EACH
0065	629-12029	PLANT GROWTH LAYER	3579.00	SYS
0066	715-05032	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	173.00	LFT
0067	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	1415.00	LFT
0068	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	64.00	LFT

0069	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	1012.00	LFT
0070	715-09064	VIDEO INSPECTION FOR PIPE	1185.00	LFT
0071	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0072	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	1479.00	LFT
0073	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	1316.00	SYS
0074	718-52610	AGGREGATE FOR UNDERDRAINS	112.00	CYS
0075	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	2.00	EACH
0076	720-45030	INLET, TYPE E7	3.00	EACH
0077	720-45035	INLET, TYPE F7	3.00	EACH
0078	720-45410	MANHOLE, TYPE C4	6.00	EACH
0079	720-98174	INLET, TYPE B15	7.00	EACH
0080	720-98555	INLET, TYPE C15	5.00	EACH
0081	801-03290	CONSTRUCTION SIGN, TYPE C	3.00	EACH
0082	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.00	EACH
0083	801-06625	DETOUR ROUTE MARKER ASSEMBLY	44.00	EACH
0084	801-06640	CONSTRUCTION SIGN, TYPE A	14.00	EACH
0085	801-06645	CONSTRUCTION SIGN, TYPE B	52.00	EACH
0086	801-06775	MAINTAINING TRAFFIC	1.00	LS
0087	801-07118	BARRICADE, TYPE III-A	168.00	LFT
0088	801-07119	BARRICADE, TYPE III-B	192.00	LFT
0089	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	96.00	LFT
0090	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	288.00	LFT
0091	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	76.00	LFT
0092	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	180.00	SFT
0093	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	60.00	SFT
0094	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	39.00	SFT
0095	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0096	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	11.00	EACH
0097	805-06742	SOLAR POWERED FLASHING BEACON ASSEMBLY	10.00	EACH
0098	805-06742	SOLAR POWERED FLASHING BEACON ASSEMBLY	1.00	EACH
0099	805-11771	SIGNAL POLE, PEDESTAL, 16 FT	10.00	EACH
0100	807-02191	HANDHOLE, LIGHTING	3.00	EACH
0101	807-02194	SERVICE POINT, II, MODIFIED	1.00	EACH
0102	807-03950	LUMINAIRE, ORNAMENTAL	4.00	EACH
0103	807-03951	LIGHT POLE, ORNAMENTAL	4.00	EACH
0104	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	301.00	LFT
0105	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE, WITH GROUNDING	4.00	EACH

0106	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	611.00	LFT
0107	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	440.00	LFT
0108	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	303.00	LFT
0109	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1325.00	LFT
0110	808-06716	LINE, REMOVE	114.00	LFT
0111	808-11478	LINE, THERMOPLASTIC, DOTTED, WHITE, 8 IN.	198.00	LFT
0112	808-11691	LINE, THERMOPLASTIC, DOTTED, WHITE, 12 IN.	148.00	LFT
0113	808-11698	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 27 IN.	99.00	LFT
0114	808-12032	GROOVING FOR PAVEMENT MARKINGS	7922.00	LFT
0115	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	6295.00	LFT
0116	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	23.00	EACH
0117	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	1.00	EACH
0118	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	54.00	EACH

Call: 390

Contract: R -44208-A

Section No.: 1 ASPHALT RESURFACE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	202-02240	PAVEMENT REMOVAL	47.00	SYS
	0012	202-02278	CURB, CONCRETE, REMOVE	126.00	LFT
	0013	202-02279	CURB AND GUTTER, REMOVE	102.00	LFT
	0014	202-52710	SIDEWALK CONCRETE, REMOVE	120.00	SYS
	0015	203-02070	BORROW	121.00	CYS
	0016	205-12108	STORMWATER MANAGEMENT BUDGET	2000.00	DOL
	0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0018	207-09935	SUBGRADE TREATMENT, TYPE IC	162.00	SYS
	0019	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	143.00	TON
	0020	304-12624	HMA PATCHING, PARTIAL DEPTH, TYPE B	259.00	TON
	0021	306-08034	MILLING, ASPHALT, 1 1/2 IN.	32397.00	SYS
	0022	306-08042	MILLING, SCARIFICATION	2426.00	SYS
	0023	306-08159	MILLING, ASPHALT	420.00	SYS
	0024	306-08432	MILLING, APPROACH	1446.00	SYS
	0025	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2673.00	TON
	0026	401-10258	JOINT ADHESIVE, SURFACE	20278.00	LFT
	0027	401-11785	LIQUID ASPHALT SEALANT	20278.00	LFT
	0028	406-05520	ASPHALT FOR TACK COAT	13.00	TON
	0029	604-05528	HMA FOR SIDEWALK	201.00	TON
	0030	604-06070	SIDEWALK, CONCRETE	27.00	SYS
	0031	604-08086	CURB RAMP, CONCRETE	92.00	SYS

0032	604-12083	DETECTABLE WARNING SURFACES	13.00	SYS
0033	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	3.00	SYS
0034	605-06120	CURB, CONCRETE	91.00	LFT
0035	605-06125	CURB, CONCRETE, MODIFIED	597.00	LFT
0036	605-06140	CURB AND GUTTER, CONCRETE	102.00	LFT
0037	605-06210	CENTER CURB, C CONCRETE	7.00	LFT
0038	610-07487	HMA FOR APPROACHES, TYPE B	120.00	TON
0039	615-06505	MONUMENT, TYPE B	6.00	EACH
0040	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0041	621-06560	MULCHED SEEDING, TYPE U	91.00	SYS
0042	621-06567	WATER	2.00	KGAL
0043	621-06570	TOPSOIL	73.00	CYS
0044	621-06574	SODDING	433.00	SYS
0045	628-09401	FIELD OFFICE, TYPE A	12.00	MOS
0046	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0047	720-01355	INLET, CLEAN EXISTING	13.00	EACH
0048	720-12797	CASTING, INLET, ADJUST TO GRADE	3.00	EACH
0049	720-44055	CASTING, TYPE 10, FURNISH AND ADJUST TO GRADE	2.00	EACH
0050	801-03291	CONSTRUCTION SIGN, TYPE D	3.00	EACH
0051	801-06640	CONSTRUCTION SIGN, TYPE A	19.00	EACH
0052	801-06645	CONSTRUCTION SIGN, TYPE B	37.00	EACH
0053	801-06775	MAINTAINING TRAFFIC	1.00	LS
0054	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	23.00	SYS
0055	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	77.00	LFT
0056	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	1.00	EACH
0057	805-10107	WIRELESS MAGNETOMETER DETECTOR	7.00	EACH
0058	808-02977	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	44.00	EACH
0059	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	1905.00	LFT
0060	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	6985.00	LFT
0061	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0062	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	779.00	LFT
0063	808-12032	GROOVING FOR PAVEMENT MARKINGS	18982.00	LFT
0064	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1233.00	LFT
0065	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	8080.00	LFT
0066	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	124.00	LFT
0067	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	204.00	LFT
0068	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	20.00	EACH

0069	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	18.00 EACH
0070	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	342.00 EACH
0071	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	346.00 EACH

Call: 400

Contract: R -44889-A

Section No.: 1 PAVEMENT PATCHING

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
	0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0008	202-02240	PAVEMENT REMOVAL	2494.00	SYS
	0009	207-09895	SUBGRADE TREATMENT, TYPE V	2494.00	SYS
	0010	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	2744.00	TON
	0011	304-12626	HMA PATCHING, PARTIAL DEPTH, TYPE C	146.00	TON
	0012	305-12695	LEAN CONCRETE BASE, 9 IN.	2494.00	SYS
	0013	401-11785	LIQUID ASPHALT SEALANT	6346.00	LFT
	0014	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
	0015	628-12683	FIELD OFFICE, TYPE D	5.00	MOS
	0016	801-03290	CONSTRUCTION SIGN, TYPE C	2.00	EACH
	0017	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	58986.00	LFT
	0018	801-06640	CONSTRUCTION SIGN, TYPE A	33.00	EACH
	0019	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	EACH
	0020	801-06775	MAINTAINING TRAFFIC	1.00	LS
	0021	808-06716	LINE, REMOVE	39655.00	LFT
	0022	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
	0023	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	18599.00	LFT
	0024	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	18992.00	LFT
	0025	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	4748.00	LFT

Call: 410

Contract: R -44923-A

Section No.: 1 NOISE ABATEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0008	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
	0009	202-01000	STRUCTURES AND OBSTRUCTIONS, REMOVE	1.00	LS
	0010	203-02000	EXCAVATION, COMMON	10.00	CYS
	0011	203-02070	BORROW	5.00	CYS
	0012	205-12108	STORMWATER MANAGEMENT BUDGET	2800.00	DOL
	0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0014	303-01180	COMPACTED AGGREGATE, NO. 53	18.00	TON
	0015	601-06035	GUARDRAIL, RESET	75.00	LFT
	0016	620-01754	SOUND BARRIER PANELS, GROUND MOUNTED TYPE	555.00	SFT
	0017	620-01756	SOUND BARRIER ERECTION, GROUND MOUNTED TYPE	555.00	SFT
	0018	620-08426	SOUND BARRIER DESIGN AND LAYOUT	1.00	LS
	0019	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
	0020	621-06560	MULCHED SEEDING, TYPE U	300.00	SYS
	0021	621-06567	WATER	1.00	KGAL
	0022	628-09403	FIELD OFFICE, TYPE C	6.00	MOS
	0023	628-09409	MOBILE INTERNET SERVICE	6.00	MOS
	0024	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
	0025	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
	0026	628-11977	COMPUTER SYSTEM	1.00	EACH
	0027	628-12923	CELLULAR TELEPHONE SERVICE, UNLIMITED MINUTES	6.00	MOS
	0028	801-06640	CONSTRUCTION SIGN, TYPE A	17.00	EACH
	0029	801-06645	CONSTRUCTION SIGN, TYPE B	1.00	EACH
	0030	801-06775	MAINTAINING TRAFFIC	1.00	LS
	0031	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	1.00	EACH

0032	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2
0033	801-12042	TRUCK MOUNTED ATTENUATOR

465.00	LFT
2.00	DAY

Call: 420

Contract: R -45025-A

Section No.: 1 INTERSECTION IMPROVEMENT WITH ADDED TURN LANES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02273	CENTER CURB, CONCRETE, REMOVE	106.00	SYS
0013	202-02279	CURB AND GUTTER, REMOVE	807.00	LFT
0014	202-52710	SIDEWALK CONCRETE, REMOVE	662.00	SYS
0015	202-74035	SIGN, REMOVE	2.00	EACH
0016	202-90277	DETECTOR HOUSING, REMOVE	2.00	EACH
0017	202-91385	INLET, REMOVE	6.00	EACH
0018	203-02000	EXCAVATION, COMMON	870.00	CYS
0019	203-02070	BORROW	11.00	CYS
0020	205-12108	STORMWATER MANAGEMENT BUDGET	6161.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	207-09935	SUBGRADE TREATMENT, TYPE IC	2066.00	SYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	92.00	CYS
0024	304-07494	WIDENING WITH HMA, TYPE C	56.00	TON
0025	306-11872	MILLING, PROFILE	2357.00	SYS
0026	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	346.00	TON
0027	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	565.00	TON
0028	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	771.00	TON
0029	401-10258	JOINT ADHESIVE, SURFACE	4173.00	LFT
0030	401-10259	JOINT ADHESIVE, INTERMEDIATE	4173.00	LFT
0031	401-11785	LIQUID ASPHALT SEALANT	4173.00	LFT

0032	406-05520	ASPHALT FOR TACK COAT	5.00 TON
0033	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00 TON
0034	604-06070	SIDEWALK, CONCRETE	434.00 SYS
0035	604-08086	CURB RAMP, CONCRETE	37.00 SYS
0036	604-12083	DETECTABLE WARNING SURFACES	7.00 SYS
0037	605-06140	CURB AND GUTTER, CONCRETE	801.00 LFT
0038	621-06560	MULCHED SEEDING, TYPE U	184.00 SYS
0039	715-05148	PIPE, TYPE 2, CIRCULAR, DIAMETER 10 IN.	277.00 LFT
0040	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	70.00 LFT
0041	720-45070	INLET, TYPE P12A	1.00 EACH
0042	720-45410	MANHOLE, TYPE C4	1.00 EACH
0043	720-98174	INLET, TYPE B15	5.00 EACH
0044	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	9.00 EACH
0045	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	18663.00 LFT
0046	801-06640	CONSTRUCTION SIGN, TYPE A	33.00 EACH
0047	801-06645	CONSTRUCTION SIGN, TYPE B	29.00 EACH
0048	801-06710	FLASHING ARROW SIGN	45.00 DAY
0049	801-06775	MAINTAINING TRAFFIC	1.00 LS
0050	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	4.00 EACH
0051	801-07118	BARRICADE, TYPE III-A	56.00 LFT
0052	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	3750.00 LFT
0053	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	8.00 EACH
0054	802-03783	SIGN, PANEL, REMOVE	1.00 EACH
0055	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	12.00 LFT
0056	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	22.00 LFT
0057	802-07057	SIGN, PANEL, WITH LEGEND	233.00 SFT
0058	802-07060	SIGN, SHEET, RELOCATE	4.00 EACH
0059	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	9.00 SFT
0060	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	19.00 SFT
0061	805-01828	TRAFFIC SIGNAL HEAD, REALIGN	2.00 EACH
0062	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	90.00 LFT
0063	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	2.00 EACH
0064	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	803.00 LFT
0065	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	199.00 LFT
0066	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	161.00 LFT
0067	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	90.00 LFT
0068	805-78785	SIGNAL DETECTOR HOUSING	2.00 EACH

0069	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	295.00	LFT
0070	808-06609	PAVEMENT MESSAGE MARKING	2.00	EACH
0071	808-06609	PAVEMENT MESSAGE MARKING	2.00	EACH
0072	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	2094.00	LFT
0073	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	1233.00	LFT
0074	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	113.00	LFT
0075	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	84.00	LFT
0076	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	71.00	LFT
0077	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	6.00	EACH
0078	808-96075	LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN.	388.00	LFT

Call: 460

Contract: B -41404-A

Section No.: 1 BRIDGE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	5408.00	SYS
0014	202-02637	PIPE ABANDON AND GROUT FILL	80.00	LFT
0015	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0016	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0017	202-91385	INLET, REMOVE	20.00	EACH
0018	202-96133	PIPE, REMOVE	758.00	LFT
0019	202-99187	FENCE, FARM FIELD, REMOVE	550.00	LFT
0020	203-02000	EXCAVATION, COMMON	21930.00	CYS
0021	203-02070	BORROW	5030.00	CYS
0022	205-11626	PUMP AROUND	2.00	EACH
0023	205-12108	STORMWATER MANAGEMENT BUDGET	97423.00	DOL
0024	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0025	205-12618	SWQCP PREPARATION	1.00	LS
0026	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	385.00	CYS
0027	207-08264	SUBGRADE TREATMENT, TYPE II	321.00	SYS
0028	207-09935	SUBGRADE TREATMENT, TYPE IC	16586.00	SYS
0029	207-12635	SUBGRADE TREATMENT, TYPE IBC	12058.00	SYS
0030	211-02050	B BORROW	8.00	CYS
0031	211-06467	AGGREGATE FOR END BENT BACKFILL	124.00	CYS

0032	211-09265	STRUCTURE BACKFILL, TYPE 2	185.00	CYS
0033	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	40.00	CYS
0034	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	9969.00	SYS
0035	301-12231	COMPACTED AGGREGATE, NO. 2	91.00	CYS
0036	301-12234	COMPACTED AGGREGATE, NO. 53	2611.00	CYS
0037	302-06464	SUBBASE FOR PCCP	156.00	CYS
0038	303-01180	COMPACTED AGGREGATE, NO. 53	7013.00	TON
0039	306-08034	MILLING, ASPHALT, 1 1/2 IN.	670.00	SYS
0040	306-08043	MILLING, TRANSITION	1817.00	SYS
0041	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	1775.00	TON
0042	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	2747.00	TON
0043	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	12707.00	TON
0044	401-10258	JOINT ADHESIVE, SURFACE	12011.00	LFT
0045	401-10259	JOINT ADHESIVE, INTERMEDIATE	15529.00	LFT
0046	401-11785	LIQUID ASPHALT SEALANT	12011.00	LFT
0047	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	1250.00	TON
0048	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0049	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	6106.00	LFT
0050	402-10084	HMA FOR TEMPORARY PAVEMENT, TYPE B	265.00	TON
0051	402-10086	HMA FOR TEMPORARY PAVEMENT, TYPE C	3639.00	TON
0052	406-05520	ASPHALT FOR TACK COAT	30.00	TON
0053	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0054	502-06329	PCCP, 12 IN.	64.00	SYS
0055	502-06331	PCCP, 14 IN.	486.00	SYS
0056	503-05240	D-1 CONTRACTION JOINT	48.00	LFT
0057	503-12477	TERMINAL JOINT, TYPE HMA	158.00	LFT
0058	601-02241	GUARDRAIL, REMOVE	3475.00	LFT
0059	601-06234	IMPACT ATTENUATOR, R1-W1, TL-2	2.00	EACH
0060	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	2138.00	LFT
0061	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED, 6 FT 3 IN. SPACING	376.00	LFT
0062	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	4.00	EACH
0063	601-12291	GUARDRAIL TRANSITION, MGS WITH CURB	1.00	EACH
0064	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	7.00	EACH
0065	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00	EACH
0066	601-94690	GUARDRAIL END TREATMENT, TYPE MS	2.00	EACH
0067	602-06729	BARRIER DELINEATOR	28.00	EACH
0068	603-06040	FENCE, FARM FIELD, 47 IN.	838.00	LFT

0069	605-06125	CURB, CONCRETE, MODIFIED	1.00	LFT
0070	605-06145	CURB AND GUTTER, TYPE B, CONCRETE	180.00	LFT
0071	605-06245	CENTER CURB, B CONCRETE	58.00	SYS
0072	605-08636	CURB AND GUTTER, TURNOUT COMBINED	5.00	LFT
0073	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	700.00	SYS
0074	610-07487	HMA FOR APPROACHES, TYPE B	75.00	TON
0075	615-06490	RIGHT-OF-WAY MARKER	9.00	EACH
0076	615-06505	MONUMENT, TYPE B	11.00	EACH
0077	615-06510	MONUMENT, TYPE C	4.00	EACH
0078	616-05688	RIPRAP, CLASS 1	8.00	TON
0079	616-06405	RIPRAP, REVETMENT	1221.00	TON
0080	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	1810.00	SYS
0081	616-51367	SLOPEWALL, CONCRETE, 4 IN.	1992.00	SYS
0082	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0083	621-02770	EROSION CONTROL BLANKET	9745.00	SYS
0084	621-06545	FERTILIZER	2.00	TON
0085	621-06554	SEED MIXTURE, TYPE U	922.00	LBS
0086	621-06560	MULCHED SEEDING, TYPE U	26995.00	SYS
0087	621-06565	MULCHING MATERIAL	10.00	TON
0088	621-06567	WATER	43.00	KGAL
0089	621-06574	SODDING	7697.00	SYS
0090	621-07657	FIBER MAT, COCONUT	788.00	SYS
0091	621-12612	SEED MIXTURE, FLOODPLAIN	11.00	LBS
0092	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0093	628-12683	FIELD OFFICE, TYPE D	36.00	MOS
0094	629-12029	PLANT GROWTH LAYER	13000.00	SYS
0095	701-02938	CORED HOLE IN ROCK, DIAMETER 24 IN.	96.00	LFT
0096	701-06011	DYNAMIC PILE LOAD TEST	4.00	EACH
0097	701-09557	TEST PILE, DYNAMIC, PRODUCTION	225.00	LFT
0098	701-09559	TEST PILE, DYNAMIC, RESTRIKE	4.00	EACH
0099	701-51195	PILE, STEEL H, HP 12 X 53	1281.00	LFT
0100	702-51005	CONCRETE, A, SUBSTRUCTURE	265.50	CYS
0101	702-92857	CONCRETE, C, SUBSTRUCTURE	137.40	CYS
0102	703-06028	REINFORCING BARS	117644.00	LBS
0103	703-06029	REINFORCING BARS, EPOXY COATED	350061.00	LBS
0104	704-51002	CONCRETE, C, SUPERSTRUCTURE	828.60	CYS
0105	706-11601	RAILING, CONCRETE TYPE FT	112.80	CYS

0106	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFT	8.00 EACH
0107	707-08158	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 42 IN. X 49 IN.	2286.00 LFT
0108	709-51821	SURFACE SEAL	1.00 LS
0109	709-51821	SURFACE SEAL	1.00 LS
0110	715-04482	PIPE CONNECTION COLLAR AND PAD	1.00 EACH
0111	715-04596	WATER SERVICE	1.00 EACH
0112	715-04837	PLUG	2.00 EACH
0113	715-04837	PLUG	1.00 EACH
0114	715-04964	WATER MAIN	236.00 LFT
0115	715-04987	CONNECTION	2.00 EACH
0116	715-04987	CONNECTION	2.00 EACH
0117	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	6527.00 LFT
0118	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	1806.00 LFT
0119	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	432.00 LFT
0120	715-05118	PIPE, TYPE 1, CIRCULAR, DIAMETER 12 IN.	321.00 LFT
0121	715-05119	PIPE, TYPE 1, CIRCULAR, DIAMETER 15 IN.	60.00 LFT
0122	715-05123	PIPE, TYPE 1, CIRCULAR, DIAMETER 24 IN.	87.00 LFT
0123	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	392.00 LFT
0124	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	149.00 LFT
0125	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	180.00 LFT
0126	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	308.00 LFT
0127	715-05422	PIPE, SLOTTED DRAIN, DIAMETER 12 IN.	1748.00 LFT
0128	715-08560	GRATED BOX END SECTION TYPE II, 3:1, DIAMETER 15 IN.	4.00 EACH
0129	715-09064	VIDEO INSPECTION FOR PIPE	4866.00 LFT
0130	715-09843	BYPASS PUMPING	1.00 LS
0131	715-11360	INSERTION VALVE 12 IN.	2.00 EACH
0132	715-12406	VALVE WITH BOX, TAPPING SLEEVE	2.00 EACH
0133	715-12406	VALVE WITH BOX, TAPPING SLEEVE	1.00 EACH
0134	715-46000	PIPE END SECTION, DIAMETER 12 IN.	4.00 EACH
0135	715-46005	PIPE END SECTION, DIAMETER 15 IN.	3.00 EACH
0136	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00 EACH
0137	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00 EACH
0138	715-90853	TAPPING SLEEVE WITH VALVE	2.00 EACH
0139	715-93913	WATER MAIN, 8 IN.	136.00 LFT
0140	715-93913	WATER MAIN, 8 IN.	236.00 LFT
0141	715-98165	WATER MAIN, 12 IN.	168.00 LFT
0142	715-98165	WATER MAIN, 12 IN.	400.00 LFT

0143	715-98961	FORCE MAIN	403.00	LFT
0144	715-98961	FORCE MAIN	30.00	LFT
0145	715-98961	FORCE MAIN	540.00	LFT
0146	715-98961	FORCE MAIN	303.00	LFT
0147	715-98961	FORCE MAIN	403.00	LFT
0148	716-07630	PIPE INSTALLATION, TRENCHLESS, 12 IN.	264.00	LFT
0149	716-07631	PIPE INSTALLATION, TRENCHLESS, 15 IN.	32.00	LFT
0150	716-07632	PIPE INSTALLATION, TRENCHLESS, 18 IN.	79.00	LFT
0151	718-06528	OUTLET PROTECTOR, TYPE 1	3.00	EACH
0152	718-06531	OUTLET PROTECTOR, TYPE 3	3.00	EACH
0153	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	7031.00	SYS
0154	718-52610	AGGREGATE FOR UNDERDRAINS	732.00	CYS
0155	720-02442	PIPE, PLUG EXISTING	1.00	EACH
0156	720-45069	INLET, TYPE P12	5.00	EACH
0157	720-45070	INLET, TYPE P12A	5.00	EACH
0158	720-45410	MANHOLE, TYPE C4	1.00	EACH
0159	720-95310	INLET, TYPE P12A, MODIFIED	5.00	EACH
0160	728-11672	DRILLED SHAFT EXPLORATORY CORE	800.00	LFT
0161	728-11673	DRILLED SHAFT PERMANENT CASING	384.00	LFT
0162	728-11863	DRILLED SHAFT, DIAMETER 54 IN.	560.00	LFT
0163	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	16.00	EACH
0164	801-03290	CONSTRUCTION SIGN, TYPE C	2.00	EACH
0165	801-04308	ROAD CLOSURE SIGN ASSEMBLY	1.00	EACH
0166	801-06199	ROAD CLOSURE SIGN ASSEMBLY, PERMANENT	1.00	EACH
0167	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	32798.00	LFT
0168	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	29268.00	LFT
0169	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	8271.00	LFT
0170	801-06625	DETOUR ROUTE MARKER ASSEMBLY	15.00	EACH
0171	801-06640	CONSTRUCTION SIGN, TYPE A	97.00	EACH
0172	801-06645	CONSTRUCTION SIGN, TYPE B	5.00	EACH
0173	801-06710	FLASHING ARROW SIGN	600.00	DAY
0174	801-06775	MAINTAINING TRAFFIC	1.00	LS
0175	801-07118	BARRICADE, TYPE III-A	294.00	LFT
0176	801-07119	BARRICADE, TYPE III-B	12.00	LFT
0177	801-07606	TEMPORARY CROSSEVER DRAINAGE PIPE	1198.00	LFT
0178	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	992.00	LFT
0179	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH

0180	801-12031	TEMPORARY PORTABLE RUMBLE STRIPS	540.00	DAY
0181	801-12042	TRUCK MOUNTED ATTENUATOR	112.00	DAY
0182	801-12324	LAW ENFORCEMENT OFFICER	672.00	HRS
0183	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	28.00	EACH
0184	801-52817	TEMPORARY CROSSOVER, TYPE B	2.00	EACH
0185	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	495.00	LFT
0186	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	52.00	LFT
0187	802-05703	SIGN POST, SQUARE, TYPE 3, REINFORCED ANCHOR BASE	94.00	LFT
0188	802-07057	SIGN, PANEL, WITH LEGEND	104.00	SFT
0189	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	13.00	EACH
0190	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	68.00	SFT
0191	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	467.00	SFT
0192	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	110.00	SFT
0193	802-12223	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, TYPE B	4.00	EACH
0194	802-76095	STRUCTURAL STEEL, BREAKAWAY	1430.00	LBS
0195	804-06770	DELINEATOR POST	6.00	EACH
0196	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0197	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0198	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	4.00	EACH
0199	805-06742	SOLAR POWERED FLASHING BEACON ASSEMBLY	4.00	EACH
0200	805-09451	SIGNAL POLE, PEDESTAL, 15 FT	4.00	EACH
0201	807-02191	HANDHOLE, LIGHTING	4.00	EACH
0202	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	433.00	LFT
0203	807-12199	LUMINAIRE, HIGH LUMEN ROADWAY	20.00	EACH
0204	807-12343	CABLE, POLE CIRCUIT, XHHW, NO. 10 COPPER, STRANDED, 1/C	2310.00	LFT
0205	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE, WITH GROUNDING	20.00	EACH
0206	807-84762	LIGHT POLE, 40 FT E.M.H., 15 FT MAST ARM, BREAKAWAY BASE	12.00	EACH
0207	807-85752	LIGHT POLE, 40 FT E.M.H., 10 FT MAST ARM, BREAKAWAY BASE	8.00	EACH
0208	807-86805	SERVICE POINT, TYPE I	1.00	EACH
0209	807-86910	CONNECTOR KIT, UNFUSED	20.00	EACH
0210	807-86915	CONNECTOR KIT, FUSED	20.00	EACH
0211	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	48.00	EACH
0212	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	12.00	EACH
0213	807-86930	INSULATION LINK, NON-WATERPROOFED	40.00	EACH
0214	807-86935	INSULATION LINK, WATERPROOFED	12.00	EACH
0215	807-86950	SIGN, UNDERPASS, AND ROADWAY LIGHTING, LOCATION IDENTIFICATION	20.00	EACH
0216	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	4186.00	LFT

0217	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1960.00	LFT
0218	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	893.00	LFT
0219	808-06716	LINE, REMOVE	8271.00	LFT
0220	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0221	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	2660.00	LFT
0222	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	6940.00	LFT
0223	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	1050.00	LFT
0224	808-12032	GROOVING FOR PAVEMENT MARKINGS	19193.00	LFT
0225	808-12667	LINE, THERMOPLASTIC, SOLID, WHITE, 10 IN.	3931.00	LFT
0226	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	4819.00	LFT
0227	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2121.00	LFT
0228	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	4383.00	LFT
0229	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	283.00	LFT
0230	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	84.00	LFT
0231	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	206.00	LFT
0232	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	124.00	LFT
0233	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	31.00	EACH
0234	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	2.00	EACH
0235	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	114.00	EACH
0236	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	188.00	EACH
0237	808-96075	LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN.	1086.00	LFT

Call: 490

Contract: B -41923-A

Section No.: 1

BRIDGE REHABILITATION OR REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	28.00	SYS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0013	202-94810	CURB TURNOUT, REMOVE	2.00	EACH
0014	203-02000	EXCAVATION, COMMON	215.00	CYS
0015	203-02070	BORROW	870.00	CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	13067.05	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	206-51215	EXCAVATION, X	2.00	CYS
0019	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	26.00	CYS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	832.00	SYS
0021	207-08266	SUBGRADE TREATMENT, TYPE III	90.00	SYS
0022	207-12498	SUBGRADE TREATMENT, TYPE ID	84.00	SYS
0023	211-06467	AGGREGATE FOR END BENT BACKFILL	16.00	CYS
0024	211-09268	STRUCTURE BACKFILL, TYPE 5	28.00	CYS
0025	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	35.00	SYS
0026	302-06464	SUBBASE FOR PCCP	9.00	CYS
0027	303-07449	COMPACTED AGGREGATE, NO. 73	31.00	TON
0028	306-11872	MILLING, PROFILE	140.00	SYS
0029	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	87.00	TON
0030	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	107.00	TON
0031	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	266.00	TON

0032	401-10258	JOINT ADHESIVE, SURFACE	1291.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	1021.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	1291.00	LFT
0035	406-05521	ASPHALT FOR TACK COAT	2528.00	SYS
0036	601-01846	GUARDRAIL TERMINAL SYSTEM, W-BEAM CURVED, TYPE 3	1.00	EACH
0037	601-04150	GUARDRAIL, THRIE-BEAM, 6 FT 3 IN. SPACING	18.00	LFT
0038	601-06037	GUARDRAIL END TREATMENT, TYPE I	1.00	EACH
0039	601-06374	GUARDRAIL TRANSITION, TYPE TGS-1	2.00	EACH
0040	601-06374	GUARDRAIL TRANSITION, TYPE TGS-1	2.00	EACH
0041	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00	EACH
0042	605-02278	CURB, REMOVE	10.00	LFT
0043	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	38.00	SYS
0044	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0045	615-06490	RIGHT-OF-WAY MARKER	16.00	EACH
0046	615-06505	MONUMENT, TYPE B	2.00	EACH
0047	616-05688	RIPRAP, CLASS 1	445.00	TON
0048	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	495.00	SYS
0049	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0050	621-02770	EROSION CONTROL BLANKET	692.00	SYS
0051	621-06559	MULCHED SEEDING, TYPE R	1051.00	SYS
0052	621-12612	SEED MIXTURE, FLOODPLAIN	5.00	LBS
0053	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0054	628-12683	FIELD OFFICE, TYPE D	12.00	MOS
0055	702-02925	WATERPROOFING MEMBRANE SYSTEM	485.00	SFT
0056	702-51005	CONCRETE, A, SUBSTRUCTURE	5.30	CYS
0057	702-51015	CONCRETE, B, FOOTINGS	7.30	CYS
0058	702-51863	FIELD DRILLED HOLE IN CONCRETE	103.00	EACH
0059	703-06028	REINFORCING BARS	1500.00	LBS
0060	703-06029	REINFORCING BARS, EPOXY COATED	9474.00	LBS
0061	704-51002	CONCRETE, C, SUPERSTRUCTURE	76.20	CYS
0062	706-06344	RAILING, STEEL TYPE TS-1	241.00	LFT
0063	707-07776	STRUCTURAL MEMBER, CONCRETE, BOX BEAM, 21 IN. X 36 IN.	129.00	LFT
0064	707-11494	STRUCTURAL MEMBER, CONCRETE, BOX BEAM, 21 IN. X 48 IN.	770.00	LFT
0065	709-51821	SURFACE SEAL	1.00	LS
0066	710-09158	PATCHING CONCRETE STRUCTURES	10.00	SFT
0067	710-51870	REPOINTING MASONRY IN STRUCTURES	75.00	SFT
0068	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	56.00	LFT

0069	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	47.00	SYS
0070	722-12732	LONGITUDINAL GROOVING	418.00	SYS
0071	724-12773	BRIDGE EXPANSION JOINT, TYPE PCF	55.00	LFT
0072	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0073	801-06625	DETOUR ROUTE MARKER ASSEMBLY	26.00	EACH
0074	801-06640	CONSTRUCTION SIGN, TYPE A	11.00	EACH
0075	801-06645	CONSTRUCTION SIGN, TYPE B	8.00	EACH
0076	801-06775	MAINTAINING TRAFFIC	1.00	LS
0077	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0078	801-07119	BARRICADE, TYPE III-B	48.00	LFT
0079	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	32.00	LFT
0080	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	13.00	SFT
0081	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	16.00	SFT

Call: 500

Contract: B -42004-A

Section No.: 1 BRIDGE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
	0011	202-06542	RELOCATE	1.00	EACH
	0012	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
	0013	203-02000	EXCAVATION, COMMON	1196.00	CYS
	0014	203-02070	BORROW	4528.00	CYS
	0015	203-51223	EXCAVATION, WATERWAY	502.00	CYS
	0016	205-12108	STORMWATER MANAGEMENT BUDGET	39959.00	DOL
	0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0018	205-12618	SWQCP PREPARATION	1.00	LS
	0019	206-51220	EXCAVATION, WET	101.00	CYS
	0020	206-51235	COFFERDAM	1.00	LS
	0021	207-09935	SUBGRADE TREATMENT, TYPE IC	1871.00	SYS
	0022	211-02050	B BORROW	530.00	CYS
	0023	211-06467	AGGREGATE FOR END BENT BACKFILL	60.00	CYS
	0024	211-09264	STRUCTURE BACKFILL, TYPE 1	94.00	CYS
	0025	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	128.00	SYS
	0026	301-12234	COMPACTED AGGREGATE, NO. 53	17.00	CYS
	0027	302-06464	SUBBASE FOR PCCP	32.00	CYS
	0028	303-01180	COMPACTED AGGREGATE, NO. 53	14.00	TON
	0029	306-08043	MILLING, TRANSITION	177.00	SYS
	0030	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	148.00	TON
	0031	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	311.00	TON

0032	401-10258	JOINT ADHESIVE, SURFACE	696.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	596.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	696.00	LFT
0035	406-05521	ASPHALT FOR TACK COAT	1780.00	SYS
0036	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0037	601-06374	GUARDRAIL TRANSITION, TYPE TGS-1	4.00	EACH
0038	601-94689	GUARDRAIL END TREATMENT, TYPE OS	4.00	EACH
0039	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	130.00	SYS
0040	615-06527	MONUMENT, SECTION CORNER	1.00	EACH
0041	616-06405	RIPRAP, REVETMENT	711.00	TON
0042	616-06451	RIPRAP, UNIFORM	81.00	TON
0043	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	1371.00	SYS
0044	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0045	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0046	619-51859	COAT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0047	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0048	621-06559	MULCHED SEEDING, TYPE R	267.00	SYS
0049	621-06565	MULCHING MATERIAL	3.00	TON
0050	621-06567	WATER	1.00	KGAL
0051	621-06574	SODDING	104.00	SYS
0052	621-12612	SEED MIXTURE, FLOODPLAIN	69.00	LBS
0053	621-52448	SIGN, "DO NOT SPRAY"	8.00	EACH
0054	621-98038	MULCH, HARDWOOD SHREDDED BARK	14.00	CYS
0055	628-09403	FIELD OFFICE, TYPE C	13.00	MOS
0056	701-02938	CORED HOLE IN ROCK, DIAMETER 24 IN.	213.00	LFT
0057	701-09558	TEST PILE, INDICATOR, PRODUCTION	271.00	LFT
0058	701-09560	TEST PILE, INDICATOR, RESTRIKE	5.00	EACH
0059	701-09683	PILE SHOE, HP 12 X 74	21.00	EACH
0060	701-95780	PILE, STEEL H, HP 12 X 74	620.00	LFT
0061	702-51005	CONCRETE, A, SUBSTRUCTURE	61.60	CYS
0062	702-92857	CONCRETE, C, SUBSTRUCTURE	56.30	CYS
0063	703-06028	REINFORCING BARS	12807.00	LBS
0064	703-06029	REINFORCING BARS, EPOXY COATED	38159.00	LBS
0065	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	66.00	EACH
0066	704-51002	CONCRETE, C, SUPERSTRUCTURE	169.10	CYS
0067	706-06344	RAILING, STEEL TYPE TS-1	213.00	LFT
0068	707-07776	STRUCTURAL MEMBER, CONCRETE, BOX BEAM, 21 IN. X 36 IN.	402.00	LFT

0069	711-12147	SUPERSTRUCTURE INSTALLATION	1.00	LS
0070	711-91996	REPAIR EXISTING STRUCTURE	1.00	LS
0071	712-05854	BRIDGE DECK	1.00	LS
0072	715-05127	PIPE, TYPE 1, CIRCULAR, DIAMETER 42 IN.	86.00	LFT
0073	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	85.00	LFT
0074	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	224.00	LFT
0075	715-05842	CONCRETE ANCHOR, DIAMETER 42 IN.	2.00	EACH
0076	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0077	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	179.00	SYS
0078	722-12732	LONGITUDINAL GROOVING	376.00	SYS
0079	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0080	801-06625	DETOUR ROUTE MARKER ASSEMBLY	16.00	EACH
0081	801-06640	CONSTRUCTION SIGN, TYPE A	10.00	EACH
0082	801-06775	MAINTAINING TRAFFIC	1.00	LS
0083	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0084	801-07119	BARRICADE, TYPE III-B	48.00	LFT
0085	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1580.00	LFT
0086	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1580.00	LFT

Call: 504

Contract: B -42063-A

Section No.: 1 BRIDGE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0012	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0013	203-02000	EXCAVATION, COMMON	613.00	CYS
0014	203-51223	EXCAVATION, WATERWAY	28.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	20000.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	206-51220	EXCAVATION, WET	216.00	CYS
0018	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	114.00	CYS
0019	206-51235	COFFERDAM	1.00	LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	152.00	SYS
0021	207-08266	SUBGRADE TREATMENT, TYPE III	1634.00	SYS
0022	211-06467	AGGREGATE FOR END BENT BACKFILL	52.00	CYS
0023	214-11796	GEOGRID, TYPE IB	1634.00	SYS
0024	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	200.00	SYS
0025	301-12234	COMPACTED AGGREGATE, NO. 53	839.00	CYS
0026	302-06464	SUBBASE FOR PCCP	50.00	CYS
0027	302-07455	DENSE GRADED SUBBASE	8.00	CYS
0028	303-01180	COMPACTED AGGREGATE, NO. 53	148.00	TON
0029	306-08043	MILLING, TRANSITION	317.00	SYS
0030	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	156.00	TON
0031	401-07372	QC/QA-HMA, 3, 64, INTERMEDIATE, 12.5 mm	259.00	TON

0032	401-10258	JOINT ADHESIVE, SURFACE	1164.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	912.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	1164.00	LFT
0035	406-05521	ASPHALT FOR TACK COAT	1662.00	SYS
0036	601-01522	GUARDRAIL TRANSITION, TYPE TGB	1.00	EACH
0037	601-01942	GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, MODIFIED, 17 FT RADIUS	1.00	EACH
0038	601-02241	GUARDRAIL, REMOVE	259.00	LFT
0039	601-09146	IMPACT ATTENUATOR, CR1-W1, TL-2	1.00	EACH
0040	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	2.00	EACH
0041	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00	EACH
0042	602-06729	BARRIER DELINEATOR	4.00	EACH
0043	605-06150	CURB AND GUTTER, TYPE C, CONCRETE	313.00	LFT
0044	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	200.00	SYS
0045	610-07487	HMA FOR APPROACHES, TYPE B	24.00	TON
0046	610-08446	PCCP FOR APPROACHES, 6 IN.	44.00	SYS
0047	611-08232	MAILBOX ASSEMBLY, RESET, SINGLE	3.00	EACH
0048	615-06490	RIGHT-OF-WAY MARKER	8.00	EACH
0049	615-06505	MONUMENT, TYPE B	3.00	EACH
0050	616-06405	RIPRAP, REVETMENT	397.00	TON
0051	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	502.00	SYS
0052	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0053	621-06559	MULCHED SEEDING, TYPE R	2600.00	SYS
0054	621-06574	SODDING	429.00	SYS
0055	628-09403	FIELD OFFICE, TYPE C	8.00	MOS
0056	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0057	701-06011	DYNAMIC PILE LOAD TEST	2.00	EACH
0058	701-09557	TEST PILE, DYNAMIC, PRODUCTION	142.00	LFT
0059	701-09559	TEST PILE, DYNAMIC, RESTRIKE	2.00	EACH
0060	701-09663	PILE, STEEL PIPE, 0.312 IN., DIAMETER 14 IN.	3036.00	LFT
0061	701-09679	CONICAL PILE TIP, 14 IN.	50.00	EACH
0062	702-51005	CONCRETE, A, SUBSTRUCTURE	120.60	CYS
0063	702-51015	CONCRETE, B, FOOTINGS	50.00	CYS
0064	702-51046	CONCRETE, FOUNDATION SEAL	61.80	CYS
0065	702-92857	CONCRETE, C, SUBSTRUCTURE	32.00	CYS
0066	703-06028	REINFORCING BARS	17850.00	LBS
0067	703-06029	REINFORCING BARS, EPOXY COATED	103422.00	LBS
0068	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	46.00	EACH

0069	704-51002	CONCRETE, C, SUPERSTRUCTURE	218.50	CYS
0070	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TYPE TPF-1	2.00	EACH
0071	706-06353	CONCRETE BRIDGE RAILING TRANSITION, TYPE TPS-1	2.00	EACH
0072	706-09961	RAILING, CONCRETE TYPE PS-1	152.00	LFT
0073	706-09962	RAILING, CONCRETE TYPE PF-1	152.00	LFT
0074	706-11404	RAILING, STEEL TYPE PF-1	161.00	LFT
0075	706-11418	RAILING, STEEL TYPE PS-1	161.00	LFT
0076	707-11494	STRUCTURAL MEMBER, CONCRETE, BOX BEAM, 21 IN. X 48 IN.	750.00	LFT
0077	709-51821	SURFACE SEAL	1.00	LS
0078	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	65.00	LFT
0079	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	72.00	LFT
0080	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	112.00	LFT
0081	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0082	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0083	718-12308	GEOTEXTILE FOR UNDERDRAINS, TYPE 2B	116.00	SYS
0084	720-98174	INLET, TYPE B15	1.00	EACH
0085	720-98555	INLET, TYPE C15	1.00	EACH
0086	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0087	801-06625	DETOUR ROUTE MARKER ASSEMBLY	15.00	EACH
0088	801-06640	CONSTRUCTION SIGN, TYPE A	10.00	EACH
0089	801-06775	MAINTAINING TRAFFIC	1.00	LS
0090	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0091	801-07119	BARRICADE, TYPE III-B	48.00	LFT
0092	804-11921	DELINEATOR POST, FLEXIBLE, TYPE II	10.00	EACH
0093	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1300.00	LFT
0094	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1300.00	LFT

Call: 510

Contract: B -42068-A

Section No.: 1

BRIDGE REHABILITATION OR REPAIR

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
	0011	202-02240	PAVEMENT REMOVAL	90.00	SYS
	0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
	0013	202-52710	SIDEWALK CONCRETE, REMOVE	32.00	SYS
	0014	203-02000	EXCAVATION, COMMON	40.00	CYS
	0015	203-02070	BORROW	25.00	CYS
	0016	205-12108	STORMWATER MANAGEMENT BUDGET	203330.10	DOL
	0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0018	205-12618	SWQCP PREPARATION	1.00	LS
	0019	207-09935	SUBGRADE TREATMENT, TYPE IC	44.00	SYS
	0020	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	130.00	SYS
	0021	302-06464	SUBBASE FOR PCCP	22.00	CYS
	0022	306-08043	MILLING, TRANSITION	600.00	SYS
	0023	306-08159	MILLING, ASPHALT	987.00	SYS
	0024	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	55.00	TON
	0025	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	6.00	TON
	0026	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	18.00	TON
	0027	401-10258	JOINT ADHESIVE, SURFACE	450.00	LFT
	0028	401-10259	JOINT ADHESIVE, INTERMEDIATE	30.00	LFT
	0029	401-11785	LIQUID ASPHALT SEALANT	450.00	LFT
	0030	402-10084	HMA FOR TEMPORARY PAVEMENT, TYPE B	163.00	TON
	0031	406-05521	ASPHALT FOR TACK COAT	2694.00	SYS

0032	604-06070	SIDEWALK, CONCRETE	32.00	SYS
0033	605-06120	CURB, CONCRETE	20.00	LFT
0034	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	92.00	SYS
0035	615-06505	MONUMENT, TYPE B	2.00	EACH
0036	616-06405	RIPRAP, REVETMENT	98.00	TON
0037	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	131.00	SYS
0038	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0039	621-06545	FERTILIZER	1.00	TON
0040	621-06554	SEED MIXTURE, TYPE U	161.00	LBS
0041	621-06565	MULCHING MATERIAL	5.00	TON
0042	621-06737	SEED MIXTURE, EMERGENT WETLAND	4.00	LBS
0043	621-12612	SEED MIXTURE, FLOODPLAIN	90.00	LBS
0044	622-05638	PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	20.00	EACH
0045	628-09403	FIELD OFFICE, TYPE C	12.00	MOS
0046	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0047	702-51863	FIELD DRILLED HOLE IN CONCRETE	964.00	EACH
0048	703-06029	REINFORCING BARS, EPOXY COATED	5282.00	LBS
0049	703-08247	EMBEDDED GALVANIC ANODE	345.00	EACH
0050	704-51002	CONCRETE, C, SUPERSTRUCTURE	2.80	CYS
0051	706-11455	BRIDGE RAILING PEDESTRIAN FENCE	1397.00	LFT
0052	708-51814	WELDED STEEL WIRE REINFORCEMENT	294.00	SFT
0053	709-12077	FIBER WRAP CONCRETE CASING SYSTEM	7056.00	SFT
0054	709-51821	SURFACE SEAL	1.00	LS
0055	709-96826	CONCRETE SURFACE COATING	1.00	LS
0056	709-96826	CONCRETE SURFACE COATING	1.00	LS
0057	710-09158	PATCHING CONCRETE STRUCTURES	1681.00	SFT
0058	711-51035	STRUCTURAL STEEL	72.00	LBS
0059	713-04331	TEMPORARY CAUSEWAY	1.00	LS
0060	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0061	722-01066	HYDRODEMOLITION	3495.00	SYS
0062	722-12380	BRIDGE DECK OVERLAY BUDGET	79420.00	DOL
0063	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	3495.00	SYS
0064	722-12732	LONGITUDINAL GROOVING	2816.00	SYS
0065	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	2776.00	SFT
0066	722-51874	OVERLAY DAM	648.00	SFT
0067	724-12773	BRIDGE EXPANSION JOINT, TYPE PCF	490.00	LFT
0068	727-90308	EPOXY INJECTION, CRACK PREPARATION	5.00	LFT

0069	727-90309	EPOXY INJECTION, EPOXY MATERIAL	2.00	GAL
0070	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0071	731-06223	SOIL NAILED WALL	33.00	SYS
0072	734-11760	PLAN SUBMITTAL	1.00	EACH
0073	801-03291	CONSTRUCTION SIGN, TYPE D	7.00	EACH
0074	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0075	801-06625	DETOUR ROUTE MARKER ASSEMBLY	27.00	EACH
0076	801-06640	CONSTRUCTION SIGN, TYPE A	7.00	EACH
0077	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	EACH
0078	801-06775	MAINTAINING TRAFFIC	1.00	LS
0079	801-07118	BARRICADE, TYPE III-A	72.00	LFT
0080	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	16.00	LFT
0081	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	678.00	LFT
0082	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	53.00	LFT
0083	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	6.00	EACH
0084	808-10077	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, LANE INDICATION ARROW	10.00	EACH
0085	808-10097	TRANSVERSE MARKING, MULTI-COMPONENT, YIELD LINE, WHITE, 27 IN.	1754.00	LFT

Call: 510

Contract: B -42068-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0086	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	3495.00	SYS

Call: 510

Contract: B -42068-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME

Line

Item No	Item Code	Description	Quantity	Unit
0087	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	3495.00	SYS

Call: 520

Contract: B -42186-A

Section No.: 1 BRIDGE DECK OVERLAY

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
	0012	202-02240	PAVEMENT REMOVAL	202.00	SYS
	0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
	0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
	0015	203-02000	EXCAVATION, COMMON	772.00	CYS
	0016	205-11626	PUMP AROUND	1.00	EACH
	0017	205-12108	STORMWATER MANAGEMENT BUDGET	70930.00	DOL
	0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0019	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	22.00	CYS
	0020	206-51235	COFFERDAM	1.00	LS
	0021	207-09935	SUBGRADE TREATMENT, TYPE IC	2667.00	SYS
	0022	211-06467	AGGREGATE FOR END BENT BACKFILL	22.00	CYS
	0023	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	26.00	CYS
	0024	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	3123.00	SYS
	0025	302-06464	SUBBASE FOR PCCP	116.00	CYS
	0026	303-01180	COMPACTED AGGREGATE, NO. 53	453.00	TON
	0027	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1658.00	SYS
	0028	306-08043	MILLING, TRANSITION	1989.00	SYS
	0029	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	491.00	TON
	0030	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	310.00	TON
	0031	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	742.00	TON

0032	401-10258	JOINT ADHESIVE, SURFACE	3999.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	610.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	3999.00	LFT
0035	406-05521	ASPHALT FOR TACK COAT	8127.00	SYS
0036	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	3.00	TON
0037	507-08271	JOINTS IN PCCP, FILLED	48.00	LFT
0038	507-08272	JOINTS IN PCCP, SAW AND SEAL	172.00	LFT
0039	601-02241	GUARDRAIL, REMOVE	961.00	LFT
0040	601-06035	GUARDRAIL, RESET	700.00	LFT
0041	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	200.00	LFT
0042	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	8.00	EACH
0043	601-94689	GUARDRAIL END TREATMENT, TYPE OS	8.00	EACH
0044	602-06729	BARRIER DELINEATOR	16.00	EACH
0045	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	199.00	LFT
0046	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	252.00	SYS
0047	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	210.00	SYS
0048	616-05688	RIPRAP, CLASS 1	515.00	TON
0049	616-06405	RIPRAP, REVETMENT	205.00	TON
0050	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	950.00	SYS
0051	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0052	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0053	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0054	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0055	619-12506	CLEAN STEEL BRIDGE, TOP FLANGES, TYPE QP-2, BRIDGE NO.	1.00	LS
0056	619-12506	CLEAN STEEL BRIDGE, TOP FLANGES, TYPE QP-2, BRIDGE NO.	1.00	LS
0057	619-51860	COAT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0058	619-51860	COAT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0059	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0060	621-06559	MULCHED SEEDING, TYPE R	2859.00	SYS
0061	621-06567	WATER	1.00	kGAL
0062	621-06574	SODDING	184.00	SYS
0063	628-09403	FIELD OFFICE, TYPE C	18.00	MOS
0064	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0065	702-51863	FIELD DRILLED HOLE IN CONCRETE	78.00	EACH
0066	703-06029	REINFORCING BARS, EPOXY COATED	61863.00	LBS
0067	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	88.00	EACH
0068	704-51002	CONCRETE, C, SUPERSTRUCTURE	72.80	CYS

0069	706-11600	RAILING, CONCRETE TYPE FC	43.10	CYS
0070	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	8.00	EACH
0071	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0072	709-51821	SURFACE SEAL	1.00	LS
0073	709-51821	SURFACE SEAL	1.00	LS
0074	709-51821	SURFACE SEAL	1.00	LS
0075	709-51821	SURFACE SEAL	1.00	LS
0076	709-51821	SURFACE SEAL	1.00	LS
0077	710-09158	PATCHING CONCRETE STRUCTURES	113.00	SFT
0078	711-51878	JACKING AND SUPPORTING GIRDERS	1.00	LS
0079	711-51878	JACKING AND SUPPORTING GIRDERS	1.00	LS
0080	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	128.00	LFT
0081	718-06528	OUTLET PROTECTOR, TYPE 1	6.00	EACH
0082	722-01066	HYDRODEMOLITION	3463.00	SYS
0083	722-12380	BRIDGE DECK OVERLAY BUDGET	60916.00	DOL
0084	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	2179.00	SYS
0085	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	1284.00	SYS
0086	722-12732	LONGITUDINAL GROOVING	3988.00	SYS
0087	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	250.00	SFT
0088	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	50.00	SFT
0089	722-51874	OVERLAY DAM	169.00	SFT
0090	724-12774	BRIDGE EXPANSION JOINT, TYPE SS, REPLACE	172.00	LFT
0091	726-12766	BEARING ASSEMBLY, SHIM EXISTING	22.00	EACH
0092	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0093	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	10696.00	LFT
0094	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	2762.00	LFT
0095	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	113.00	LFT
0096	801-06625	DETOUR ROUTE MARKER ASSEMBLY	38.00	EACH
0097	801-06640	CONSTRUCTION SIGN, TYPE A	140.00	EACH
0098	801-06645	CONSTRUCTION SIGN, TYPE B	25.00	EACH
0099	801-06710	FLASHING ARROW SIGN	56.00	DAY
0100	801-06775	MAINTAINING TRAFFIC	1.00	LS
0101	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	6.00	EACH
0102	801-07118	BARRICADE, TYPE III-A	108.00	LFT
0103	801-07119	BARRICADE, TYPE III-B	60.00	LFT
0104	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1526.00	LFT
0105	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	612.00	LFT

0106	801-12081	PORTABLE SIGNAL	1.00	LS
0107	801-12390	TEMPORARY PAVEMENT MARKING, REMOVABLE, 7 IN.	1931.00	LFT
0108	801-12392	TEMPORARY PAVEMENT MARKING, REMOVABLE, 28 IN.	52.00	LFT
0109	801-12482	DRIVEWAY ASSISTANCE DEVICE	2.00	EACH
0110	801-12930	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, INTERMITTENT	16.00	EACH
0111	802-04089	SIGN, SHEET, REMOVE	2.00	EACH
0112	802-04893	REFERENCE POST	4.00	EACH
0113	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	20.00	LFT
0114	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	6.00	SFT
0115	802-91122	SIGN, GROUND MOUNTED, RESET	3.00	EACH
0116	808-06716	LINE, REMOVE	2799.00	LFT
0117	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	881.00	LFT
0118	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	5252.00	LFT
0119	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	1649.00	LFT
0120	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	40.00	EACH

Call: 520

Contract: B -42186-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0121	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	3536.00	SYS

Call: 520

Contract: B -42186-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0122	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	3536.00	SYS

Call: 530

Contract: B -42235-A

Section No.: 1 BRIDGE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	108-09283	CPM SCHEDULE	1.00	LS
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0010	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0012	109-12573	SPECIAL MAINTENANCE	20000.00	DOL
0013	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0014	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0015	202-02240	PAVEMENT REMOVAL	3620.00	SYS
0016	202-02278	CURB, CONCRETE, REMOVE	90.00	LFT
0017	202-06580	CONTAMINATED SOIL, REMOVE	641.00	CYS
0018	202-12024	CABLE BARRIER, REMOVE	7695.00	LFT
0019	202-12026	SAFETY TERMINAL, REMOVE	9.00	EACH
0020	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0021	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0022	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0023	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0024	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0025	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0026	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0027	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0028	202-91385	INLET, REMOVE	4.00	EACH
0029	202-96022	CONCRETE FOUNDATION, REMOVE	3.00	EACH
0030	202-96133	PIPE, REMOVE	135.00	LFT
0031	202-99187	FENCE, FARM FIELD, REMOVE	80.00	LFT

0032	203-02000	EXCAVATION, COMMON	8697.00	CYS
0033	203-02070	BORROW	17260.00	CYS
0034	205-12108	STORMWATER MANAGEMENT BUDGET	264716.00	DOL
0035	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0036	205-12618	SWQCP PREPARATION	1.00	LS
0037	207-08264	SUBGRADE TREATMENT, TYPE II	14409.00	SYS
0038	207-09935	SUBGRADE TREATMENT, TYPE IC	35883.00	SYS
0039	211-06467	AGGREGATE FOR END BENT BACKFILL	172.00	CYS
0040	211-09265	STRUCTURE BACKFILL, TYPE 2	9035.00	CYS
0041	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	4.00	CYS
0042	214-11796	GEOGRID, TYPE IB	21795.00	SYS
0043	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	15136.00	SYS
0044	301-12234	COMPACTED AGGREGATE, NO. 53	2486.00	CYS
0045	302-06464	SUBBASE FOR PCCP	248.00	CYS
0046	303-01180	COMPACTED AGGREGATE, NO. 53	1901.00	TON
0047	304-07789	WIDENING WITH HMA, TYPE D	491.00	TON
0048	305-97019	RUBBLIZING PCCP	739.00	SYS
0049	306-08034	MILLING, ASPHALT, 1 1/2 IN.	881.00	SYS
0050	306-08043	MILLING, TRANSITION	8988.00	SYS
0051	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	3800.00	TON
0052	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	5368.00	TON
0053	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	17529.00	TON
0054	401-10258	JOINT ADHESIVE, SURFACE	8889.00	LFT
0055	401-10259	JOINT ADHESIVE, INTERMEDIATE	11913.00	LFT
0056	401-11785	LIQUID ASPHALT SEALANT	11470.00	LFT
0057	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	1974.00	TON
0058	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0059	402-10087	HMA FOR TEMPORARY PAVEMENT, TYPE D	7355.00	TON
0060	406-05520	ASPHALT FOR TACK COAT	21.00	TON
0061	412-09355	FOG SEAL	5009.00	SYS
0062	503-12477	TERMINAL JOINT, TYPE HMA	244.00	LFT
0063	601-02241	GUARDRAIL, REMOVE	4928.00	LFT
0064	601-06035	GUARDRAIL, RESET	200.00	LFT
0065	601-09238	HAND DIG GUARDRAIL POST HOLES	46.00	EACH
0066	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	3577.00	LFT
0067	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	15.00	EACH
0068	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	20.00	EACH

0069	601-12294	GUARDRAIL, MGS W-BEAM, CABLE TERMINAL ANCHOR	4.00 EACH
0070	601-12670	GUARDRAIL, THRIE-BEAM, 1 FT 6 3/4 IN. SPACING	388.00 LFT
0071	601-91649	GUARDRAIL, THRIE-BEAM TRANSITION SECTION, GALVANIZED	2.00 EACH
0072	601-94689	GUARDRAIL END TREATMENT, TYPE OS	4.00 EACH
0073	601-94690	GUARDRAIL END TREATMENT, TYPE MS	1.00 EACH
0074	602-06729	BARRIER DELINEATOR	76.00 EACH
0075	603-06040	FENCE, FARM FIELD, 47 IN.	160.00 LFT
0076	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	34403.00 LFT
0077	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	882.00 SYS
0078	615-06505	MONUMENT, TYPE B	17.00 EACH
0079	615-06510	MONUMENT, TYPE C	1.00 EACH
0080	616-06405	RIPRAP, REVETMENT	186.00 TON
0081	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	440.00 SYS
0082	616-93772	INSPECTION HOLE	4.00 EACH
0083	619-12506	CLEAN STEEL BRIDGE, TOP FLANGES, TYPE QP-2, BRIDGE NO.	1.00 LS
0084	619-12506	CLEAN STEEL BRIDGE, TOP FLANGES, TYPE QP-2, BRIDGE NO.	1.00 LS
0085	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.00 EACH
0086	621-06545	FERTILIZER	3.00 TON
0087	621-06554	SEED MIXTURE, TYPE U	889.00 LBS
0088	621-06560	MULCHED SEEDING, TYPE U	20957.00 SYS
0089	627-09326	CABLE BARRIER SYSTEM, TYPE TL-3	7025.00 LFT
0090	627-09330	SAFETY TERMINAL, TYPE TL-3	7.00 EACH
0091	627-10177	CABLE BARRIER SYSTEM, TYPE TL-3, SPARE PARTS	1.00 LS
0092	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00 EACH
0093	628-12684	FIELD OFFICE, TYPE E	36.00 MOS
0094	702-04325	TEMPORARY SHORING	1.00 LS
0095	702-04325	TEMPORARY SHORING	1.00 LS
0096	703-06029	REINFORCING BARS, EPOXY COATED	395132.00 LBS
0097	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	2092.00 EACH
0098	704-51002	CONCRETE, C, SUPERSTRUCTURE	592.00 CYS
0099	704-51002	CONCRETE, C, SUPERSTRUCTURE	228.00 CYS
0100	706-08502	REINFORCED CONCRETE MOMENT SLAB, 15 IN.	240.00 SYS
0101	706-11601	RAILING, CONCRETE TYPE FT	154.00 CYS
0102	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFT	24.00 EACH
0103	709-51821	SURFACE SEAL	1.00 LS
0104	709-51821	SURFACE SEAL	1.00 LS
0105	709-51821	SURFACE SEAL	1.00 LS

0106	709-51821	SURFACE SEAL	1.00	LS
0107	711-51864	DRILLED HOLE	168.00	EACH
0108	711-95291	JACKING AND SUPPORTING STEEL BEAMS	1.00	LS
0109	711-95291	JACKING AND SUPPORTING STEEL BEAMS	1.00	LS
0110	711-95291	JACKING AND SUPPORTING STEEL BEAMS	1.00	LS
0111	711-95291	JACKING AND SUPPORTING STEEL BEAMS	1.00	LS
0112	711-96800	STUD SHEAR CONNECTORS	8256.00	EACH
0113	713-04858	TEMPORARY BRIDGE	1.00	LS
0114	715-05032	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	197.00	LFT
0115	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	12833.00	LFT
0116	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	582.00	LFT
0117	718-06528	OUTLET PROTECTOR, TYPE 1	34.00	EACH
0118	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	12833.00	LFT
0119	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	500.00	SYS
0120	718-12306	GEOTEXTILE FOR UNDERDRAINS, TYPE 1B	8358.00	SYS
0121	718-52610	AGGREGATE FOR UNDERDRAINS	931.00	CYS
0122	720-12796	CASTING, CATCH BASIN, ADJUST TO GRADE	5.00	EACH
0123	720-12797	CASTING, INLET, ADJUST TO GRADE	6.00	EACH
0124	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	1.00	EACH
0125	720-45035	INLET, TYPE F7	4.00	EACH
0126	722-12732	LONGITUDINAL GROOVING	2768.00	SYS
0127	723-11203	STRUCTURE, REINFORCED CONCRETE, THREE-SIDED SECTIONS	162.00	LFT
0128	723-11203	STRUCTURE, REINFORCED CONCRETE, THREE-SIDED SECTIONS	236.00	LFT
0129	726-92406	BEARING ASSEMBLY, ELASTOMERIC	56.00	EACH
0130	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00	EACH
0131	801-06201	TEMPORARY PANEL SIGNS	226.00	SFT
0132	801-06202	TEMPORARY PANEL SIGN SUPPORTS	88.00	LFT
0133	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	11448.00	LFT
0134	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	236444.00	LFT
0135	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	13615.00	LFT
0136	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	50407.00	LFT
0137	801-06640	CONSTRUCTION SIGN, TYPE A	170.00	EACH
0138	801-06645	CONSTRUCTION SIGN, TYPE B	39.00	EACH
0139	801-06649	TEMPORARY RAISED PAVEMENT MARKER, GRADE 1	1245.00	EACH
0140	801-06710	FLASHING ARROW SIGN	480.00	DAY
0141	801-06775	MAINTAINING TRAFFIC	1.00	LS
0142	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	7.00	EACH

0143	801-07118	BARRICADE, TYPE III-A	230.00	LFT
0144	801-07119	BARRICADE, TYPE III-B	24.00	LFT
0145	801-07606	TEMPORARY CROSSOVER DRAINAGE PIPE	910.00	LFT
0146	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	7612.00	LFT
0147	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	10364.00	LFT
0148	801-08402	TEMPORARY TRAFFIC BARRIER, TYPE 3	1260.00	LFT
0149	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	890.00	LFT
0150	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	9.00	EACH
0151	801-52817	TEMPORARY CROSSOVER, TYPE B	2.00	EACH
0152	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	96.00	LFT
0153	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	72.00	SFT
0154	807-02191	HANDHOLE, LIGHTING	4.00	EACH
0155	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	264.00	LFT
0156	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	130.00	LFT
0157	807-12206	LUMINAIRE, UNDERPASS	7.00	EACH
0158	807-82051	CIRCUIT INSTALLATION, UNDERPASS, 1 LUMINAIRES	1.00	EACH
0159	807-82052	CIRCUIT INSTALLATION, UNDERPASS, 2 LUMINAIRES	3.00	EACH
0160	807-86805	SERVICE POINT, TYPE I	2.00	EACH
0161	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	8.00	EACH
0162	807-86935	INSULATION LINK, WATERPROOFED	16.00	EACH
0163	807-86950	SIGN, UNDERPASS, AND ROADWAY LIGHTING, LOCATION IDENTIFICATION	7.00	EACH
0164	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	314.00	LFT
0165	808-06716	LINE, REMOVE	66957.00	LFT
0166	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0167	808-12032	GROOVING FOR PAVEMENT MARKINGS	72962.00	LFT
0168	808-75052	LINE, PREFORMED PLASTIC, SOLID, WHITE, 6 IN.	34109.00	LFT
0169	808-75053	LINE, PREFORMED PLASTIC, SOLID, WHITE, 8 IN.	4549.00	LFT
0170	808-75055	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 6 IN.	8799.00	LFT
0171	808-75057	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 6 IN.	29105.00	LFT
0172	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	45.00	EACH
0173	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	83.00	EACH

Call: 550

Contract: B -42325-A

Section No.: 1 BRIDGE REHABILITATION OR REPAIR

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	105-12018	UTILITY PROTECTION	1.00	LS
	0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0004	109-08360	CONTRACT LIENS	1.00	DOL
	0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
	0012	201-90788	DEBRIS, REMOVE, STRUCTURE NO.	1.00	LS
	0013	202-02240	PAVEMENT REMOVAL	4568.00	SYS
	0014	202-02273	CENTER CURB, CONCRETE, REMOVE	145.00	SYS
	0015	202-05571	TESTING FOR WASTES, TYPE	22.00	EACH
	0016	202-06580	CONTAMINATED SOIL, REMOVE	1160.00	CYS
	0017	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
	0018	203-02000	EXCAVATION, COMMON	7370.00	CYS
	0019	203-02070	BORROW	1160.00	CYS
	0020	205-12108	STORMWATER MANAGEMENT BUDGET	86800.00	DOL
	0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0022	205-12618	SWQCP PREPARATION	1.00	LS
	0023	206-51235	COFFERDAM	1.00	LS
	0024	207-08264	SUBGRADE TREATMENT, TYPE II	65.00	SYS
	0025	207-09935	SUBGRADE TREATMENT, TYPE IC	937.00	SYS
	0026	211-09266	STRUCTURE BACKFILL, TYPE 3	6896.00	CYS
	0027	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	937.00	SYS
	0028	301-12234	COMPACTED AGGREGATE, NO. 53	91.00	CYS
	0029	302-06464	SUBBASE FOR PCCP	1033.00	CYS
	0030	303-01180	COMPACTED AGGREGATE, NO. 53	96.00	TON
	0031	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	43.00	TON

0032	306-08034	MILLING, ASPHALT, 1 1/2 IN.	3713.00	SYS
0033	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	350.00	TON
0034	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	71.00	TON
0035	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	256.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	1701.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	240.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	1701.00	LFT
0039	406-05521	ASPHALT FOR TACK COAT	1031.00	SYS
0040	503-12477	TERMINAL JOINT, TYPE HMA	105.00	LFT
0041	601-02241	GUARDRAIL, REMOVE	113.00	LFT
0042	601-03464	GUARDRAIL, STEEL CURVED TERMINAL END SECTION	2.00	EACH
0043	601-06035	GUARDRAIL, RESET	300.00	LFT
0044	601-09146	IMPACT ATTENUATOR, CR1-W1, TL-2	2.00	EACH
0045	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	100.00	LFT
0046	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	2.00	EACH
0047	601-94689	GUARDRAIL END TREATMENT, TYPE OS	1.00	EACH
0048	603-97461	TEMPORARY FENCE	1500.00	LFT
0049	604-06070	SIDEWALK, CONCRETE	52.00	SYS
0050	604-08086	CURB RAMP, CONCRETE	23.00	SYS
0051	604-12083	DETECTABLE WARNING SURFACES	7.00	SYS
0052	604-92237	HAND RAIL, STEEL	1119.00	LFT
0053	605-06120	CURB, CONCRETE	279.00	LFT
0054	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	346.00	SYS
0055	616-05688	RIPRAP, CLASS 1	756.00	TON
0056	616-06405	RIPRAP, REVETMENT	901.00	TON
0057	616-12251	GEOTEXTILE FOR RIPRAP, TYPE 3	2444.00	SYS
0058	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0059	621-06545	FERTILIZER	0.10	TON
0060	621-06560	MULCHED SEEDING, TYPE U	1766.00	SYS
0061	621-12612	SEED MIXTURE, FLOODPLAIN	2.00	LBS
0062	622-05640	PLANT, DECIDUOUS SHRUB, 24 IN. TO 36 IN.	16.00	EACH
0063	622-05648	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER	16.00	EACH
0064	622-05654	PLANT, PERENNIAL	66.00	EACH
0065	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0066	628-12683	FIELD OFFICE, TYPE D	24.00	MOS
0067	702-02925	WATERPROOFING MEMBRANE SYSTEM	36800.00	SFT
0068	702-04325	TEMPORARY SHORING	1.00	LS

0069	702-51863	FIELD DRILLED HOLE IN CONCRETE	120.00 EACH
0070	703-06029	REINFORCING BARS, EPOXY COATED	250069.00 LBS
0071	703-08247	EMBEDDED GALVANIC ANODE	5678.00 EACH
0072	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	54.00 EACH
0073	704-51002	CONCRETE, C, SUPERSTRUCTURE	1600.30 CYS
0074	704-51106	DECK DRAIN	8.00 EACH
0075	706-04683	RAILING	1201.00 LFT
0076	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TYPE TPF-1	4.00 EACH
0077	706-51020	RAILING, CONCRETE TYPE C	50.00 CYS
0078	709-51821	SURFACE SEAL	1.00 LS
0079	710-09158	PATCHING CONCRETE STRUCTURES	13120.00 SFT
0080	713-04331	TEMPORARY CAUSEWAY	1.00 LS
0081	715-05203	PIPE, TYPE 4, CIRCULAR, DIAMETER 4 IN.	1634.00 LFT
0082	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	1448.00 SYS
0083	718-52610	AGGREGATE FOR UNDERDRAINS	171.00 CYS
0084	720-12797	CASTING, INLET, ADJUST TO GRADE	2.00 EACH
0085	720-44055	CASTING, TYPE 10, FURNISH AND ADJUST TO GRADE	1.00 EACH
0086	722-12732	LONGITUDINAL GROOVING	4052.00 SYS
0087	801-03290	CONSTRUCTION SIGN, TYPE C	9.00 EACH
0088	801-03291	CONSTRUCTION SIGN, TYPE D	6.00 EACH
0089	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00 EACH
0090	801-06625	DETOUR ROUTE MARKER ASSEMBLY	40.00 EACH
0091	801-06640	CONSTRUCTION SIGN, TYPE A	16.00 EACH
0092	801-06645	CONSTRUCTION SIGN, TYPE B	22.00 EACH
0093	801-06775	MAINTAINING TRAFFIC	1.00 LS
0094	801-07119	BARRICADE, TYPE III-B	250.00 LFT
0095	801-11990	TEMPORARY CURB RAMP	3.00 EACH
0096	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	200.00 LFT
0097	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	70.00 LFT
0098	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	76.00 SFT
0099	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	54.00 SFT
0100	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	2.00 EACH
0101	805-04133	SIGNAL POLE, PEDESTAL, 12 FT	2.00 EACH
0102	805-11817	PEDESTRIAN PUSH BUTTON, APS	2.00 EACH
0103	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	4.00 EACH
0104	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	476.00 LFT
0105	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	281.00 LFT

0106	807-02191	HANDHOLE, LIGHTING	1.00 EACH
0107	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	1604.00 LFT
0108	808-02977	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	8.00 EACH
0109	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	448.00 LFT
0110	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	557.00 LFT
0111	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2307.00 LFT
0112	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2380.00 LFT
0113	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	85.00 LFT
0114	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	4.00 EACH
0115	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	1.00 EACH
0116	808-75330	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, PED XING	4.00 EACH
0117	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	39.00 LFT
0118	808-95933	CURB, PAINTING, YELLOW	160.00 LFT

Call: 560

Contract: B -42341-A

Section No.: 1

SMALL STRUCTURE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	202-01000	STRUCTURES AND OBSTRUCTIONS, REMOVE	1.00	LS
	0011	203-02000	EXCAVATION, COMMON	35.00	CYS
	0012	205-11626	PUMP AROUND	1.00	EACH
	0013	205-12108	STORMWATER MANAGEMENT BUDGET	2645.00	DOL
	0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0015	207-09935	SUBGRADE TREATMENT, TYPE IC	85.00	SYS
	0016	211-09265	STRUCTURE BACKFILL, TYPE 2	440.00	CYS
	0017	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	90.00	SYS
	0018	301-12232	COMPACTED AGGREGATE, NO. 5	56.00	CYS
	0019	303-01180	COMPACTED AGGREGATE, NO. 53	9.00	TON
	0020	306-08034	MILLING, ASPHALT, 1 1/2 IN.	128.00	SYS
	0021	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	18.00	TON
	0022	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	12.00	TON
	0023	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	29.00	TON
	0024	401-10258	JOINT ADHESIVE, SURFACE	60.00	LFT
	0025	401-10259	JOINT ADHESIVE, INTERMEDIATE	24.00	LFT
	0026	401-11785	LIQUID ASPHALT SEALANT	60.00	LFT
	0027	406-05520	ASPHALT FOR TACK COAT	1.00	TON
	0028	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	1.00	TON
	0029	616-06405	RIPRAP, REVETMENT	27.00	TON
	0030	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	35.00	SYS
	0031	621-06559	MULCHED SEEDING, TYPE R	210.00	SYS

0032	621-06574	SODDING	42.00	SYS
0033	628-09403	FIELD OFFICE, TYPE C	9.00	MOS
0034	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0035	714-11094	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 9 FT X 4 FT	66.00	LFT
0036	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	10.00	LFT
0037	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0038	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH
0039	801-06625	DETOUR ROUTE MARKER ASSEMBLY	23.00	EACH
0040	801-06640	CONSTRUCTION SIGN, TYPE A	7.00	EACH
0041	801-06775	MAINTAINING TRAFFIC	1.00	LS
0042	801-07118	BARRICADE, TYPE III-A	68.00	LFT
0043	801-07119	BARRICADE, TYPE III-B	108.00	LFT
0044	808-12032	GROOVING FOR PAVEMENT MARKINGS	204.00	LFT
0045	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	120.00	LFT
0046	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	60.00	LFT
0047	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2.00	EACH
0048	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2.00	EACH
0049	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	24.00	LFT

Call: 570

Contract: B -42348-A

Section No.: 1

BRIDGE REHABILITATION OR REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	1382.00	SYS
0012	202-02273	CENTER CURB, CONCRETE, REMOVE	203.00	SYS
0013	202-02278	CURB, CONCRETE, REMOVE	1262.00	LFT
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0015	202-51368	SLOPEWALL, REMOVE	6.00	SYS
0016	202-91385	INLET, REMOVE	4.00	EACH
0017	202-96133	PIPE, REMOVE	4.00	LFT
0018	203-02000	EXCAVATION, COMMON	638.00	CYS
0019	203-02070	BORROW	737.00	CYS
0020	205-12108	STORMWATER MANAGEMENT BUDGET	25503.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	206-51235	COFFERDAM	1.00	LS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	2262.00	SYS
0024	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	2.00	CYS
0025	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	2262.00	SYS
0026	302-06464	SUBBASE FOR PCCP	208.00	CYS
0027	303-01180	COMPACTED AGGREGATE, NO. 53	196.00	TON
0028	306-08043	MILLING, TRANSITION	1862.00	SYS
0029	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	202.00	TON
0030	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	75.00	TON
0031	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	324.00	TON

0032	401-10258	JOINT ADHESIVE, SURFACE	1620.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	360.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	1620.00	LFT
0035	402-07452	HMA WEDGE AND LEVEL, TYPE C	157.00	TON
0036	402-10086	HMA FOR TEMPORARY PAVEMENT, TYPE C	543.00	TON
0037	406-05521	ASPHALT FOR TACK COAT	2930.00	SYS
0038	503-12477	TERMINAL JOINT, TYPE HMA	180.00	LFT
0039	601-02241	GUARDRAIL, REMOVE	186.00	LFT
0040	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	50.00	LFT
0041	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	2.00	EACH
0042	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00	EACH
0043	602-06729	BARRIER DELINEATOR	6.00	EACH
0044	605-06100	CURB, INTEGRAL C CONCRETE	998.00	LFT
0045	605-06121	CURB, CONCRETE, TYPE B	264.00	LFT
0046	605-06255	CENTER CURB, D CONCRETE	203.00	SYS
0047	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	812.00	SYS
0048	616-05688	RIPRAP, CLASS 1	294.00	TON
0049	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	196.00	SYS
0050	616-51366	SLOPEWALL, CONCRETE, 5 IN.	6.00	SYS
0051	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0052	621-06560	MULCHED SEEDING, TYPE U	1139.00	SYS
0053	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. TO 2 IN.	5.00	EACH
0054	622-05651	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 IN. TO 3.5 IN.	6.00	EACH
0055	628-09403	FIELD OFFICE, TYPE C	12.00	MOS
0056	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0057	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	6.00	EACH
0058	702-51863	FIELD DRILLED HOLE IN CONCRETE	499.00	EACH
0059	703-06029	REINFORCING BARS, EPOXY COATED	207517.00	LBS
0060	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	929.00	EACH
0061	704-51002	CONCRETE, C, SUPERSTRUCTURE	837.60	CYS
0062	706-06353	CONCRETE BRIDGE RAILING TRANSITION, TYPE TPS-1	4.00	EACH
0063	706-11418	RAILING, STEEL TYPE PS-1	236.00	LFT
0064	706-11604	RAILING, CONCRETE TYPE PS-1	19.60	CYS
0065	709-51821	SURFACE SEAL	1.00	LS
0066	715-05595	PIPE EXTENSION, CIRCULAR, DIAMETER 15 IN.	4.00	LFT
0067	715-05596	PIPE EXTENSION, CIRCULAR, DIAMETER 18 IN.	4.00	LFT
0068	715-05756	PIPE EXTENSION, CIRCULAR, DIAMETER 12 IN.	16.00	LFT

0069	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	1.00 EACH
0070	720-12797	CASTING, INLET, ADJUST TO GRADE	5.00 EACH
0071	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	1.00 EACH
0072	720-44045	CASTING, TYPE 8, FURNISH AND ADJUST TO GRADE	5.00 EACH
0073	720-45015	INLET, TYPE A8	4.00 EACH
0074	722-12732	LONGITUDINAL GROOVING	1688.00 SYS
0075	724-12773	BRIDGE EXPANSION JOINT, TYPE PCF	109.00 LFT
0076	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	25288.00 LFT
0077	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	3259.00 LFT
0078	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	18.00 EACH
0079	801-06640	CONSTRUCTION SIGN, TYPE A	29.00 EACH
0080	801-06645	CONSTRUCTION SIGN, TYPE B	19.00 EACH
0081	801-06710	FLASHING ARROW SIGN	480.00 DAY
0082	801-06775	MAINTAINING TRAFFIC	1.00 LS
0083	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00 EACH
0084	801-07118	BARRICADE, TYPE III-A	36.00 LFT
0085	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	650.00 LFT
0086	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	8.00 EACH
0087	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	460.00 LFT
0088	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	931.00 LFT
0089	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	931.00 LFT

Call: 590

Contract: B -42437-A

Section No.: 1 BRIDGE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0010	202-02240	PAVEMENT REMOVAL	191.00	SYS
0011	202-12542	DEBRIS REMOVAL	1.00	EACH
0012	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0013	202-74035	SIGN, REMOVE	10.00	EACH
0014	203-02000	EXCAVATION, COMMON	1780.00	CYS
0015	203-02070	BORROW	56.00	CYS
0016	203-51223	EXCAVATION, WATERWAY	160.00	CYS
0017	205-11626	PUMP AROUND	1.00	EACH
0018	205-12108	STORMWATER MANAGEMENT BUDGET	15621.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	1349.00	SYS
0021	211-06467	AGGREGATE FOR END BENT BACKFILL	99.00	CYS
0022	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	1567.00	SYS
0023	302-06464	SUBBASE FOR PCCP	55.00	CYS
0024	303-01180	COMPACTED AGGREGATE, NO. 53	20.00	TON
0025	303-07449	COMPACTED AGGREGATE, NO. 73	501.00	TON
0026	306-08043	MILLING, TRANSITION	513.00	SYS
0027	306-11872	MILLING, PROFILE	1173.00	SYS
0028	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	231.00	TON
0029	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	384.00	TON
0030	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	360.00	TON
0031	401-10258	JOINT ADHESIVE, SURFACE	3543.00	LFT

0032	401-10259	JOINT ADHESIVE, INTERMEDIATE	3543.00	LFT
0033	401-11785	LIQUID ASPHALT SEALANT	3543.00	LFT
0034	406-05520	ASPHALT FOR TACK COAT	2.00	TON
0035	601-02241	GUARDRAIL, REMOVE	1085.00	LFT
0036	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	619.00	LFT
0037	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	4.00	EACH
0038	601-94689	GUARDRAIL END TREATMENT, TYPE OS	4.00	EACH
0039	602-06729	BARRIER DELINEATOR	10.00	EACH
0040	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	218.00	SYS
0041	615-06490	RIGHT-OF-WAY MARKER	8.00	EACH
0042	615-06505	MONUMENT, TYPE B	2.00	EACH
0043	616-06405	RIPRAP, REVETMENT	908.00	TON
0044	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	1521.00	SYS
0045	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0046	621-02770	EROSION CONTROL BLANKET	3025.00	SYS
0047	621-06559	MULCHED SEEDING, TYPE R	3025.00	SYS
0048	621-06570	TOPSOIL	480.00	CYS
0049	621-06574	SODDING	83.00	SYS
0050	628-09403	FIELD OFFICE, TYPE C	8.00	MOS
0051	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0052	701-06011	DYNAMIC PILE LOAD TEST	2.00	EACH
0053	701-09557	TEST PILE, DYNAMIC, PRODUCTION	129.00	LFT
0054	701-09559	TEST PILE, DYNAMIC, RESTRIKE	2.00	EACH
0055	701-09665	PILE, STEEL PIPE, 0.375 IN., DIAMETER 14 IN.	1032.00	LFT
0056	702-92857	CONCRETE, C, SUBSTRUCTURE	49.90	CYS
0057	703-06029	REINFORCING BARS, EPOXY COATED	63360.00	LBS
0058	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	43.00	EACH
0059	704-51002	CONCRETE, C, SUPERSTRUCTURE	161.00	CYS
0060	706-09960	RAILING, CONCRETE TYPE FC	211.00	LFT
0061	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	4.00	EACH
0062	707-09634	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 48 IN. X 49 IN.	412.00	LFT
0063	709-51821	SURFACE SEAL	1.00	LS
0064	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	168.00	LFT
0065	722-12732	LONGITUDINAL GROOVING	572.00	SYS
0066	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0067	801-06625	DETOUR ROUTE MARKER ASSEMBLY	33.00	EACH
0068	801-06640	CONSTRUCTION SIGN, TYPE A	8.00	EACH

0069	801-06775	MAINTAINING TRAFFIC	1.00	LS
0070	801-07118	BARRICADE, TYPE III-A	72.00	LFT
0071	801-07119	BARRICADE, TYPE III-B	72.00	LFT
0072	802-04893	REFERENCE POST	2.00	EACH
0073	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	122.00	LFT
0074	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	60.00	SFT
0075	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	9.00	SFT
0076	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	2190.00	LFT
0077	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	2190.00	LFT
0078	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	25.00	EACH
0079	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	23.00	EACH

Call: 600

Contract: B -42449-A

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	706.00	SYS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0014	202-74035	SIGN, REMOVE	4.00	EACH
0015	202-96133	PIPE, REMOVE	83.00	LFT
0016	202-98488	PIPE END SECTION, REMOVE	2.00	EACH
0017	203-02000	EXCAVATION, COMMON	1010.00	CYS
0018	205-12108	STORMWATER MANAGEMENT BUDGET	29983.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	100.00	CYS
0021	207-08264	SUBGRADE TREATMENT, TYPE II	113.00	SYS
0022	207-09935	SUBGRADE TREATMENT, TYPE IC	1800.00	SYS
0023	211-06467	AGGREGATE FOR END BENT BACKFILL	44.00	CYS
0024	211-09264	STRUCTURE BACKFILL, TYPE 1	20.00	CYS
0025	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	2078.00	SYS
0026	301-12234	COMPACTED AGGREGATE, NO. 53	72.00	CYS
0027	302-06464	SUBBASE FOR PCCP	98.00	CYS
0028	303-01180	COMPACTED AGGREGATE, NO. 53	281.00	TON
0029	303-07449	COMPACTED AGGREGATE, NO. 73	39.00	TON
0030	304-07494	WIDENING WITH HMA, TYPE C	70.00	TON
0031	306-08043	MILLING, TRANSITION	515.00	SYS

0032	306-08432	MILLING, APPROACH	29.00	SYS
0033	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	30.00	TON
0034	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	115.00	TON
0035	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	31.00	TON
0036	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	196.00	TON
0037	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	529.00	TON
0038	401-10258	JOINT ADHESIVE, SURFACE	1841.00	LFT
0039	401-10259	JOINT ADHESIVE, INTERMEDIATE	1721.00	LFT
0040	401-11785	LIQUID ASPHALT SEALANT	300.00	LFT
0041	401-11785	LIQUID ASPHALT SEALANT	1541.00	LFT
0042	406-05521	ASPHALT FOR TACK COAT	3646.00	SYS
0043	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0044	503-12477	TERMINAL JOINT, TYPE HMA	68.00	LFT
0045	601-01522	GUARDRAIL TRANSITION, TYPE TGB	4.00	EACH
0046	601-01700	GUARDRAIL TERMINAL SYSTEM, W-BEAM CURVED, TYPE 1	1.00	EACH
0047	601-01701	GUARDRAIL TERMINAL SYSTEM, W-BEAM CURVED, TYPE 2	2.00	EACH
0048	601-01740	GUARDRAIL TERMINAL SYSTEM, W-BEAM CURVED, TYPE 4	1.00	EACH
0049	601-02241	GUARDRAIL, REMOVE	602.00	LFT
0050	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	2.00	EACH
0051	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	4.00	EACH
0052	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00	EACH
0053	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	56.25	LFT
0054	602-06729	BARRIER DELINEATOR	18.00	EACH
0055	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	600.00	LFT
0056	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	418.00	SYS
0057	610-07487	HMA FOR APPROACHES, TYPE B	24.00	TON
0058	611-08232	MAILBOX ASSEMBLY, RESET, SINGLE	1.00	EACH
0059	615-06490	RIGHT-OF-WAY MARKER	8.00	EACH
0060	615-06505	MONUMENT, TYPE B	2.00	EACH
0061	616-06405	RIPRAP, REVETMENT	1287.00	TON
0062	616-12247	GEOTEXTILE FOR RIPRAP, TYPE 1B	502.00	SYS
0063	616-12251	GEOTEXTILE FOR RIPRAP, TYPE 3	1138.00	SYS
0064	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0065	621-02770	EROSION CONTROL BLANKET	21.00	SYS
0066	621-06545	FERTILIZER	1.00	TON
0067	621-06559	MULCHED SEEDING, TYPE R	1326.00	SYS
0068	621-06567	WATER	2.00	KGAL

0069	621-06570	TOPSOIL	24.00	CYS
0070	621-06574	SODDING	330.00	SYS
0071	621-12612	SEED MIXTURE, FLOODPLAIN	1.00	LBS
0072	628-09403	FIELD OFFICE, TYPE C	6.00	MOS
0073	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	8.00	EACH
0074	702-51005	CONCRETE, A, SUBSTRUCTURE	28.40	CYS
0075	702-92857	CONCRETE, C, SUBSTRUCTURE	39.60	CYS
0076	703-01540	THREADED TIE BAR ASSEMBLY	36.00	EACH
0077	703-06028	REINFORCING BARS	4250.00	LBS
0078	703-06029	REINFORCING BARS, EPOXY COATED	100936.00	LBS
0079	704-51002	CONCRETE, C, SUPERSTRUCTURE	211.10	CYS
0080	706-11600	RAILING, CONCRETE TYPE FC	23.00	CYS
0081	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	4.00	EACH
0082	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	4.00	EACH
0083	707-05984	STRUCTURAL MEMBER, CONCRETE, I-BEAM, 45 IN. X 16 IN.	597.00	LFT
0084	709-51821	SURFACE SEAL	1.00	LS
0085	709-51821	SURFACE SEAL	1.00	LS
0086	710-09158	PATCHING CONCRETE STRUCTURES	428.00	SFT
0087	715-03321	SAFETY METAL END SECTION, 6:1, DIAMETER 12 IN.	2.00	EACH
0088	715-05168	PIPE, TYPE 3, CIRCULAR, DIAMETER 12 IN.	62.00	LFT
0089	715-05363	PIPE, TYPE 3, DEFORMED, MIN. AREA 1.8 SFT	32.00	LFT
0090	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	204.00	LFT
0091	715-08449	SAFETY METAL END SECTION, 6:1, MIN. AREA 1.8 SFT	2.00	EACH
0092	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	28.00	EACH
0093	718-12309	GEOTEXTILE FOR UNDERDRAINS, TYPE 3	98.00	SYS
0094	722-01066	HYDRODEMOLITION	237.00	SYS
0095	722-12380	BRIDGE DECK OVERLAY BUDGET	5800.00	DOL
0096	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	237.00	SYS
0097	722-12732	LONGITUDINAL GROOVING	1218.00	SYS
0098	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	214.00	SFT
0099	722-51874	OVERLAY DAM	170.00	SFT
0100	727-90308	EPOXY INJECTION, CRACK PREPARATION	200.00	LFT
0101	727-90308	EPOXY INJECTION, CRACK PREPARATION	335.00	LFT
0102	727-90309	EPOXY INJECTION, EPOXY MATERIAL	92.00	GAL
0103	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0104	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0105	801-03290	CONSTRUCTION SIGN, TYPE C	2.00	EACH

0106	801-04308	ROAD CLOSURE SIGN ASSEMBLY	20.00	EACH
0107	801-06625	DETOUR ROUTE MARKER ASSEMBLY	79.00	EACH
0108	801-06640	CONSTRUCTION SIGN, TYPE A	37.00	EACH
0109	801-06645	CONSTRUCTION SIGN, TYPE B	1.00	EACH
0110	801-06775	MAINTAINING TRAFFIC	1.00	LS
0111	801-07118	BARRICADE, TYPE III-A	120.00	LFT
0112	801-07119	BARRICADE, TYPE III-B	244.00	LFT
0113	802-91122	SIGN, GROUND MOUNTED, RESET	2.00	EACH
0114	804-06770	DELINEATOR POST	2.00	EACH
0115	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	1620.00	LFT
0116	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	520.00	LFT
0117	808-12032	GROOVING FOR PAVEMENT MARKINGS	1274.00	LFT
0118	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	204.00	LFT

Call: 600

Contract: B -42449-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0119	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	237.00	SYS

Call: 600

Contract: B -42449-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0120	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	237.00	SYS

Call: 610

Contract: B -42728-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	202-74035	SIGN, REMOVE	2.00	EACH
0011	306-08034	MILLING, ASPHALT, 1 1/2 IN.	700.00	SYS
0012	306-08043	MILLING, TRANSITION	2407.00	SYS
0013	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	257.00	TON
0014	401-10258	JOINT ADHESIVE, SURFACE	2526.00	LFT
0015	401-11785	LIQUID ASPHALT SEALANT	2526.00	LFT
0016	406-05521	ASPHALT FOR TACK COAT	3107.00	SYS
0017	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	682.00	SFT
0018	507-08272	JOINTS IN PCCP, SAW AND SEAL	550.00	LFT
0019	628-09403	FIELD OFFICE, TYPE C	8.00	MOS
0020	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0021	704-51106	DECK DRAIN	32.00	EACH
0022	709-51821	SURFACE SEAL	1.00	LS
0023	709-51821	SURFACE SEAL	1.00	LS
0024	709-51821	SURFACE SEAL	1.00	LS
0025	709-51821	SURFACE SEAL	1.00	LS
0026	709-51821	SURFACE SEAL	1.00	LS
0027	709-51821	SURFACE SEAL	1.00	LS
0028	710-09158	PATCHING CONCRETE STRUCTURES	362.00	SFT
0029	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	792.00	SFT
0030	738-12855	WARRANTED POLYMER OVERLAY, BRIDGE DECK	2709.00	SYS
0031	801-04308	ROAD CLOSURE SIGN ASSEMBLY	12.00	EACH

0032	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	29294.00	LFT
0033	801-06625	DETOUR ROUTE MARKER ASSEMBLY	53.00	EACH
0034	801-06640	CONSTRUCTION SIGN, TYPE A	62.00	EACH
0035	801-06710	FLASHING ARROW SIGN	80.00	DAY
0036	801-06775	MAINTAINING TRAFFIC	1.00	LS
0037	801-07118	BARRICADE, TYPE III-A	54.00	LFT
0038	801-07119	BARRICADE, TYPE III-B	86.00	LFT
0039	801-12042	TRUCK MOUNTED ATTENUATOR	80.00	DAY
0040	801-12390	TEMPORARY PAVEMENT MARKING, REMOVABLE, 7 IN.	11296.00	LFT
0041	801-12930	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, INTERMITTENT	16.00	EACH
0042	802-04893	REFERENCE POST	6.00	EACH
0043	808-06716	LINE, REMOVE	2125.00	LFT
0044	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	84.00	LFT
0045	808-75002	LINE, PAINT, BROKEN, WHITE, 6 IN.	313.00	LFT
0046	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	2132.00	LFT
0047	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	1245.00	LFT
0048	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2.00	EACH

Call: 620

Contract: B -42852-A

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	416.00	SYS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0013	202-62420	BRIDGE RAILING, REMOVE	686.00	LFT
0014	203-02000	EXCAVATION, COMMON	190.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	8179.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	207-08264	SUBGRADE TREATMENT, TYPE II	761.00	SYS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	740.00	SYS
0019	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	740.00	SYS
0020	301-12234	COMPACTED AGGREGATE, NO. 53	50.00	CYS
0021	302-06464	SUBBASE FOR PCCP	110.00	CYS
0022	305-97019	RUBBLIZING PCCP	169.00	SYS
0023	306-08043	MILLING, TRANSITION	742.00	SYS
0024	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	150.00	TON
0025	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	146.00	TON
0026	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	466.00	TON
0027	401-10258	JOINT ADHESIVE, SURFACE	840.00	LFT
0028	401-10259	JOINT ADHESIVE, INTERMEDIATE	240.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	840.00	LFT
0030	503-12477	TERMINAL JOINT, TYPE HMA	89.00	LFT
0031	601-02241	GUARDRAIL, REMOVE	438.00	LFT

0032	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	2.00 EACH
0033	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	4.00 EACH
0034	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00 EACH
0035	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	431.00 SYS
0036	616-06405	RIPRAP, REVETMENT	374.00 TON
0037	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	497.00 SYS
0038	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00 LS
0039	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00 LS
0040	619-51860	COAT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00 LS
0041	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0042	628-12683	FIELD OFFICE, TYPE D	12.00 MOS
0043	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	12.00 EACH
0044	702-51005	CONCRETE, A, SUBSTRUCTURE	21.60 CYS
0045	702-51863	FIELD DRILLED HOLE IN CONCRETE	268.00 EACH
0046	703-06029	REINFORCING BARS, EPOXY COATED	64861.00 LBS
0047	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	286.00 EACH
0048	704-51002	CONCRETE, C, SUPERSTRUCTURE	208.20 CYS
0049	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TYPE TPF-1	4.00 EACH
0050	706-11404	RAILING, STEEL TYPE PF-1	702.00 LFT
0051	706-11602	RAILING, CONCRETE TYPE PF-1	42.10 CYS
0052	709-51821	SURFACE SEAL	1.00 LS
0053	711-51864	DRILLED HOLE	80.00 EACH
0054	711-51878	JACKING AND SUPPORTING GIRDERS	1.00 LS
0055	711-96800	STUD SHEAR CONNECTORS	150.00 EACH
0056	722-01066	HYDRODEMOLITION	1694.00 SYS
0057	722-12380	BRIDGE DECK OVERLAY BUDGET	27693.00 DOL
0058	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	1515.00 SYS
0059	722-12732	LONGITUDINAL GROOVING	2117.00 SYS
0060	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	763.00 SFT
0061	726-92406	BEARING ASSEMBLY, ELASTOMERIC	10.00 EACH
0062	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	6800.00 LFT
0063	801-06640	CONSTRUCTION SIGN, TYPE A	14.00 EACH
0064	801-06775	MAINTAINING TRAFFIC	1.00 LS
0065	801-07118	BARRICADE, TYPE III-A	12.00 LFT
0066	801-07612	TEMPORARY PAVEMENT MARKING, 24 IN.	48.00 LFT
0067	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1170.00 LFT
0068	801-12081	PORTABLE SIGNAL	1.00 LS

0069	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	4.00 EACH
0070	808-06716	LINE, REMOVE	3760.00 LFT
0071	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	2400.00 LFT
0072	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	1360.00 LFT
0073	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	18.00 EACH
0074	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	18.00 EACH

Call: 620

Contract: B -42852-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED

Line

Item No	Item Code	Description	Quantity Unit
0075	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	1694.00 SYS

Call: 620

Contract: B -42852-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

Line

Item No	Item Code	Description	Quantity Unit
0076	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	1694.00 SYS

Call: 640

Contract: B -43617-A

Section No.: 1 BRIDGE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
	0011	202-01000	STRUCTURES AND OBSTRUCTIONS, REMOVE	1.00	LS
	0012	202-02928	CATCH BASIN, REMOVE	1.00	EACH
	0013	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
	0014	202-96133	PIPE, REMOVE	57.00	LFT
	0015	202-96430	FENCE AND POSTS, REMOVE	1.00	LS
	0016	203-02000	EXCAVATION, COMMON	1575.00	CYS
	0017	203-51223	EXCAVATION, WATERWAY	230.00	CYS
	0018	205-12108	STORMWATER MANAGEMENT BUDGET	10012.00	DOL
	0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0020	207-08266	SUBGRADE TREATMENT, TYPE III	745.00	SYS
	0021	207-09935	SUBGRADE TREATMENT, TYPE IC	1067.00	SYS
	0022	211-09264	STRUCTURE BACKFILL, TYPE 1	120.00	CYS
	0023	211-09265	STRUCTURE BACKFILL, TYPE 2	1195.00	CYS
	0024	211-09266	STRUCTURE BACKFILL, TYPE 3	1465.00	CYS
	0025	211-09268	STRUCTURE BACKFILL, TYPE 5	5.00	CYS
	0026	303-01180	COMPACTED AGGREGATE, NO. 53	134.00	TON
	0027	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	26.00	TON
	0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1502.00	SYS
	0029	401-07339	QC/QA-HMA, 2, 64, SURFACE, 12.5 mm	162.00	TON
	0030	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	41.00	TON
	0031	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	65.00	TON

0032	401-10258	JOINT ADHESIVE, SURFACE	660.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	97.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	660.00	LFT
0035	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0036	502-11564	PCCP, 7 IN.	95.00	SYS
0037	601-02241	GUARDRAIL, REMOVE	133.00	LFT
0038	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	488.00	LFT
0039	601-94689	GUARDRAIL END TREATMENT, TYPE OS	4.00	EACH
0040	603-01159	FENCE, CHAIN LINK, PVC COATED, 42 IN.	595.00	LFT
0041	604-06070	SIDEWALK, CONCRETE	497.00	SYS
0042	605-06140	CURB AND GUTTER, CONCRETE	412.00	LFT
0043	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	89.00	LFT
0044	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	873.00	LFT
0045	610-08446	PCCP FOR APPROACHES, 6 IN.	70.00	SYS
0046	611-08232	MAILBOX ASSEMBLY, RESET, SINGLE	2.00	EACH
0047	615-06490	RIGHT-OF-WAY MARKER	4.00	EACH
0048	615-06505	MONUMENT, TYPE B	4.00	EACH
0049	615-06530	BENCHMARK POST	1.00	EACH
0050	616-06405	RIPRAP, REVETMENT	386.00	TON
0051	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	389.00	SYS
0052	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0053	621-06560	MULCHED SEEDING, TYPE U	2234.00	SYS
0054	715-05203	PIPE, TYPE 4, CIRCULAR, DIAMETER 4 IN.	516.00	LFT
0055	715-09064	VIDEO INSPECTION FOR PIPE	393.00	LFT
0056	715-46000	PIPE END SECTION, DIAMETER 12 IN.	10.00	EACH
0057	720-01091	MANHOLE, TYPE C10, MODIFIED	5.00	EACH
0058	720-45045	INLET, TYPE J10	6.00	EACH
0059	720-45055	INLET, TYPE M10	4.00	EACH
0060	720-45235	CATCH BASIN, TYPE E7	1.00	EACH
0061	723-11205	STRUCTURE, REINFORCED CONCRETE, THREE-SIDED SECTIONS, 504 IN. X 256 IN.	66.00	LFT
0062	732-11811	MODULAR BLOCK WALL ERECTION	4793.00	SFT
0063	732-11812	MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	4793.00	SFT
0064	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH
0065	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	13246.00	LFT
0066	801-06625	DETOUR ROUTE MARKER ASSEMBLY	24.00	EACH
0067	801-06640	CONSTRUCTION SIGN, TYPE A	6.00	EACH
0068	801-06645	CONSTRUCTION SIGN, TYPE B	3.00	EACH

0069	801-06775	MAINTAINING TRAFFIC	1.00	LS
0070	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0071	801-07119	BARRICADE, TYPE III-B	72.00	LFT
0072	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	20.00	LFT
0073	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	2.00	EACH
0074	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	5.00	SFT
0075	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	9.00	SFT
0076	808-12032	GROOVING FOR PAVEMENT MARKINGS	2744.00	LFT
0077	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	137.00	LFT
0078	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	1372.00	LFT

Call: 650

Contract: B -44295-A

Section No.: 1 BRIDGE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
	0011	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
	0012	203-02000	EXCAVATION, COMMON	15.00	CYS
	0013	203-02070	BORROW	60.00	CYS
	0014	205-12108	STORMWATER MANAGEMENT BUDGET	10500.00	DOL
	0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0016	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	210.00	CYS
	0017	207-09935	SUBGRADE TREATMENT, TYPE IC	287.00	SYS
	0018	211-09265	STRUCTURE BACKFILL, TYPE 2	32.00	CYS
	0019	211-09267	STRUCTURE BACKFILL, TYPE 4	22.00	CYS
	0020	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	379.00	SYS
	0021	302-06464	SUBBASE FOR PCCP	77.00	CYS
	0022	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	6.00	TON
	0023	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	9.00	TON
	0024	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	21.00	TON
	0025	406-05521	ASPHALT FOR TACK COAT	183.00	SYS
	0026	503-05240	D-1 CONTRACTION JOINT	23.00	LFT
	0027	503-12475	JOINTED REINFORCED CONCRETE PAVEMENT, 10 IN.	93.00	SYS
	0028	503-12478	TERMINAL JOINT, TYPE PCCP	32.00	LFT
	0029	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	22.00	LFT
	0030	601-01522	GUARDRAIL TRANSITION, TYPE TGB	1.00	EACH
	0031	601-06037	GUARDRAIL END TREATMENT, TYPE I	1.00	EACH

0032	604-06070	SIDEWALK, CONCRETE	99.00	SYS
0033	605-06090	CURB, INTEGRAL CONCRETE	13.00	LFT
0034	605-06150	CURB AND GUTTER, TYPE C, CONCRETE	22.00	LFT
0035	605-97937	CURB AND GUTTER, ROLL CURB	56.00	LFT
0036	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	179.00	SYS
0037	616-05688	RIPRAP, CLASS 1	410.00	TON
0038	616-06451	RIPRAP, UNIFORM	50.00	TON
0039	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	610.00	SYS
0040	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0041	621-02770	EROSION CONTROL BLANKET	85.00	SYS
0042	621-06560	MULCHED SEEDING, TYPE U	290.00	SYS
0043	621-06574	SODDING	40.00	SYS
0044	628-09403	FIELD OFFICE, TYPE C	8.00	MOS
0045	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0046	628-11977	COMPUTER SYSTEM	1.00	EACH
0047	701-08122	PILE, STEEL PIPE, 0.375 IN., DIAMETER 14 IN.	782.00	LFT
0048	701-09558	TEST PILE, INDICATOR, PRODUCTION	72.00	LFT
0049	701-09560	TEST PILE, INDICATOR, RESTRIKE	2.00	EACH
0050	701-09679	CONICAL PILE TIP, 14 IN.	31.00	EACH
0051	701-11714	PREBORED HOLE, DIAMETER 12 IN.	392.00	LFT
0052	701-12304	VIBRATION MONITORING	1.00	LS
0053	702-51005	CONCRETE, A, SUBSTRUCTURE	97.70	CYS
0054	702-51015	CONCRETE, B, FOOTINGS	9.20	CYS
0055	702-92857	CONCRETE, C, SUBSTRUCTURE	34.20	CYS
0056	703-06028	REINFORCING BARS	15344.00	LBS
0057	703-06029	REINFORCING BARS, EPOXY COATED	111748.00	LBS
0058	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	34.00	EACH
0059	704-51002	CONCRETE, C, SUPERSTRUCTURE	395.30	CYS
0060	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TYPE TPF-1	2.00	EACH
0061	706-06353	CONCRETE BRIDGE RAILING TRANSITION, TYPE TPS-1	1.00	EACH
0062	706-06353	CONCRETE BRIDGE RAILING TRANSITION, TYPE TPS-1	1.00	EACH
0063	706-09961	RAILING, CONCRETE TYPE PS-1	143.00	LFT
0064	706-09962	RAILING, CONCRETE TYPE PF-1	143.00	LFT
0065	706-11404	RAILING, STEEL TYPE PF-1	152.00	LFT
0066	706-11418	RAILING, STEEL TYPE PS-1	152.00	LFT
0067	706-12272	REINFORCED CONCRETE MOMENT SLAB, 10 IN.	39.00	SYS
0068	706-51020	RAILING, CONCRETE TYPE C	6.90	CYS

0069	709-51821	SURFACE SEAL	1.00	LS
0070	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	36.00	LFT
0071	720-93409	INLET, TYPE B15, MODIFIED	1.00	EACH
0072	722-12732	LONGITUDINAL GROOVING	586.00	SYS
0073	724-03855	EXPANSION JOINT SLIDING PLATE	13.00	LFT
0074	801-03290	CONSTRUCTION SIGN, TYPE C	1.00	EACH
0075	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00	EACH
0076	801-06625	DETOUR ROUTE MARKER ASSEMBLY	21.00	EACH
0077	801-06640	CONSTRUCTION SIGN, TYPE A	15.00	EACH
0078	801-06645	CONSTRUCTION SIGN, TYPE B	13.00	EACH
0079	801-06710	FLASHING ARROW SIGN	30.00	DAY
0080	801-06775	MAINTAINING TRAFFIC	1.00	LS
0081	801-07118	BARRICADE, TYPE III-A	72.00	LFT
0082	801-07119	BARRICADE, TYPE III-B	36.00	LFT
0083	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	48.00	LFT
0084	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0085	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	8.00	LFT
0086	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	16.00	SFT
0087	802-76055	SIGN POST, TYPE A	8.00	LFT
0088	805-01843	HANDHOLE, SIGNAL, ADJUST TO GRADE	1.00	EACH
0089	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	314.00	LFT
0090	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	175.00	LFT
0091	805-78785	SIGNAL DETECTOR HOUSING	1.00	EACH
0092	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	108.00	LFT
0093	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	10.00	LFT
0094	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	17.00	LFT

Call: 660

Contract: B -44415-A

Section No.: 1 SUPERSTRUCTURE REPAIR AND REHABILITATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0009	205-12108	STORMWATER MANAGEMENT BUDGET	7400.00	DOL
0010	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0011	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0012	621-06559	MULCHED SEEDING, TYPE R	1180.00	SYS
0013	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0014	628-12683	FIELD OFFICE, TYPE D	6.00	MOS
0015	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0016	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0017	710-09158	PATCHING CONCRETE STRUCTURES	430.00	SFT
0018	724-12461	CONCRETE FOR PATCHING BRIDGE EXPANSION JOINT	100.00	SFT
0019	724-12773	BRIDGE EXPANSION JOINT, TYPE PCF	100.00	LFT
0020	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2210.00	LFT
0021	801-06640	CONSTRUCTION SIGN, TYPE A	24.00	EACH
0022	801-06645	CONSTRUCTION SIGN, TYPE B	1.00	EACH
0023	801-06775	MAINTAINING TRAFFIC	1.00	LS
0024	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.00	EACH
0025	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	520.00	LFT
0026	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	20.00	LFT
0027	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	20.00	LFT

Call: 670

Contract: B -44584-A

Section No.: 1 DEBRIS REMOVAL FROM CHANNEL

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0009	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
	0010	202-02272	PAVED SIDE DITCH, REMOVE	20.00	LFT
	0011	203-02000	EXCAVATION, COMMON	220.00	CYS
	0012	203-51223	EXCAVATION, WATERWAY	375.00	CYS
	0013	205-11626	PUMP AROUND	3.00	EACH
	0014	205-12108	STORMWATER MANAGEMENT BUDGET	60882.00	DOL
	0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0016	206-51235	COFFERDAM	1.00	LS
	0017	303-01180	COMPACTED AGGREGATE, NO. 53	16.00	TON
	0018	601-03464	GUARDRAIL, STEEL CURVED TERMINAL END SECTION	1.00	EACH
	0019	601-06035	GUARDRAIL, RESET	25.00	LFT
	0020	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	87.50	LFT
	0021	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	1.00	EACH
	0022	616-05688	RIPRAP, CLASS 1	15.00	TON
	0023	616-06405	RIPRAP, REVETMENT	696.00	TON
	0024	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	42.00	SYS
	0025	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	836.00	SYS
	0026	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	7.00	EACH
	0027	621-06559	MULCHED SEEDING, TYPE R	2372.00	SYS
	0028	621-12612	SEED MIXTURE, FLOODPLAIN	15.00	LBS
	0029	710-09158	PATCHING CONCRETE STRUCTURES	7.00	SFT
	0030	713-04331	TEMPORARY CAUSEWAY	1.00	LS
	0031	715-01662	PIPE CLEANING, DIAMETER 12 IN. TO 48 IN.	41.00	LFT

0032	715-09064	VIDEO INSPECTION FOR PIPE	41.00	LFT
0033	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1637.00	LFT
0034	801-06640	CONSTRUCTION SIGN, TYPE A	81.00	EACH
0035	801-06645	CONSTRUCTION SIGN, TYPE B	16.00	EACH
0036	801-06710	FLASHING ARROW SIGN	9.00	DAY
0037	801-06775	MAINTAINING TRAFFIC	1.00	LS
0038	801-12042	TRUCK MOUNTED ATTENUATOR	9.00	DAY
0039	801-12324	LAW ENFORCEMENT OFFICER	160.00	HRS

Call: 680

Contract: B -44586-A

Section No.: 1

SCOUR PROTECTION

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0009	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
	0010	201-90788	DEBRIS, REMOVE, STRUCTURE NO.	1.00	LS
	0011	203-51223	EXCAVATION, WATERWAY	82.00	CYS
	0012	205-11626	PUMP AROUND	4.00	EACH
	0013	205-12108	STORMWATER MANAGEMENT BUDGET	31254.00	DOL
	0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0015	206-51220	EXCAVATION, WET	32.00	CYS
	0016	603-06060	FENCE, FARM FIELD, RESET	225.00	LFT
	0017	616-05688	RIPRAP, CLASS 1	286.00	TON
	0018	616-05689	RIPRAP, CLASS 2	46.00	TON
	0019	616-06405	RIPRAP, REVETMENT	112.00	TON
	0020	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	481.00	SYS
	0021	616-93772	INSPECTION HOLE	2.00	EACH
	0022	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
	0023	621-06559	MULCHED SEEDING, TYPE R	1218.00	SYS
	0024	621-06560	MULCHED SEEDING, TYPE U	738.00	SYS
	0025	628-09403	FIELD OFFICE, TYPE C	8.00	MOS
	0026	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
	0027	801-06640	CONSTRUCTION SIGN, TYPE A	90.00	EACH
	0028	801-06645	CONSTRUCTION SIGN, TYPE B	5.00	EACH
	0029	801-06775	MAINTAINING TRAFFIC	1.00	LS
	0030	801-07118	BARRICADE, TYPE III-A	48.00	LFT
	0031	801-12031	TEMPORARY PORTABLE RUMBLE STRIPS	21.00	DAY

Call: 690

Contract: B -44738-A

Section No.: 1 BRIDGE REHABILITATION OR REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	601-06035	GUARDRAIL, RESET	50.00	LFT
0008	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0009	619-12460	DISPOSAL OF CLEANING WASTE, NON-HAZARDOUS, BRIDGE NO.	1.00	LS
0010	619-51860	COAT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0011	628-09403	FIELD OFFICE, TYPE C	6.00	MOS
0012	702-12611	ULTRA HIGH PERFORMANCE CONCRETE	0.40	CYS
0013	710-09158	PATCHING CONCRETE STRUCTURES	200.00	SFT
0014	711-51864	DRILLED HOLE	32.00	EACH
0015	711-51878	JACKING AND SUPPORTING GIRDERS	1.00	LS
0016	711-96800	STUD SHEAR CONNECTORS	80.00	EACH
0017	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0018	726-95870	BEARING ASSEMBLY, PTFE	8.00	EACH
0019	729-11819	STRAIGHTEN STEEL MEMBER	1.00	LS
0020	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9635.00	LFT
0021	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	5595.00	LFT
0022	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	60.00	LFT
0023	801-06640	CONSTRUCTION SIGN, TYPE A	46.00	EACH
0024	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	EACH
0025	801-06710	FLASHING ARROW SIGN	8.00	DAY
0026	801-06775	MAINTAINING TRAFFIC	1.00	LS
0027	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	1.00	EACH
0028	801-07118	BARRICADE, TYPE III-A	96.00	LFT
0029	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	570.00	LFT
0030	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0031	801-12042	TRUCK MOUNTED ATTENUATOR	4.00	DAY

0032 801-12324 LAW ENFORCEMENT OFFICER

32.00 HRS

Call: 710

Contract: B -44947-A

Section No.: 1 BRIDGE REHABILITATION OR REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0008	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0009	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0010	619-12506	CLEAN STEEL BRIDGE, TOP FLANGES, TYPE QP-2, BRIDGE NO.	1.00	LS
0011	619-51860	COAT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0012	628-09403	FIELD OFFICE, TYPE C	9.00	MOS
0013	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0014	702-51863	FIELD DRILLED HOLE IN CONCRETE	16.00	EACH
0015	703-06029	REINFORCING BARS, EPOXY COATED	8502.00	LBS
0016	704-51002	CONCRETE, C, SUPERSTRUCTURE	24.40	CYS
0017	706-11600	RAILING, CONCRETE TYPE FC	4.20	CYS
0018	709-51821	SURFACE SEAL	1.00	LS
0019	711-51035	STRUCTURAL STEEL	9116.00	LBS
0020	711-51864	DRILLED HOLE	261.00	EACH
0021	711-96479	BOLT, REMOVE	491.00	EACH
0022	729-11819	STRAIGHTEN STEEL MEMBER	1.00	LS
0023	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH
0024	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1580.00	LFT
0025	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3980.00	LFT
0026	801-06625	DETOUR ROUTE MARKER ASSEMBLY	11.00	EACH
0027	801-06640	CONSTRUCTION SIGN, TYPE A	22.00	EACH
0028	801-06645	CONSTRUCTION SIGN, TYPE B	15.00	EACH
0029	801-06710	FLASHING ARROW SIGN	18.00	DAY
0030	801-06775	MAINTAINING TRAFFIC	1.00	LS
0031	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	1.00	EACH

0032	801-07118	BARRICADE, TYPE III-A	192.00	LFT
0033	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	300.00	LFT
0034	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	3.00	EACH
0035	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	44.00	LFT
0036	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	44.00	LFT

Call: 720

Contract: B -45204-A

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	693.00	SYS
0013	202-51133	RAILING, REMOVE	63.00	LFT
0014	203-02000	EXCAVATION, COMMON	215.00	CYS
0015	203-08607	LINEAR GRADING	374.00	LFT
0016	203-51223	EXCAVATION, WATERWAY	90.00	CYS
0017	205-11626	PUMP AROUND	1.00	EACH
0018	205-12108	STORMWATER MANAGEMENT BUDGET	12901.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	1169.00	SYS
0021	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	1270.00	SYS
0022	302-06464	SUBBASE FOR PCCP	177.00	CYS
0023	303-01180	COMPACTED AGGREGATE, NO. 53	129.00	TON
0024	306-08043	MILLING, TRANSITION	334.00	SYS
0025	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	65.00	TON
0026	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	63.00	TON
0027	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	250.00	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	707.00	LFT
0029	401-10259	JOINT ADHESIVE, INTERMEDIATE	437.00	LFT
0030	401-11785	LIQUID ASPHALT SEALANT	707.00	LFT
0031	406-05521	ASPHALT FOR TACK COAT	1238.00	SYS

0032	502-06329	PCCP, 12 IN.	279.00	SYS
0033	503-03489	RETROFITTED TIE BARS	70.00	EACH
0034	503-05240	D-1 CONTRACTION JOINT	240.00	LFT
0035	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT, 12 IN.	187.00	SYS
0036	503-12478	TERMINAL JOINT, TYPE PCCP	44.00	LFT
0037	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	42.00	LFT
0038	601-02241	GUARDRAIL, REMOVE	785.00	LFT
0039	601-06035	GUARDRAIL, RESET	180.00	LFT
0040	601-07050	GUARDRAIL END TREATMENT, TYPE OS, RESET	1.00	EACH
0041	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	262.00	LFT
0042	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	2.00	EACH
0043	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	4.00	EACH
0044	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00	EACH
0045	602-06729	BARRIER DELINEATOR	8.00	EACH
0046	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	527.00	LFT
0047	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	204.00	SYS
0048	616-06405	RIPRAP, REVETMENT	21.00	TON
0049	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	28.00	SYS
0050	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0051	621-06559	MULCHED SEEDING, TYPE R	201.00	SYS
0052	621-06565	MULCHING MATERIAL	1.00	TON
0053	621-12612	SEED MIXTURE, FLOODPLAIN	3.00	LBS
0054	621-52448	SIGN, "DO NOT SPRAY"	1.00	EACH
0055	628-09403	FIELD OFFICE, TYPE C	6.00	MOS
0056	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0057	628-12685	TELEPHONE SERVICE, TYPE A	6.00	MOS
0058	702-51863	FIELD DRILLED HOLE IN CONCRETE	70.00	EACH
0059	702-51863	FIELD DRILLED HOLE IN CONCRETE	48.00	EACH
0060	703-06029	REINFORCING BARS, EPOXY COATED	13363.00	LBS
0061	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	84.00	EACH
0062	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	4.00	EACH
0063	709-51821	SURFACE SEAL	1.00	LS
0064	722-01066	HYDRODEMOLITION	334.00	SYS
0065	722-12380	BRIDGE DECK OVERLAY BUDGET	6400.00	DOL
0066	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	334.00	SYS
0067	722-12732	LONGITUDINAL GROOVING	527.00	SYS
0068	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6372.00	LFT

0069	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0070	801-06640	CONSTRUCTION SIGN, TYPE A	10.00	EACH
0071	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	EACH
0072	801-06775	MAINTAINING TRAFFIC	1.00	LS
0073	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00	EACH
0074	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	491.00	LFT
0075	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	111.00	LFT
0076	801-12081	PORTABLE SIGNAL	1.00	LS
0077	801-12482	DRIVEWAY ASSISTANCE DEVICE	1.00	EACH
0078	802-04893	REFERENCE POST	2.00	EACH
0079	802-91122	SIGN, GROUND MOUNTED, RESET	2.00	EACH
0080	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	973.00	LFT
0081	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	973.00	LFT
0082	808-12032	GROOVING FOR PAVEMENT MARKINGS	1494.00	LFT
0083	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	3.00	EACH

Call: 720

Contract: B -45204-A

Section No.: 2 LATEX MODIFIED OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0084	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	334.00	SYS

Call: 720

Contract: B -45204-A

Section No.: 3 SILICA FUME MODIFIED OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0085	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	334.00	SYS

Call: 750

Contract: M -45406-A

Section No.: 1 MOWING

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	623-04884	MOWING, CYCLE NO. 1	1.00	CYCL
0004	623-04885	MOWING, CYCLE NO. 2	1.00	CYCL
0005	623-04886	MOWING, CYCLE NO. 3	1.00	CYCL
0006	623-04887	MOWING, CYCLE NO. 4	1.00	CYCL
0007	623-05684	MOWING, CYCLE NO. 5	1.00	CYCL
0008	623-06008	MOWING, CYCLE NO. 7	1.00	CYCL
0009	623-06010	MOWING, CYCLE NO. 9	1.00	CYCL
0010	623-06704	MOWING, CYCLE NO. 6	1.00	CYCL
0011	623-06707	MOWING, CYCLE NO. 8	1.00	CYCL

Call: 780

Contract: T -41754-A

Section No.: 1 ITS TRAFFIC MANAGEMENT SYSTEMS

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0008	601-06035	GUARDRAIL, RESET	100.00	LFT
0009	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	831.25	LFT
0010	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED, 6 FT 3 IN. SPACING	250.00	LFT
0011	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00	EACH
0012	601-94690	GUARDRAIL END TREATMENT, TYPE MS	1.00	EACH
0013	601-99123	GUARDRAIL TRANSITION, TYPE GP	4.00	EACH
0014	628-09403	FIELD OFFICE, TYPE C	24.00	MOS
0015	801-06640	CONSTRUCTION SIGN, TYPE A	72.00	EACH
0016	801-06645	CONSTRUCTION SIGN, TYPE B	24.00	EACH
0017	801-06710	FLASHING ARROW SIGN	6.00	DAY
0018	801-06775	MAINTAINING TRAFFIC	1.00	LS
0019	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	3120.00	LFT
0020	801-12042	TRUCK MOUNTED ATTENUATOR	6.00	DAY
0021	801-12324	LAW ENFORCEMENT OFFICER	48.00	HRS
0022	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	60.00	LFT
0023	802-06402	DYNAMIC MESSAGE SIGN	6.00	EACH
0024	802-12648	ITS ROADSIDE BALANCED CANTILEVER STRUCTURE	3.00	EACH
0025	802-12649	ITS ROADSIDE BALANCED CANTILEVER STRUCTURE FOUNDATION CONCRETE WITH GROUNDING	3.00	EACH
0026	805-04973	CONDUIT	1732.00	LFT
0027	805-04973	CONDUIT	1823.00	LFT
0028	805-04973	CONDUIT	124.00	LFT
0029	805-08244	CELLULAR MODEM KIT	12.00	EACH
0030	805-09845	CONTACT CLOSURE CARD	9.00	EACH
0031	805-09846	RECEIVER PROCESSOR	9.00	EACH

0032	805-10107	WIRELESS MAGNETOMETER DETECTOR	82.00 EACH
0033	805-10108	WIRELESS REPEATER	4.00 EACH
0034	807-04651	WIRE	5000.00 LFT
0035	807-04651	WIRE	5000.00 LFT
0036	807-78590	HANDHOLE	43.00 EACH
0037	809-04652	SERVICE POINT	11.00 EACH
0038	809-04652	SERVICE POINT	9.00 EACH
0039	809-04982	CABLE	1354.00 LFT
0040	809-06101	FOUNDATION	9.00 EACH
0041	809-06128	CCTV ASSEMBLY	9.00 EACH
0042	809-08398	ITS CONTROLLER CABINET	9.00 EACH
0043	809-08399	ITS CONTROLLER CABINET FOUNDATION	9.00 EACH
0044	809-09343	ITS	6.00 EACH
0045	809-09343	ITS	3.00 EACH
0046	809-09343	ITS	12.00 EACH
0047	809-11707	ITS FIELD SWITCH	12.00 EACH

Call: 790

Contract: T -41764-A

Section No.: 1 ITS DEVICES MAINTENANCE

Line			
Item No	Item Code	Description	Quantity Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0002	109-08360	CONTRACT LIENS	1.00 DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0006	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	1190.00 DOL
0007	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	900.00 DOL
0008	202-06541	REMOVE	2.00 EACH
0009	202-86946	HANDHOLE, REMOVE	2.00 EACH
0010	202-90277	DETECTOR HOUSING, REMOVE	2.00 EACH
0011	202-95579	SERVICE POINT, REMOVE	2.00 EACH
0012	301-12231	COMPACTED AGGREGATE, NO. 2	2.00 CYS
0013	702-90915	CONCRETE, A	2.00 CYS
0014	715-04985	VAULT	2.00 EACH
0015	715-04985	VAULT	2.00 EACH
0016	801-06640	CONSTRUCTION SIGN, TYPE A	2.00 EACH
0017	801-06710	FLASHING ARROW SIGN	2.00 DAY
0018	801-06775	MAINTAINING TRAFFIC	1.00 LS
0019	802-03821	SIGN, SHEET, WITH LEGEND	2.00 EACH
0020	805-01439	MICROWAVE DETECTOR	2.00 EACH
0021	805-01479	CONTROLLER CABINET FOUNDATION, TYPE P1, MODIFIED	2.00 EACH
0022	805-01842	HANDHOLE, SIGNAL, TYPE 1	2.00 EACH
0023	805-01843	HANDHOLE, SIGNAL, ADJUST TO GRADE	2.00 EACH
0024	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	2.00 LFT
0025	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	2.00 LFT
0026	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00 LS
0027	805-02202	SIGNAL DETECTOR HOUSING, DOUBLE	2.00 EACH
0028	805-02658	CABLE COAXIAL	2.00 LFT
0029	805-04973	CONDUIT	2.00 LFT
0030	805-06997	CAMERA	2.00 EACH
0031	805-07212	SPLICE KIT	2.00 EACH

0032	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	2.00	LFT
0033	805-09089	RADIO, YAGI ANTENNA	2.00	EACH
0034	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	2.00	EACH
0035	805-09540	LOOP DETECTOR RACK	2.00	EACH
0036	805-09845	CONTACT CLOSURE CARD	2.00	EACH
0037	805-09846	RECEIVER PROCESSOR	2.00	EACH
0038	805-10107	WIRELESS MAGNETOMETER DETECTOR	2.00	EACH
0039	805-10108	WIRELESS REPEATER	2.00	EACH
0040	805-11539	AUXILIARY BIU PANEL	2.00	EACH
0041	805-11540	MICROLOOP DETECTOR PROBE	2.00	EACH
0042	805-11569	RADIO SPLITTER	2.00	EACH
0043	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	2.00	LFT
0044	805-11814	CONDUIT, HDPE, 2 IN. SCHEDULE 40	2.00	LFT
0045	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	2.00	LFT
0046	805-11817	PEDESTRIAN PUSH BUTTON, APS	2.00	EACH
0047	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	2.00	LFT
0048	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	2.00	LFT
0049	805-78785	SIGNAL DETECTOR HOUSING	2.00	EACH
0050	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	2.00	LFT
0051	805-91706	ANCHOR BOLT REPAIR	2.00	EACH
0052	805-92951	SIGNAL DETECTOR HOUSING ADJUST TO GRADE	2.00	EACH
0053	805-93067	CONTROLLER CABINET, TYPE P	2.00	EACH
0054	807-01617	HANDHOLE, COVER AND RING	2.00	EACH
0055	807-02618	WIRE, NO. 2 COPPER, 3 1/C	2.00	LFT
0056	807-04651	WIRE	2.00	LFT
0057	807-04651	WIRE	6.00	LFT
0058	807-04651	WIRE	2.00	LFT
0059	807-04651	WIRE	2.00	LFT
0060	807-04651	WIRE	2.00	LFT
0061	807-78590	HANDHOLE	2.00	EACH
0062	807-87085	ELECTRICIAN	2.00	HRS
0063	809-04652	SERVICE POINT	2.00	EACH
0064	809-04652	SERVICE POINT	2.00	EACH
0065	809-04652	SERVICE POINT	2.00	EACH
0066	809-04652	SERVICE POINT	2.00	EACH
0067	809-04652	SERVICE POINT	2.00	EACH
0068	809-04652	SERVICE POINT	2.00	EACH

0069	809-04652	SERVICE POINT	2.00 EACH
0070	809-04652	SERVICE POINT	2.00 EACH
0071	809-04652	SERVICE POINT	2.00 EACH
0072	809-04956	PANEL FOR FIBER OPTICS	2.00 EACH
0073	809-04970	FIBER OPTIC	2.00 EACH
0074	809-04970	FIBER OPTIC	2.00 EACH
0075	809-04970	FIBER OPTIC	2.00 EACH
0076	809-04970	FIBER OPTIC	2.00 EACH
0077	809-04970	FIBER OPTIC	2.00 EACH
0078	809-04982	CABLE	2.00 LFT
0079	809-04982	CABLE	2.00 LFT
0080	809-06114	ANTENNA	2.00 EACH
0081	809-06128	CCTV ASSEMBLY	2.00 EACH
0082	809-08398	ITS CONTROLLER CABINET	2.00 EACH
0083	809-08398	ITS CONTROLLER CABINET	2.00 EACH
0084	809-08398	ITS CONTROLLER CABINET	2.00 EACH
0085	809-08399	ITS CONTROLLER CABINET FOUNDATION	2.00 EACH
0086	809-09343	ITS	2.00 EACH
0087	809-09343	ITS	2.00 EACH
0088	809-09343	ITS	2.00 EACH
0089	809-09343	ITS	2.00 EACH
0090	809-09343	ITS	2.00 EACH
0091	809-09343	ITS	2.00 EACH
0092	809-09343	ITS	2.00 EACH
0093	809-11707	ITS FIELD SWITCH	1.00 EACH
0094	809-11707	ITS FIELD SWITCH	1.00 EACH
0095	809-11707	ITS FIELD SWITCH	1.00 EACH
0096	809-11707	ITS FIELD SWITCH	1.00 EACH
0097	809-11707	ITS FIELD SWITCH	1.00 EACH
0098	809-11707	ITS FIELD SWITCH	1.00 EACH
0099	809-12711	ROADWAY WEATHER INFORMATION SYSTEM	2.00 DOL
0100	809-94971	FIBER OPTIC CABLE	2.00 LFT

Call: 800

Contract: T -41766-A

Section No.: 1 TRAFFIC MANAGEMENT SYSTEM PROJECT

Line			
Item No	Item Code	Description	Quantity Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0002	109-08360	CONTRACT LIENS	1.00 DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0006	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	2.00 DOL
0007	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	2.00 DOL
0008	202-06541	REMOVE	2.00 EACH
0009	202-86946	HANDHOLE, REMOVE	2.00 EACH
0010	202-90277	DETECTOR HOUSING, REMOVE	2.00 EACH
0011	202-95579	SERVICE POINT, REMOVE	2.00 EACH
0012	301-12231	COMPACTED AGGREGATE, NO. 2	2.00 CYS
0013	702-90915	CONCRETE, A	2.00 CYS
0014	715-04985	VAULT	2.00 EACH
0015	715-04985	VAULT	2.00 EACH
0016	801-06640	CONSTRUCTION SIGN, TYPE A	2.00 EACH
0017	801-06710	FLASHING ARROW SIGN	2.00 DAY
0018	801-06775	MAINTAINING TRAFFIC	1.00 LS
0019	802-03821	SIGN, SHEET, WITH LEGEND	2.00 EACH
0020	805-01439	MICROWAVE DETECTOR	2.00 EACH
0021	805-01479	CONTROLLER CABINET FOUNDATION, TYPE P1, MODIFIED	2.00 EACH
0022	805-01842	HANDHOLE, SIGNAL, TYPE 1	2.00 EACH
0023	805-01843	HANDHOLE, SIGNAL, ADJUST TO GRADE	2.00 EACH
0024	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	2.00 LFT
0025	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	2.00 LFT
0026	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00 LS
0027	805-02202	SIGNAL DETECTOR HOUSING, DOUBLE	2.00 EACH
0028	805-02658	CABLE COAXIAL	2.00 LFT
0029	805-04973	CONDUIT	2.00 LFT
0030	805-06997	CAMERA	2.00 EACH
0031	805-07212	SPLICE KIT	2.00 EACH

0032	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	2.00	LFT
0033	805-09089	RADIO, YAGI ANTENNA	2.00	EACH
0034	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	2.00	EACH
0035	805-09540	LOOP DETECTOR RACK	2.00	EACH
0036	805-09845	CONTACT CLOSURE CARD	2.00	EACH
0037	805-09846	RECEIVER PROCESSOR	2.00	EACH
0038	805-10107	WIRELESS MAGNETOMETER DETECTOR	2.00	EACH
0039	805-10108	WIRELESS REPEATER	2.00	EACH
0040	805-11539	AUXILIARY BIU PANEL	2.00	EACH
0041	805-11540	MICROLOOP DETECTOR PROBE	2.00	EACH
0042	805-11569	RADIO SPLITTER	2.00	EACH
0043	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	2.00	LFT
0044	805-11814	CONDUIT, HDPE, 2 IN. SCHEDULE 40	2.00	LFT
0045	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	4.00	LFT
0046	805-11817	PEDESTRIAN PUSH BUTTON, APS	2.00	EACH
0047	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	2.00	LFT
0048	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	2.00	LFT
0049	805-78785	SIGNAL DETECTOR HOUSING	2.00	EACH
0050	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	2.00	LFT
0051	805-91706	ANCHOR BOLT REPAIR	2.00	EACH
0052	805-92951	SIGNAL DETECTOR HOUSING ADJUST TO GRADE	2.00	EACH
0053	805-93067	CONTROLLER CABINET, TYPE P	2.00	EACH
0054	807-01617	HANDHOLE, COVER AND RING	2.00	EACH
0055	807-02618	WIRE, NO. 2 COPPER, 3 1/C	2.00	LFT
0056	807-04651	WIRE	2.00	LFT
0057	807-04651	WIRE	6.00	LFT
0058	807-04651	WIRE	2.00	LFT
0059	807-04651	WIRE	2.00	LFT
0060	807-04651	WIRE	2.00	LFT
0061	807-78590	HANDHOLE	2.00	EACH
0062	807-87085	ELECTRICIAN	2.00	HRS
0063	809-04652	SERVICE POINT	2.00	EACH
0064	809-04652	SERVICE POINT	2.00	EACH
0065	809-04652	SERVICE POINT	2.00	EACH
0066	809-04652	SERVICE POINT	2.00	EACH
0067	809-04652	SERVICE POINT	2.00	EACH
0068	809-04652	SERVICE POINT	2.00	EACH

0069	809-04652	SERVICE POINT	2.00 EACH
0070	809-04652	SERVICE POINT	2.00 EACH
0071	809-04652	SERVICE POINT	2.00 EACH
0072	809-04956	PANEL FOR FIBER OPTICS	2.00 EACH
0073	809-04970	FIBER OPTIC	2.00 EACH
0074	809-04970	FIBER OPTIC	2.00 EACH
0075	809-04970	FIBER OPTIC	2.00 EACH
0076	809-04970	FIBER OPTIC	2.00 EACH
0077	809-04970	FIBER OPTIC	2.00 EACH
0078	809-04982	CABLE	2.00 LFT
0079	809-04982	CABLE	2.00 LFT
0080	809-06114	ANTENNA	2.00 EACH
0081	809-06128	CCTV ASSEMBLY	2.00 EACH
0082	809-08398	ITS CONTROLLER CABINET	2.00 EACH
0083	809-08398	ITS CONTROLLER CABINET	2.00 EACH
0084	809-08398	ITS CONTROLLER CABINET	2.00 EACH
0085	809-08399	ITS CONTROLLER CABINET FOUNDATION	2.00 EACH
0086	809-09343	ITS	2.00 EACH
0087	809-09343	ITS	2.00 EACH
0088	809-09343	ITS	2.00 EACH
0089	809-09343	ITS	2.00 EACH
0090	809-09343	ITS	2.00 EACH
0091	809-09343	ITS	2.00 EACH
0092	809-09343	ITS	2.00 EACH
0093	809-11707	ITS FIELD SWITCH	2.00 EACH
0094	809-11707	ITS FIELD SWITCH	2.00 EACH
0095	809-11707	ITS FIELD SWITCH	2.00 EACH
0096	809-12711	ROADWAY WEATHER INFORMATION SYSTEM	2.00 DOL
0097	809-94971	FIBER OPTIC CABLE	2.00 LFT

Call: 810

Contract: T -41767-A

Section No.: 1 ITS DEVICES MAINTENANCE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0002	109-08360	CONTRACT LIENS	1.00	DOL
	0003	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0004	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	2.00	DOL
	0005	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	2.00	DOL
	0006	202-06541	REMOVE	2.00	EACH
	0007	202-86946	HANDHOLE, REMOVE	2.00	EACH
	0008	202-90277	DETECTOR HOUSING, REMOVE	2.00	EACH
	0009	202-95579	SERVICE POINT, REMOVE	2.00	EACH
	0010	301-12231	COMPACTED AGGREGATE, NO. 2	2.00	CYS
	0011	702-90915	CONCRETE, A	2.00	CYS
	0012	715-04985	VAULT	2.00	EACH
	0013	715-04985	VAULT	2.00	EACH
	0014	801-06640	CONSTRUCTION SIGN, TYPE A	2.00	EACH
	0015	801-06710	FLASHING ARROW SIGN	2.00	DAY
	0016	801-06775	MAINTAINING TRAFFIC	1.00	LS
	0017	802-03821	SIGN, SHEET, WITH LEGEND	2.00	EACH
	0018	805-01439	MICROWAVE DETECTOR	2.00	EACH
	0019	805-01479	CONTROLLER CABINET FOUNDATION, TYPE P1, MODIFIED	2.00	EACH
	0020	805-01842	HANDHOLE, SIGNAL, TYPE 1	2.00	EACH
	0021	805-01843	HANDHOLE, SIGNAL, ADJUST TO GRADE	2.00	EACH
	0022	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	2.00	LFT
	0023	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	2.00	LFT
	0024	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
	0025	805-02202	SIGNAL DETECTOR HOUSING, DOUBLE	2.00	EACH
	0026	805-02658	CABLE COAXIAL	2.00	LFT
	0027	805-04973	CONDUIT	2.00	LFT
	0028	805-06997	CAMERA	2.00	EACH
	0029	805-07212	SPLICE KIT	2.00	EACH
	0030	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	2.00	LFT
	0031	805-09089	RADIO, YAGI ANTENNA	2.00	EACH

0032	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	2.00 EACH
0033	805-09540	LOOP DETECTOR RACK	2.00 EACH
0034	805-09845	CONTACT CLOSURE CARD	2.00 EACH
0035	805-09846	RECEIVER PROCESSOR	2.00 EACH
0036	805-10107	WIRELESS MAGNETOMETER DETECTOR	2.00 EACH
0037	805-10108	WIRELESS REPEATER	2.00 EACH
0038	805-11539	AUXILIARY BIU PANEL	2.00 EACH
0039	805-11540	MICROLOOP DETECTOR PROBE	2.00 EACH
0040	805-11569	RADIO SPLITTER	2.00 EACH
0041	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	2.00 LFT
0042	805-11814	CONDUIT, HDPE, 2 IN. SCHEDULE 40	2.00 LFT
0043	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	2.00 LFT
0044	805-11817	PEDESTRIAN PUSH BUTTON, APS	2.00 EACH
0045	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	2.00 LFT
0046	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	2.00 LFT
0047	805-78785	SIGNAL DETECTOR HOUSING	2.00 EACH
0048	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	2.00 LFT
0049	805-91706	ANCHOR BOLT REPAIR	2.00 EACH
0050	805-92951	SIGNAL DETECTOR HOUSING ADJUST TO GRADE	2.00 EACH
0051	805-93067	CONTROLLER CABINET, TYPE P	2.00 EACH
0052	807-01617	HANDHOLE, COVER AND RING	2.00 EACH
0053	807-02618	WIRE, NO. 2 COPPER, 3 1/C	2.00 LFT
0054	807-04651	WIRE	2.00 LFT
0055	807-04651	WIRE	6.00 LFT
0056	807-04651	WIRE	2.00 LFT
0057	807-04651	WIRE	2.00 LFT
0058	807-04651	WIRE	2.00 LFT
0059	807-78590	HANDHOLE	2.00 EACH
0060	807-87085	ELECTRICIAN	2.00 HRS
0061	809-04652	SERVICE POINT	2.00 EACH
0062	809-04652	SERVICE POINT	2.00 EACH
0063	809-04652	SERVICE POINT	2.00 EACH
0064	809-04652	SERVICE POINT	2.00 EACH
0065	809-04652	SERVICE POINT	2.00 EACH
0066	809-04652	SERVICE POINT	2.00 EACH
0067	809-04652	SERVICE POINT	2.00 EACH
0068	809-04652	SERVICE POINT	2.00 EACH

0069	809-04652	SERVICE POINT	2.00 EACH
0070	809-04956	PANEL FOR FIBER OPTICS	2.00 EACH
0071	809-04970	FIBER OPTIC	2.00 EACH
0072	809-04970	FIBER OPTIC	2.00 EACH
0073	809-04970	FIBER OPTIC	2.00 EACH
0074	809-04970	FIBER OPTIC	2.00 EACH
0075	809-04970	FIBER OPTIC	2.00 EACH
0076	809-04982	CABLE	2.00 LFT
0077	809-04982	CABLE	2.00 LFT
0078	809-06114	ANTENNA	2.00 EACH
0079	809-06128	CCTV ASSEMBLY	2.00 EACH
0080	809-08398	ITS CONTROLLER CABINET	2.00 EACH
0081	809-08398	ITS CONTROLLER CABINET	2.00 EACH
0082	809-08398	ITS CONTROLLER CABINET	2.00 EACH
0083	809-08399	ITS CONTROLLER CABINET FOUNDATION	2.00 EACH
0084	809-09343	ITS	2.00 EACH
0085	809-09343	ITS	2.00 EACH
0086	809-09343	ITS	2.00 EACH
0087	809-09343	ITS	2.00 EACH
0088	809-09343	ITS	2.00 EACH
0089	809-09343	ITS	2.00 EACH
0090	809-09343	ITS	2.00 EACH
0091	809-11707	ITS FIELD SWITCH	2.00 EACH
0092	809-11707	ITS FIELD SWITCH	2.00 EACH
0093	809-11707	ITS FIELD SWITCH	2.00 EACH
0094	809-12711	ROADWAY WEATHER INFORMATION SYSTEM	2.00 DOL
0095	809-94971	FIBER OPTIC CABLE	2.00 LFT

Call: 820

Contract: T -42335-A

Section No.: 1 ADA SIDEWALK RAMP CONSTRUCTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0009	202-02279	CURB AND GUTTER, REMOVE	1807.00	LFT
0010	202-52710	SIDEWALK CONCRETE, REMOVE	965.00	SYS
0011	202-91385	INLET, REMOVE	1.00	EACH
0012	205-12108	STORMWATER MANAGEMENT BUDGET	14135.00	DOL
0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0014	306-08034	MILLING, ASPHALT, 1 1/2 IN.	749.00	SYS
0015	604-06070	SIDEWALK, CONCRETE	459.00	SYS
0016	604-08086	CURB RAMP, CONCRETE	459.00	SYS
0017	604-12083	DETECTABLE WARNING SURFACES	102.00	SYS
0018	605-06120	CURB, CONCRETE	1262.00	LFT
0019	605-06140	CURB AND GUTTER, CONCRETE	389.00	LFT
0020	610-07488	HMA FOR APPROACHES, TYPE C	55.00	TON
0021	621-06567	WATER	2.00	KGAL
0022	621-06570	TOPSOIL	95.00	CYS
0023	621-06574	SODDING	581.00	SYS
0024	628-09401	FIELD OFFICE, TYPE A	12.00	MOS
0025	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0026	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	70.00	LFT
0027	715-09064	VIDEO INSPECTION FOR PIPE	165.00	LFT
0028	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	1.00	EACH
0029	720-12797	CASTING, INLET, ADJUST TO GRADE	24.00	EACH
0030	720-44025	CASTING, TYPE 4, FURNISH AND ADJUST TO GRADE	2.00	EACH
0031	720-45010	INLET, TYPE A3	1.00	EACH

0032	720-45015	INLET, TYPE A8	3.00 EACH
0033	720-91051	INLET, TYPE A	3.00 EACH
0034	801-06640	CONSTRUCTION SIGN, TYPE A	82.00 EACH
0035	801-06645	CONSTRUCTION SIGN, TYPE B	87.00 EACH
0036	801-06775	MAINTAINING TRAFFIC	1.00 LS
0037	801-07118	BARRICADE, TYPE III-A	480.00 LFT
0038	801-11990	TEMPORARY CURB RAMP	80.00 EACH
0039	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.00 EACH
0040	805-01830	CONFLICT MONITOR CHANGEOUT	2.00 EACH
0041	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	10.00 EACH
0042	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	8.00 EACH
0043	805-04133	SIGNAL POLE, PEDESTAL, 12 FT	8.00 EACH
0044	805-06483	CONTROLLER	2.00 EACH
0045	805-11799	RECTANGULAR RAPID FLASHING BEACON	2.00 EACH
0046	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	55.00 LFT
0047	805-11817	PEDESTRIAN PUSH BUTTON, APS	10.00 EACH
0048	805-78412	SIGNAL POLE, PEDESTAL, 9 FT	2.00 EACH
0049	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GAUGE	797.00 LFT
0050	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	1534.00 LFT
0051	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	737.00 LFT
0052	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	319.00 LFT
0053	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	106.00 LFT
0054	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	111.00 LFT
0055	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	405.00 LFT
0056	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	1657.00 LFT

Call: 830

Contract: T -43258-B

Section No.: 1 TRAFFIC SIGNALS MODERNIZATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	62.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0010	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0013	202-74055	OVERHEAD SIGN STRUCTURE, BOX TRUSS, REMOVE	1.00	EACH
0014	202-86946	HANDHOLE, REMOVE	11.00	EACH
0015	202-90277	DETECTOR HOUSING, REMOVE	23.00	EACH
0016	202-93741	GUARDRAIL END TREATMENT, REMOVE	1.00	EACH
0017	202-94954	BARRIER WALL, CONCRETE, REMOVE	90.00	LFT
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	611.00	SYS
0019	303-07449	COMPACTED AGGREGATE, NO. 73	67.00	TON
0020	304-07789	WIDENING WITH HMA, TYPE D	421.00	TON
0021	304-12627	HMA PATCHING, FULL DEPTH, TYPE D	22.00	TON
0022	306-08034	MILLING, ASPHALT, 1 1/2 IN.	10358.00	SYS
0023	306-08432	MILLING, APPROACH	610.00	SYS
0024	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	855.00	TON
0025	401-10258	JOINT ADHESIVE, SURFACE	7707.00	LFT
0026	401-11785	LIQUID ASPHALT SEALANT	7707.00	LFT
0027	406-05520	ASPHALT FOR TACK COAT	5.00	TON
0028	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0029	506-06333	PCCP PATCHING, FULL DEPTH	28.00	SYS
0030	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	66.00	LFT
0031	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	1.00	EACH

0032	601-94689	GUARDRAIL END TREATMENT, TYPE OS	1.00 EACH
0033	602-91266	CONCRETE MEDIAN BARRIER, MODIFIED	95.00 LFT
0034	610-07788	HMA FOR APPROACHES, TYPE D	51.00 TON
0035	628-09403	FIELD OFFICE, TYPE C	16.00 MOS
0036	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0037	628-11977	COMPUTER SYSTEM	1.00 EACH
0038	801-03290	CONSTRUCTION SIGN, TYPE C	4.00 EACH
0039	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00 EACH
0040	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	2848.00 LFT
0041	801-06625	DETOUR ROUTE MARKER ASSEMBLY	43.00 EACH
0042	801-06640	CONSTRUCTION SIGN, TYPE A	393.00 EACH
0043	801-06710	FLASHING ARROW SIGN	210.00 DAY
0044	801-06775	MAINTAINING TRAFFIC	1.00 LS
0045	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	5.00 EACH
0046	801-07118	BARRICADE, TYPE III-A	64.00 LFT
0047	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2050.00 LFT
0048	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	16.00 EACH
0049	801-12042	TRUCK MOUNTED ATTENUATOR	10.00 DAY
0050	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	56.00 LFT
0051	802-05705	SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	102.00 LFT
0052	802-07057	SIGN, PANEL, WITH LEGEND	364.00 SFT
0053	802-09221	OVERHEAD SIGN STRUCTURE, BOX TRUSS, TYPE A	1.00 EACH
0054	802-09536	BOX TRUSS SIGN STRUCTURE FOUNDATION, 45 IN. CONCRETE BARRIER WALL	1.00 EACH
0055	802-09537	BOX TRUSS SIGN STRUCTURE FOUNDATION, 36 IN. MEDIAN OR SHOULDER	1.00 EACH
0056	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	654.00 SFT
0057	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	260.00 SFT
0058	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	367.00 SFT
0059	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	22.00 EACH
0060	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	1.00 EACH
0061	805-01824	SPAN, CATENARY, AND TETHER, TIGHTEN	16.00 EACH
0062	805-01842	HANDHOLE, SIGNAL, TYPE 1	19.00 EACH
0063	805-02056	SPAN AND CATENARY FOR FLASHER	4.00 EACH
0064	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00 LS
0065	805-02445	CONTROLLER AND CABINET, TYPE P1	7.00 EACH
0066	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	2.00 EACH
0067	805-03372	TETHER FOR SIGNAL	16.00 EACH
0068	805-06483	CONTROLLER	3.00 EACH

0069	805-06742	SOLAR POWERED FLASHING BEACON ASSEMBLY	2.00 EACH
0070	805-07190	TRAFFIC SIGNAL HEAD, NO. 1 SECTION, 12 IN.	32.00 EACH
0071	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	45.00 EACH
0072	805-10234	CONTROLLER AND CABINET, TYPE R	1.00 EACH
0073	805-11771	SIGNAL POLE, PEDESTAL, 16 FT	2.00 EACH
0074	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	3828.00 LFT
0075	805-78010	CONTROLLER AND CABINET, FLASHER SOLID STATE	4.00 EACH
0076	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	115.00 EACH
0077	805-78225	TRAFFIC SIGNAL HEAD, NO. 4 SECTION, 12 IN.	15.00 EACH
0078	805-78230	TRAFFIC SIGNAL HEAD, NO. 5 SECTION, 12 IN.	6.00 EACH
0079	805-78415	SPAN, CATENARY, AND TETHER	45.00 EACH
0080	805-78420	DISCONNECT HANGER	61.00 EACH
0081	805-78445	SIGNAL SERVICE	16.00 EACH
0082	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	644.00 LFT
0083	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	15864.00 LFT
0084	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GAUGE	1749.00 LFT
0085	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	6461.00 LFT
0086	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	9716.00 LFT
0087	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	2679.00 LFT
0088	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	22995.00 LFT
0089	805-78785	SIGNAL DETECTOR HOUSING	37.00 EACH
0090	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	5532.00 LFT
0091	805-78925	CONTROLLER CABINET FOUNDATION, TYPE P1	2.00 EACH
0092	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	1.00 EACH
0093	805-92504	LOOP DETECTOR DELAY AMPLIFIER, NONCOUNTING 2 CHANNEL	24.00 EACH
0094	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	3250.00 LFT
0095	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	128.00 LFT
0096	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	2488.00 LFT
0097	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	660.00 LFT
0098	808-10077	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, LANE INDICATION ARROW	9.00 EACH
0099	808-10119	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW, 24 IN.	132.00 LFT
0100	808-12032	GROOVING FOR PAVEMENT MARKINGS	6398.00 LFT
0101	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	89.00 EACH
0102	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	89.00 EACH

Call: 840

Contract: T -43704-A

Section No.: 1 ITS COMMUNICATIONS SYSTEMS

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	10.00	EACH
	0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	25.00	EACH
	0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0005	109-08360	CONTRACT LIENS	1.00	DOL
	0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
	0012	202-86946	HANDHOLE, REMOVE	32.00	EACH
	0013	202-95579	SERVICE POINT, REMOVE	2.00	EACH
	0014	203-02000	EXCAVATION, COMMON	54.00	CYS
	0015	205-12108	STORMWATER MANAGEMENT BUDGET	5000.00	DOL
	0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0017	207-08264	SUBGRADE TREATMENT, TYPE II	340.00	SYS
	0018	211-02050	B BORROW	30.00	CYS
	0019	302-07455	DENSE GRADED SUBBASE	57.00	CYS
	0020	303-01180	COMPACTED AGGREGATE, NO. 53	72.00	TON
	0021	506-06333	PCCP PATCHING, FULL DEPTH	340.00	SYS
	0022	616-05688	RIPRAP, CLASS 1	23.00	TON
	0023	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	10.00	EACH
	0024	621-06560	MULCHED SEEDING, TYPE U	650.00	SYS
	0025	621-06574	SODDING	125.00	SYS
	0026	628-09401	FIELD OFFICE, TYPE A	18.00	MOS
	0027	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
	0028	715-04985	VAULT	5.00	EACH
	0029	801-06640	CONSTRUCTION SIGN, TYPE A	64.00	EACH
	0030	801-06645	CONSTRUCTION SIGN, TYPE B	6.00	EACH
	0031	801-06710	FLASHING ARROW SIGN	10.00	DAY

0032	801-06775	MAINTAINING TRAFFIC	1.00	LS
0033	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	6.00	EACH
0034	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2055.00	LFT
0035	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	2850.00	LFT
0036	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	5.00	EACH
0037	801-12324	LAW ENFORCEMENT OFFICER	40.00	HRS
0038	801-12930	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, INTERMITTENT	11.00	EACH
0039	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0040	805-04973	CONDUIT	2335.00	LFT
0041	805-04973	CONDUIT	1343.00	LFT
0042	805-04973	CONDUIT	30.00	LFT
0043	805-04973	CONDUIT	1195.00	LFT
0044	805-04973	CONDUIT	15.00	LFT
0045	805-04973	CONDUIT	164.00	LFT
0046	805-04973	CONDUIT	18.00	LFT
0047	805-04973	CONDUIT	1462.00	LFT
0048	805-04973	CONDUIT	270.00	LFT
0049	805-04973	CONDUIT	1874.00	LFT
0050	805-04973	CONDUIT	2766.00	LFT
0051	805-04973	CONDUIT	138.00	LFT
0052	805-04973	CONDUIT	928.00	LFT
0053	805-04973	CONDUIT	190.00	LFT
0054	805-04973	CONDUIT	6.00	LFT
0055	805-04973	CONDUIT	47947.00	LFT
0056	805-04973	CONDUIT	105.00	LFT
0057	805-78930	CONTROLLER CABINET FOUNDATION, TYPE M	4.00	EACH
0058	807-04651	WIRE	1695.00	LFT
0059	807-04651	WIRE	1695.00	LFT
0060	807-12733	HANDHOLE, ATMS	26.00	EACH
0061	807-78590	HANDHOLE	15.00	EACH
0062	807-86955	CABLE-DUCT MARKER	87.00	EACH
0063	809-04652	SERVICE POINT	3.00	EACH
0064	809-04652	SERVICE POINT	1.00	EACH
0065	809-04970	FIBER OPTIC	1.00	EACH
0066	809-04970	FIBER OPTIC	4.00	EACH
0067	809-04970	FIBER OPTIC	3.00	EACH
0068	809-04970	FIBER OPTIC	3.00	EACH

0069	809-04970	FIBER OPTIC	4002.00 EACH
0070	809-04970	FIBER OPTIC	18.00 EACH
0071	809-04970	FIBER OPTIC	47.00 EACH
0072	809-04970	FIBER OPTIC	22.00 EACH
0073	809-04970	FIBER OPTIC	112.00 EACH
0074	809-04970	FIBER OPTIC	5.00 EACH
0075	809-04970	FIBER OPTIC	6.00 EACH
0076	809-04970	FIBER OPTIC	2.00 EACH
0077	809-04970	FIBER OPTIC	22.00 EACH
0078	809-04970	FIBER OPTIC	24.00 EACH
0079	809-04982	CABLE	1215.00 LFT
0080	809-04982	CABLE	3059.00 LFT
0081	809-06101	FOUNDATION	1.00 EACH
0082	809-08398	ITS CONTROLLER CABINET	4.00 EACH
0083	809-09343	ITS	7.00 EACH
0084	809-09343	ITS	1.00 EACH
0085	809-09343	ITS	6.00 EACH
0086	809-09343	ITS	1.00 EACH
0087	809-09343	ITS	19.00 EACH
0088	809-09343	ITS	2.00 EACH
0089	809-09343	ITS	3.00 EACH
0090	809-09343	ITS	1.00 EACH
0091	809-09343	ITS	1.00 EACH
0092	809-09343	ITS	8.00 EACH
0093	809-09343	ITS	1.00 EACH
0094	809-09343	ITS	2.00 EACH
0095	809-11707	ITS FIELD SWITCH	11.00 EACH
0096	809-94971	FIBER OPTIC CABLE	34657.00 LFT
0097	809-94971	FIBER OPTIC CABLE	25348.00 LFT
0098	809-94971	FIBER OPTIC CABLE	28538.00 LFT
0099	809-94971	FIBER OPTIC CABLE	22708.00 LFT
0100	809-94971	FIBER OPTIC CABLE	56869.00 LFT
0101	809-94971	FIBER OPTIC CABLE	53094.00 LFT

Call: 850

Contract: T -44014-A

Section No.: 1 ACCESS MANAGEMENT, RAISED MEDIANS

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-02279	CURB AND GUTTER, REMOVE	163.00	LFT
0012	202-91385	INLET, REMOVE	1.00	EACH
0013	203-02000	EXCAVATION, COMMON	176.00	CYS
0014	205-12108	STORMWATER MANAGEMENT BUDGET	1534.00	DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	207-08264	SUBGRADE TREATMENT, TYPE II	538.00	SYS
0017	211-09264	STRUCTURE BACKFILL, TYPE 1	73.00	CYS
0018	214-11796	GEOGRID, TYPE IB	538.00	SYS
0019	303-01180	COMPACTED AGGREGATE, NO. 53	36.00	TON
0020	304-07494	WIDENING WITH HMA, TYPE C	107.00	TON
0021	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	196.00	TON
0022	306-08034	MILLING, ASPHALT, 1 1/2 IN.	968.00	SYS
0023	306-11872	MILLING, PROFILE	408.00	SYS
0024	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	162.00	TON
0025	401-07379	QC/QA-HMA, 3, 70, INTERMEDIATE, 12.5 mm	39.00	TON
0026	406-05521	ASPHALT FOR TACK COAT	3085.00	SYS
0027	604-06070	SIDEWALK, CONCRETE	5.00	SYS
0028	604-08086	CURB RAMP, CONCRETE	5.00	SYS
0029	604-12083	DETECTABLE WARNING SURFACES	3.00	SYS
0030	605-06140	CURB AND GUTTER, CONCRETE	155.00	LFT
0031	605-06250	CENTER CURB, C CONCRETE	162.00	SYS

0032	621-06575	SODDING, NURSERY	52.00	SYS
0033	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0034	628-12683	FIELD OFFICE, TYPE D	6.00	MOS
0035	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	147.00	LFT
0036	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	206.00	LFT
0037	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	121.00	SYS
0038	718-52610	AGGREGATE FOR UNDERDRAINS	14.00	CYS
0039	720-07301	INLET, TYPE HA	2.00	EACH
0040	720-07302	INLET, TYPE HA, WITH SLOTTED DRAIN	1.00	EACH
0041	720-45410	MANHOLE, TYPE C4	1.00	EACH
0042	720-98555	INLET, TYPE C15	1.00	EACH
0043	801-03290	CONSTRUCTION SIGN, TYPE C	2.00	EACH
0044	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	2666.00	LFT
0045	801-06640	CONSTRUCTION SIGN, TYPE A	26.00	EACH
0046	801-06710	FLASHING ARROW SIGN	7.00	DAY
0047	801-06775	MAINTAINING TRAFFIC	1.00	LS
0048	801-07119	BARRICADE, TYPE III-B	32.00	LFT
0049	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	44.00	LFT
0050	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	56.00	SFT
0051	805-01828	TRAFFIC SIGNAL HEAD, REALIGN	2.00	EACH
0052	808-06368	TRANSVERSE MARKING, REMOVE	135.00	LFT
0053	808-06716	LINE, REMOVE	1082.00	LFT
0054	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	305.00	LFT
0055	808-10047	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 12 IN.	139.00	LFT
0056	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	976.00	LFT
0057	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	1468.00	LFT
0058	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	160.00	LFT
0059	808-10077	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, LANE INDICATION ARROW	6.00	EACH
0060	808-12032	GROOVING FOR PAVEMENT MARKINGS	1839.00	LFT

Call: 860

Contract: T -44082-A

Section No.: 1 HIGH FRICTION SURFACE TREATMENT

Line			Quantity	Unit
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	617-12128	HIGH FRICTION SURFACE TREATMENT	8254.00	SYS
0008	801-06640	CONSTRUCTION SIGN, TYPE A	105.00	EACH
0009	801-06645	CONSTRUCTION SIGN, TYPE B	15.00	EACH
0010	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 870

Contract: T -44745-A

Section No.: 1

NEW SIGNAL INSTALLATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	1.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	202-74035	SIGN, REMOVE	4.00	EACH
0009	801-06640	CONSTRUCTION SIGN, TYPE A	12.00	EACH
0010	801-06645	CONSTRUCTION SIGN, TYPE B	4.00	EACH
0011	801-06775	MAINTAINING TRAFFIC	1.00	LS
0012	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	39.00	LFT
0013	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	24.00	SFT
0014	805-01842	HANDHOLE, SIGNAL, TYPE 1	11.00	EACH
0015	805-02445	CONTROLLER AND CABINET, TYPE P1	1.00	EACH
0016	805-08244	CELLULAR MODEM KIT	1.00	EACH
0017	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	4.00	EACH
0018	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	1750.00	LFT
0019	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	8.00	EACH
0020	805-78415	SPAN, CATENARY, AND TETHER	4.00	EACH
0021	805-78420	DISCONNECT HANGER	4.00	EACH
0022	805-78445	SIGNAL SERVICE	1.00	EACH
0023	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	100.00	LFT
0024	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	750.00	LFT
0025	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	350.00	LFT
0026	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	650.00	LFT
0027	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	2750.00	LFT
0028	805-78785	SIGNAL DETECTOR HOUSING	8.00	EACH
0029	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	650.00	LFT
0030	805-78925	CONTROLLER CABINET FOUNDATION, TYPE P1	1.00	EACH
0031	805-92504	LOOP DETECTOR DELAY AMPLIFIER, NONCOUNTING 2 CHANNEL	2.00	EACH

0032	808-06716	LINE, REMOVE	50.00	LFT
0033	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	120.00	LFT