

**Schedule of Pay Items Letting Date February 15, 2024 Letting ID 240215**

Call: 220

Contract: R -42249-A

Section No.: 1 INTERSECTION IMPROVEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-02271	HEADWALL, REMOVE	1.00	EACH
0012	202-02272	PAVED SIDE DITCH, REMOVE	192.00	LFT
0013	202-96133	PIPE, REMOVE	361.00	LFT
0014	203-02000	EXCAVATION, COMMON	4620.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	19654.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	205-12618	SWQCP PREPARATION	1.00	LS
0018	207-08264	SUBGRADE TREATMENT, TYPE II	107.00	SYS
0019	207-12635	SUBGRADE TREATMENT, TYPE IBC	9492.00	SYS
0020	211-02050	B BORROW	1424.00	CYS
0021	211-09265	STRUCTURE BACKFILL, TYPE 2	513.00	CYS
0022	211-09268	STRUCTURE BACKFILL, TYPE 5	23.00	CYS
0023	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	20.00	CYS
0024	214-12238	GEOTEXTILE FOR PAVEMENT, TYPE 2A	1899.00	SYS
0025	301-12232	COMPACTED AGGREGATE, NO. 5	165.00	CYS
0026	301-12234	COMPACTED AGGREGATE, NO. 53	165.00	CYS
0027	303-01180	COMPACTED AGGREGATE, NO. 53	36.00	TON
0028	303-07449	COMPACTED AGGREGATE, NO. 73	397.00	TON
0029	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	186.00	TON
0030	306-08034	MILLING, ASPHALT, 1 1/2 IN.	316.00	SYS
0031	306-08432	MILLING, APPROACH	107.00	SYS

0032	306-10113	MILLING, ASPHALT, 4 1/2 IN.	2950.00	SYS
0033	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1053.00	TON
0034	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	2053.00	TON
0035	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	3133.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	7806.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	7706.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	11764.00	LFT
0039	406-05520	ASPHALT FOR TACK COAT	9.00	TON
0040	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	3.00	TON
0041	601-02241	GUARDRAIL, REMOVE	584.00	LFT
0042	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	738.00	LFT
0043	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	2.00	EACH
0044	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00	EACH
0045	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	4058.00	LFT
0046	610-07487	HMA FOR APPROACHES, TYPE B	24.00	TON
0047	611-08232	MAILBOX ASSEMBLY, RESET, SINGLE	2.00	EACH
0048	615-06490	RIGHT-OF-WAY MARKER	20.00	EACH
0049	615-06505	MONUMENT, TYPE B	2.00	EACH
0050	616-06406	RIPRAP, REVETMENT	917.00	SYS
0051	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	1171.00	SYS
0052	616-12247	GEOTEXTILE FOR RIPRAP, TYPE 1B	68.00	SYS
0053	616-12251	GEOTEXTILE FOR RIPRAP, TYPE 3	41.00	SYS
0054	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0055	621-06560	MULCHED SEEDING, TYPE U	7769.00	SYS
0056	621-06574	SODDING	800.00	SYS
0057	628-09403	FIELD OFFICE, TYPE C	12.00	MOS
0058	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0059	714-11193	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 4 FT X 2 FT	77.00	LFT
0060	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	554.00	LFT
0061	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	617.00	LFT
0062	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	56.00	LFT
0063	715-05171	PIPE, TYPE 3, CIRCULAR, DIAMETER 18 IN.	53.00	LFT
0064	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	11.00	TON
0065	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0066	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0067	715-46010	PIPE END SECTION, DIAMETER 18 IN.	4.00	EACH
0068	720-45030	INLET, TYPE E7	3.00	EACH

0069	720-45045	INLET, TYPE J10	3.00 EACH
0070	720-45205	CATCH BASIN, TYPE A2	2.00 EACH
0071	720-45410	MANHOLE, TYPE C4	6.00 EACH
0072	801-04308	ROAD CLOSURE SIGN ASSEMBLY	10.00 EACH
0073	801-06625	DETOUR ROUTE MARKER ASSEMBLY	63.00 EACH
0074	801-06640	CONSTRUCTION SIGN, TYPE A	24.00 EACH
0075	801-06775	MAINTAINING TRAFFIC	1.00 LS
0076	801-07119	BARRICADE, TYPE III-B	160.00 LFT
0077	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	52.00 LFT
0078	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	4.00 SFT
0079	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	18.00 SFT
0080	802-91122	SIGN, GROUND MOUNTED, RESET	10.00 EACH
0081	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	4990.00 LFT
0082	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	5334.00 LFT
0083	808-12032	GROOVING FOR PAVEMENT MARKINGS	10324.00 LFT
0084	808-75078	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, YELLOW, 12 IN.	308.00 LFT
0085	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	50.00 LFT
0086	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	4.00 EACH
0087	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	23.00 EACH
0088	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	156.00 EACH

Call: 290

Contract: R -42358-A

Section No.: 1 INTERSECTION IMPROVEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	2385.00	SYS
0014	202-02278	CURB, CONCRETE, REMOVE	2499.00	LFT
0015	202-52710	SIDEWALK CONCRETE, REMOVE	171.00	SYS
0016	203-02000	EXCAVATION, COMMON	11442.00	CYS
0017	203-02070	BORROW	2081.00	CYS
0018	205-12108	STORMWATER MANAGEMENT BUDGET	61030.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	205-12618	SWQCP PREPARATION	1.00	LS
0021	207-08264	SUBGRADE TREATMENT, TYPE II	1113.00	SYS
0022	207-08266	SUBGRADE TREATMENT, TYPE III	1704.00	SYS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	15345.00	SYS
0024	211-09264	STRUCTURE BACKFILL, TYPE 1	1446.00	CYS
0025	211-09265	STRUCTURE BACKFILL, TYPE 2	59.00	CYS
0026	211-09268	STRUCTURE BACKFILL, TYPE 5	148.00	CYS
0027	214-11796	GEOGRID, TYPE IB	1113.00	SYS
0028	214-12238	GEOTEXTILE FOR PAVEMENT, TYPE 2A	9126.00	SYS
0029	301-12232	COMPACTED AGGREGATE, NO. 5	218.00	CYS
0030	301-12233	COMPACTED AGGREGATE, NO. 8	29.00	CYS
0031	301-12234	COMPACTED AGGREGATE, NO. 53	1581.00	CYS

0032	302-06464	SUBBASE FOR PCCP	559.00	CYS
0033	302-07455	DENSE GRADED SUBBASE	145.00	CYS
0034	303-01180	COMPACTED AGGREGATE, NO. 53	512.00	TON
0035	303-07449	COMPACTED AGGREGATE, NO. 73	82.00	TON
0036	304-07494	WIDENING WITH HMA, TYPE C	427.00	TON
0037	306-08034	MILLING, ASPHALT, 1 1/2 IN.	18575.00	SYS
0038	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2302.00	TON
0039	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1206.00	TON
0040	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	4036.00	TON
0041	401-10258	JOINT ADHESIVE, SURFACE	16647.00	LFT
0042	401-10259	JOINT ADHESIVE, INTERMEDIATE	3953.00	LFT
0043	401-11785	LIQUID ASPHALT SEALANT	16647.00	LFT
0044	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	1394.00	TON
0045	406-05520	ASPHALT FOR TACK COAT	9.00	TON
0046	501-06323	QC/QA-PCCP, 12 IN.	1971.00	SYS
0047	502-06329	PCCP, 12 IN.	9.00	SYS
0048	502-06627	PCCP, 6 IN.	562.00	SYS
0049	502-11543	PCCP, 4 IN.	677.00	SYS
0050	503-03489	RETROFITTED TIE BARS	1336.00	EACH
0051	503-05240	D-1 CONTRACTION JOINT	1144.00	LFT
0052	601-01740	GUARDRAIL TERMINAL SYSTEM, W-BEAM CURVED, TYPE 4	3.00	EACH
0053	601-02241	GUARDRAIL, REMOVE	512.00	LFT
0054	601-06855	GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	2.00	EACH
0055	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	188.00	LFT
0056	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	2.00	EACH
0057	601-94689	GUARDRAIL END TREATMENT, TYPE OS	1.00	EACH
0058	604-06070	SIDEWALK, CONCRETE	1208.00	SYS
0059	604-08086	CURB RAMP, CONCRETE	227.00	SYS
0060	604-12083	DETECTABLE WARNING SURFACES	20.00	SYS
0061	605-06090	CURB, INTEGRAL CONCRETE	2258.00	LFT
0062	605-06120	CURB, CONCRETE	1771.00	LFT
0063	605-06140	CURB AND GUTTER, CONCRETE	3480.00	LFT
0064	605-06255	CENTER CURB, D CONCRETE	187.00	SYS
0065	605-90726	CURB, CONCRETE, DEPRESSED	20.00	LFT
0066	605-96305	CURB AND GUTTER, CONCRETE DEPRESSED	62.00	LFT
0067	610-07487	HMA FOR APPROACHES, TYPE B	139.00	TON
0068	610-09108	PCCP FOR APPROACHES, 9 IN.	871.00	SYS

0069	615-06490	RIGHT-OF-WAY MARKER	32.00 EACH
0070	615-06505	MONUMENT, TYPE B	4.00 EACH
0071	616-05688	RIPRAP, CLASS 1	14.00 TON
0072	616-06405	RIPRAP, REVETMENT	92.00 TON
0073	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	328.00 SYS
0074	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0075	621-02770	EROSION CONTROL BLANKET	4730.00 SYS
0076	621-06545	FERTILIZER	2.00 TON
0077	621-06554	SEED MIXTURE, TYPE U	559.00 LBS
0078	621-06565	MULCHING MATERIAL	6.00 TON
0079	621-06567	WATER	8.00 kGAL
0080	621-06575	SODDING, NURSERY	1804.00 SYS
0081	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0082	628-12683	FIELD OFFICE, TYPE D	24.00 MOS
0083	714-11059	STRUCTURE EXTENSION, REINFORCED CONCRETE, BOX SECTIONS, 3 FT X 3 FT	36.00 LFT
0084	714-12517	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 3 FT X 3 FT	145.00 LFT
0085	715-05024	PIPE, TYPE 2, CIRCULAR, DIAMETER 36 IN.	268.00 LFT
0086	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	6566.00 LFT
0087	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	13.00 LFT
0088	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	1827.00 LFT
0089	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	396.00 LFT
0090	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	284.00 LFT
0091	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	139.00 LFT
0092	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	56.00 LFT
0093	715-09064	VIDEO INSPECTION FOR PIPE	2914.00 LFT
0094	715-09475	STORMWATER QUALITY STRUCTURE	1.00 EACH
0095	715-09996	PIPE, TYPE 3, DEFORMED, MIN. AREA 16.6 SFT	81.00 LFT
0096	715-11472	PIPE END SECTION, MIN. AREA 16.6 SFT	2.00 EACH
0097	715-46000	PIPE END SECTION, DIAMETER 12 IN.	4.00 EACH
0098	715-46005	PIPE END SECTION, DIAMETER 15 IN.	4.00 EACH
0099	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00 EACH
0100	715-46040	PIPE END SECTION, DIAMETER 36 IN.	1.00 EACH
0101	718-06531	OUTLET PROTECTOR, TYPE 3	1.00 EACH
0102	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	3000.00 LFT
0103	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	6981.00 SYS
0104	718-52610	AGGREGATE FOR UNDERDRAINS	898.00 CYS
0105	720-12797	CASTING, INLET, ADJUST TO GRADE	3.00 EACH

0106	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	1.00 EACH
0107	720-45042	INLET, TYPE HA5	1.00 EACH
0108	720-45410	MANHOLE, TYPE C4	7.00 EACH
0109	720-92884	MANHOLE, TYPE K4, MODIFIED	1.00 EACH
0110	720-95409	MANHOLE, TYPE J4, MODIFIED	1.00 EACH
0111	720-95422	MANHOLE, TYPE J4	1.00 EACH
0112	720-98174	INLET, TYPE B15	15.00 EACH
0113	720-98555	INLET, TYPE C15	28.00 EACH
0114	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	29820.00 LFT
0115	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	30.00 EACH
0116	801-06640	CONSTRUCTION SIGN, TYPE A	29.00 EACH
0117	801-06645	CONSTRUCTION SIGN, TYPE B	16.00 EACH
0118	801-06710	FLASHING ARROW SIGN	120.00 DAY
0119	801-06775	MAINTAINING TRAFFIC	1.00 LS
0120	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	6.00 EACH
0121	801-07118	BARRICADE, TYPE III-A	72.00 LFT
0122	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	5406.00 LFT
0123	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	398.00 LFT
0124	802-05705	SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	49.00 LFT
0125	802-07057	SIGN, PANEL, WITH LEGEND	1111.00 SFT
0126	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	4.00 EACH
0127	802-07060	SIGN, SHEET, RELOCATE	2.00 EACH
0128	802-09577	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE E	4.00 EACH
0129	802-09578	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE F	1.00 EACH
0130	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	318.00 SFT
0131	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	45.00 SFT
0132	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	49.00 SFT
0133	802-11886	CANTILEVER SIGN SUPPORT FOUNDATION, DRILLED SHAFT 48 IN.	4.00 EACH
0134	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, TYPE A	4.00 EACH
0135	802-12223	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, TYPE B	2.00 EACH
0136	802-76095	STRUCTURAL STEEL, BREAKAWAY	1103.00 LBS
0137	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00 EACH
0138	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	8.00 EACH
0139	805-01842	HANDHOLE, SIGNAL, TYPE 1	16.00 EACH
0140	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	6.00 EACH
0141	805-02445	CONTROLLER AND CABINET, TYPE P1	2.00 EACH
0142	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	6.00 EACH



0143	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	2307.00	LFT
0144	805-08244	CELLULAR MODEM KIT	3.00	EACH
0145	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	18.00	EACH
0146	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	1887.00	LFT
0147	805-11817	PEDESTRIAN PUSH BUTTON, APS	6.00	EACH
0148	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	17.00	EACH
0149	805-78225	TRAFFIC SIGNAL HEAD, NO. 4 SECTION, 12 IN.	2.00	EACH
0150	805-78230	TRAFFIC SIGNAL HEAD, NO. 5 SECTION, 12 IN.	2.00	EACH
0151	805-78415	SPAN, CATENARY, AND TETHER	8.00	EACH
0152	805-78420	DISCONNECT HANGER	7.00	EACH
0153	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	49.00	LFT
0154	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	11454.00	LFT
0155	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GAUGE	1348.00	LFT
0156	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	2315.00	LFT
0157	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	198.00	LFT
0158	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	739.00	LFT
0159	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	12214.00	LFT
0160	805-78785	SIGNAL DETECTOR HOUSING	30.00	EACH
0161	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	3267.00	LFT
0162	805-78925	CONTROLLER CABINET FOUNDATION, TYPE P1	2.00	EACH
0163	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	8.00	EACH
0164	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	6.00	EACH
0165	807-02191	HANDHOLE, LIGHTING	5.00	EACH
0166	807-02370	LIGHT STRUCTURE, REMOVE AND RESET	5.00	EACH
0167	807-03758	LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING, 24 IN. X 24 IN. X 96 IN.	13.00	EACH
0168	807-03950	LUMINAIRE, ORNAMENTAL	3.00	EACH
0169	807-03950	LUMINAIRE, ORNAMENTAL	6.00	EACH
0170	807-03951	LIGHT POLE, ORNAMENTAL	6.00	EACH
0171	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	588.00	LFT
0172	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	3430.00	LFT
0173	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	2.00	EACH
0174	807-84748	LIGHT POLE, 40 FT E.M.H., 8 FT MAST ARM, BREAKAWAY BASE	2.00	EACH
0175	807-86805	SERVICE POINT, TYPE I	1.00	EACH
0176	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	4300.00	LFT
0177	807-86910	CONNECTOR KIT, UNFUSED	22.00	EACH
0178	807-86915	CONNECTOR KIT, FUSED	22.00	EACH
0179	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	37.00	EACH

0180	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	12.00	EACH
0181	807-86930	INSULATION LINK, NON-WATERPROOFED	25.00	EACH
0182	807-86935	INSULATION LINK, WATERPROOFED	20.00	EACH
0183	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	69.00	SYS
0184	808-06716	LINE, REMOVE	7429.00	LFT
0185	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0186	808-10042	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW, 12 IN.	190.00	LFT
0187	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	8313.00	LFT
0188	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	394.00	LFT
0189	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	11.00	EACH
0190	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	8546.00	LFT
0191	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	1474.00	LFT
0192	808-10077	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, LANE INDICATION ARROW	26.00	EACH
0193	808-10099	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 24 IN.	455.00	LFT
0194	808-12032	GROOVING FOR PAVEMENT MARKINGS	20044.00	LFT
0195	808-12353	LINE, MULTI-COMPONENT, DOTTED, WHITE, 6 IN.	134.00	LFT
0196	808-12781	LINE, MULTI-COMPONENT, SOLID, WHITE, 10 IN.	353.00	LFT
0197	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	525.00	LFT
0198	808-12851	LINE, MULTI-COMPONENT, DOTTED, WHITE, 10 IN.	28.00	LFT
0199	808-12859	LINE, MULTI-COMPONENT, SOLID, YELLOW, 10 IN.	673.00	LFT

Call: 320

Contract: R -42494-B

Section No.: 1            CONCRETE PAVEMENT RESTORATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0010	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0013	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0014	201-90788	DEBRIS, REMOVE, STRUCTURE NO.	1.00	LS
0015	202-02240	PAVEMENT REMOVAL	1888.00	SYS
0016	202-02273	CENTER CURB, CONCRETE, REMOVE	145.00	SYS
0017	202-02274	CURB, CONCRETE INTEGRAL, REMOVE	465.00	LFT
0018	202-02279	CURB AND GUTTER, REMOVE	123.00	LFT
0019	202-04435	DELINEATOR POST, REMOVE	3.00	EACH
0020	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0021	202-52710	SIDEWALK CONCRETE, REMOVE	386.00	SYS
0022	202-90277	DETECTOR HOUSING, REMOVE	18.00	EACH
0023	203-02000	EXCAVATION, COMMON	490.00	CYS
0024	203-08607	LINEAR GRADING	253.00	LFT
0025	205-11626	PUMP AROUND	1.00	EACH
0026	205-12108	STORMWATER MANAGEMENT BUDGET	14000.00	DOL
0027	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0028	207-08264	SUBGRADE TREATMENT, TYPE II	3755.00	SYS
0029	207-09935	SUBGRADE TREATMENT, TYPE IC	2108.00	SYS
0030	214-11796	GEOGRID, TYPE IB	3755.00	SYS
0031	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	2108.00	SYS

0032	302-06464	SUBBASE FOR PCCP	1433.00	CYS
0033	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	15.00	TON
0034	306-08034	MILLING, ASPHALT, 1 1/2 IN.	578.00	SYS
0035	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	48.00	TON
0036	502-06329	PCCP, 12 IN.	983.00	SYS
0037	503-03489	RETROFITTED TIE BARS	252.00	EACH
0038	503-05240	D-1 CONTRACTION JOINT	1470.00	LFT
0039	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT, 12 IN.	597.00	SYS
0040	503-12478	TERMINAL JOINT, TYPE PCCP	138.00	LFT
0041	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	134.00	LFT
0042	506-06333	PCCP PATCHING, FULL DEPTH	3755.00	SYS
0043	507-07480	PROFILING PCCP	2194.00	SYS
0044	507-08269	CRACKS IN PCCP, FILLED	3296.00	LFT
0045	507-08271	JOINTS IN PCCP, FILLED	30324.00	LFT
0046	507-08272	JOINTS IN PCCP, SAW AND SEAL	72395.00	LFT
0047	509-12191	JOINT REPAIR, PARTIAL DEPTH	2790.00	SFT
0048	509-12192	JOINT REPAIR, BOTTOM-HALF	38.00	SFT
0049	601-06035	GUARDRAIL, RESET	100.00	LFT
0050	604-06070	SIDEWALK, CONCRETE	298.00	SYS
0051	604-08086	CURB RAMP, CONCRETE	64.00	SYS
0052	604-12083	DETECTABLE WARNING SURFACES	10.00	SYS
0053	605-06100	CURB, INTEGRAL C CONCRETE	465.00	LFT
0054	605-06140	CURB AND GUTTER, CONCRETE	123.00	LFT
0055	605-06250	CENTER CURB, C CONCRETE	114.00	SYS
0056	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	329.00	SYS
0057	616-06405	RIPRAP, REVETMENT	183.00	TON
0058	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	293.00	SYS
0059	619-12460	DISPOSAL OF CLEANING WASTE, NON-HAZARDOUS, BRIDGE NO.	1.00	LS
0060	619-12507	CLEAN AND COAT STEEL PILING, BRIDGE NO.	1.00	LS
0061	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0062	621-06560	MULCHED SEEDING, TYPE U	503.00	SYS
0063	621-06567	WATER	1.00	KGAL
0064	621-06570	TOPSOIL	27.00	CYS
0065	621-06574	SODDING	97.00	SYS
0066	621-06575	SODDING, NURSERY	117.00	SYS
0067	628-09403	FIELD OFFICE, TYPE C	18.00	MOS
0068	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH

0069	703-06029	REINFORCING BARS, EPOXY COATED	17819.00	LBS
0070	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	175.00	EACH
0071	709-51821	SURFACE SEAL	1.00	LS
0072	711-51035	STRUCTURAL STEEL	700.00	LBS
0073	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	857.00	LFT
0074	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	16088.00	LFT
0075	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	459.00	SYS
0076	718-52610	AGGREGATE FOR UNDERDRAINS	40.00	CYS
0077	720-12797	CASTING, INLET, ADJUST TO GRADE	6.00	EACH
0078	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	3.00	EACH
0079	720-45605	STRUCTURE, MANHOLE, RECONSTRUCTED	20.00	LFT
0080	722-01066	HYDRODEMOLITION	902.00	SYS
0081	722-12380	BRIDGE DECK OVERLAY BUDGET	15000.00	DOL
0082	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	902.00	SYS
0083	722-12732	LONGITUDINAL GROOVING	1231.00	SYS
0084	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	245.00	SFT
0085	724-12773	BRIDGE EXPANSION JOINT, TYPE PCF	24.00	LFT
0086	801-03290	CONSTRUCTION SIGN, TYPE C	4.00	EACH
0087	801-04308	ROAD CLOSURE SIGN ASSEMBLY	1.00	EACH
0088	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1566.00	LFT
0089	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	1386.00	LFT
0090	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	488.00	LFT
0091	801-06625	DETOUR ROUTE MARKER ASSEMBLY	44.00	EACH
0092	801-06640	CONSTRUCTION SIGN, TYPE A	99.00	EACH
0093	801-06645	CONSTRUCTION SIGN, TYPE B	48.00	EACH
0094	801-06710	FLASHING ARROW SIGN	880.00	DAY
0095	801-06775	MAINTAINING TRAFFIC	1.00	LS
0096	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	4.00	EACH
0097	801-07118	BARRICADE, TYPE III-A	348.00	LFT
0098	801-07119	BARRICADE, TYPE III-B	60.00	LFT
0099	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1106.00	LFT
0100	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0101	801-11990	TEMPORARY CURB RAMP	7.00	EACH
0102	801-12042	TRUCK MOUNTED ATTENUATOR	402.00	DAY
0103	801-12324	LAW ENFORCEMENT OFFICER	1000.00	HRS
0104	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	38.00	SYS
0105	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	48.00	LFT

0106	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	8.00 EACH
0107	802-91122	SIGN, GROUND MOUNTED, RESET	7.00 EACH
0108	804-11920	DELINEATOR POST, FLEXIBLE, TYPE I	2.00 EACH
0109	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	8448.00 LFT
0110	805-78785	SIGNAL DETECTOR HOUSING	18.00 EACH
0111	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1285.00 LFT
0112	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0113	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	7592.00 LFT
0114	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	13426.00 LFT
0115	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	9399.00 LFT
0116	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	91.00 LFT
0117	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	1024.00 LFT
0118	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	6.00 EACH
0119	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	742.00 LFT
0120	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	186.00 LFT
0121	808-10074	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 8 IN.	356.00 LFT
0122	808-10077	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, LANE INDICATION ARROW	95.00 EACH
0123	808-12032	GROOVING FOR PAVEMENT MARKINGS	30832.00 LFT
0124	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1053.00 EACH
0125	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1049.00 EACH

Call: 320

Contract: R -42494-B

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED

**Line**

Item No	Item Code	Description	Quantity Unit
0126	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	902.00 SYS

Call: 320

Contract: R -42494-B

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

**Line**

Item No	Item Code	Description	Quantity Unit
0127	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	902.00 SYS

Call: 340

Contract: R -42979-A

Section No.: 1            SMALL STRUCTURES AND DRAINS CONSTRUCTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-02271	HEADWALL, REMOVE	6.00	EACH
0012	202-96133	PIPE, REMOVE	144.00	LFT
0013	203-02000	EXCAVATION, COMMON	170.00	CYS
0014	203-02070	BORROW	10.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	8303.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	95.00	CYS
0018	303-01180	COMPACTED AGGREGATE, NO. 53	9.00	TON
0019	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1113.00	SYS
0020	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	94.00	TON
0021	401-10258	JOINT ADHESIVE, SURFACE	979.00	LFT
0022	401-10259	JOINT ADHESIVE, INTERMEDIATE	79.00	LFT
0023	401-11785	LIQUID ASPHALT SEALANT	979.00	LFT
0024	406-05521	ASPHALT FOR TACK COAT	1408.00	SYS
0025	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	109.50	LFT
0026	611-08232	MAILBOX ASSEMBLY, RESET, SINGLE	1.00	EACH
0027	616-06405	RIPRAP, REVETMENT	15.00	TON
0028	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	40.00	SYS
0029	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0030	621-06559	MULCHED SEEDING, TYPE R	683.00	SYS
0031	621-06560	MULCHED SEEDING, TYPE U	554.00	SYS

0032	702-51005	CONCRETE, A, SUBSTRUCTURE	0.60	CYS
0033	703-06029	REINFORCING BARS, EPOXY COATED	60.00	LBS
0034	715-05121	PIPE, TYPE 1, CIRCULAR, DIAMETER 18 IN.	103.00	LFT
0035	715-05123	PIPE, TYPE 1, CIRCULAR, DIAMETER 24 IN.	53.00	LFT
0036	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	67.00	TON
0037	715-46010	PIPE END SECTION, DIAMETER 18 IN.	3.00	EACH
0038	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00	EACH
0039	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00	EACH
0040	801-06625	DETOUR ROUTE MARKER ASSEMBLY	25.00	EACH
0041	801-06640	CONSTRUCTION SIGN, TYPE A	42.00	EACH
0042	801-06775	MAINTAINING TRAFFIC	1.00	LS
0043	801-07118	BARRICADE, TYPE III-A	56.00	LFT
0044	801-07119	BARRICADE, TYPE III-B	60.00	LFT
0045	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	652.00	LFT
0046	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	30.00	LFT
0047	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	436.00	LFT