

Schedule of Pay Items Letting Date October 8, 2025 Letting ID 251008

Call: 230

Contract: R -46140-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-02260	TREE, 30 IN., REMOVE	1.00	ACH
0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0013	203-02000	EXCAVATION, COMMON	146.00	CYS
0014	205-11626	PUMP AROUND	3.00	ACH
0015	205-12108	STORMWATER MANAGEMENT BUDGET	3940.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	207-09935	SUBGRADE TREATMENT, TYPE IC	134.00	SYS
0018	211-09265	STRUCTURE BACKFILL, TYPE 2	27.00	CYS
0019	211-09268	STRUCTURE BACKFILL, TYPE 5	498.00	CYS
0020	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	134.00	SYS
0021	301-12233	COMPACTED AGGREGATE, NO. 8	15.00	CYS
0022	301-12234	COMPACTED AGGREGATE, NO. 53	15.00	CYS
0023	306-08034	MILLING, ASPHALT, 1 1/2 IN.	227.00	SYS
0024	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	29.00	TON
0025	401-11526	JOINT ADHESIVE	200.00	LFT
0026	406-05520	ASPHALT FOR TACK COAT	0.20	TON
0027	615-06490	RIGHT-OF-WAY MARKER	8.00	ACH
0028	615-06505	MONUMENT, TYPE B	2.00	ACH
0029	616-06405	RIPRAP, REVETMENT	83.00	TON
0030	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	350.00	SYS
0031	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	ACH

0032	621-02770	EROSION CONTROL BLANKET	134.00	SYS
0033	621-06559	MULCHED SEEDING, TYPE R	519.00	SYS
0034	702-51005	CONCRETE, A, SUBSTRUCTURE	4.00	CYS
0035	702-51863	FIELD DRILLED HOLE IN CONCRETE	127.00	EACH
0036	703-06029	REINFORCING BARS, EPOXY COATED	351.00	LBS
0037	709-51821	SURFACE SEAL	1.00	LS
0038	714-000086	WATERPROOFING MEMBRANE TYPE 2	1093.00	SFT
0039	715-05136	PIPE, TYPE 1, CIRCULAR, DIAMETER 72 IN.	58.00	LFT
0040	715-06357	CONCRETE ANCHOR, DIAMETER 72 IN.	2.00	EACH
0041	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	53.00	TON
0042	719-05443	PIPE, DRAIN TILE TERMINAL SECTION, DIAMETER 12 IN.	30.00	LFT
0043	719-09447	PIPE, DRAIN TILE TERMINAL SECTION, DIAMETER 24 IN.	10.00	LFT
0044	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0045	801-06625	DETOUR ROUTE MARKER ASSEMBLY	37.00	EACH
0046	801-06640	CONSTRUCTION SIGN, TYPE A	60.00	EACH
0047	801-06775	MAINTAINING TRAFFIC	1.00	LS
0048	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0049	801-07119	BARRICADE, TYPE III-B	48.00	LFT
0050	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	38.00	LFT
0051	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	300.00	LFT