

**Schedule of Pav Items Letting Date May 9, 2024 Letting ID 240509**

Call: 111

Contract: R -40512-B

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08441		QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0005	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463		PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377		QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	202-02240		PAVEMENT REMOVAL	2828.00	SYS
0011	202-51328		PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0012	207-09935		SUBGRADE TREATMENT, TYPE IC	4710.00	SYS
0013	214-11796		GEOGRID, TYPE IB	3482.00	SYS
0014	214-12239		GEOTEXTILE FOR PAVEMENT, TYPE 2B	2828.00	SYS
0015	302-06464		SUBBASE FOR PCCP	1179.00	CYS
0016	503-03489		RETROFITTED TIE BARS	90.00	EACH
0017	503-05240		D-1 CONTRACTION JOINT	1619.00	LFT
0018	503-09261		PCCP STITCHING	232.00	EACH
0019	503-12478		TERMINAL JOINT, TYPE PCCP	365.00	LFT
0020	503-12479		EXPANSION JOINT WITH LOAD TRANSFER	365.00	LFT
0021	503-12480		TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	1114.00	SFT
0022	503-12505		JOINTED REINFORCED CONCRETE PAVEMENT, 14 IN.	1600.00	SYS
0023	506-06333		PCCP PATCHING, FULL DEPTH	1882.00	SYS
0024	507-12941		RCBA CRACK FILLING, PCC SEALER/HEALER	11010.00	LFT
0025	509-12191		JOINT REPAIR, PARTIAL DEPTH	1249.00	SFT
0026	509-12192		JOINT REPAIR, BOTTOM-HALF	79.00	SFT
0027	609-08579		REINFORCED CONCRETE BRIDGE APPROACH, 16 IN.	1227.90	SYS
0028	628-09403		FIELD OFFICE, TYPE C	12.00	MOS
0029	702-51863		FIELD DRILLED HOLE IN CONCRETE	115.00	EACH
0030	703-06029		REINFORCING BARS, EPOXY COATED	68704.00	LBS
0031	703-97936		THREADED TIE BAR ASSEMBLY, EPOXY COATED	237.00	EACH

0032	706-51020	RAILING, CONCRETE TYPE C	2.10	CYS
0033	709-51821	SURFACE SEAL	1.00	LS
0034	709-51821	SURFACE SEAL	1.00	LS
0035	709-51821	SURFACE SEAL	1.00	LS
0036	710-09158	PATCHING CONCRETE STRUCTURES	47.00	SFT
0037	718-08308	UNDERDRAIN, PATCHING	399.00	LFT
0038	720-12797	CASTING, INLET, ADJUST TO GRADE	2.00	EACH
0039	722-12732	LONGITUDINAL GROOVING	1228.00	SYS
0040	724-12420	BRIDGE JOINT NOSING	1026.00	SFT
0041	727-90308	EPOXY INJECTION, CRACK PREPARATION	150.00	LFT
0042	727-90309	EPOXY INJECTION, EPOXY MATERIAL	50.00	GAL
0043	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0044	801-03290	CONSTRUCTION SIGN, TYPE C	9.00	EACH
0045	801-04308	ROAD CLOSURE SIGN ASSEMBLY	17.00	EACH
0046	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	10826.00	LFT
0047	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	150055.00	LFT
0048	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	141568.00	LFT
0049	801-06640	CONSTRUCTION SIGN, TYPE A	195.00	EACH
0050	801-06645	CONSTRUCTION SIGN, TYPE B	40.00	EACH
0051	801-06710	FLASHING ARROW SIGN	56.00	DAY
0052	801-06775	MAINTAINING TRAFFIC	1.00	LS
0053	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	33.00	EACH
0054	801-07118	BARRICADE, TYPE III-A	1020.00	LFT
0055	801-07119	BARRICADE, TYPE III-B	12.00	LFT
0056	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	13008.00	LFT
0057	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	22.00	EACH
0058	801-12042	TRUCK MOUNTED ATTENUATOR	205.00	DAY
0059	801-12324	LAW ENFORCEMENT OFFICER	1000.00	HRS
0060	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	8.00	EACH
0061	801-12930	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, INTERMITTENT	12.00	EACH
0062	801-12956	TEMPORARY PAVEMENT MARKING, REMOVABLE, 10 IN.	113768.00	LFT
0063	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	400.00	LFT
0064	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	150.00	LFT
0065	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	67.00	SYS
0066	808-06716	LINE, REMOVE	46148.00	LFT
0067	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	8.00	EACH
0068	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS

0069	808-10038	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 24 IN.	2836.00	LFT
0070	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	2905.00	LFT
0071	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	19.00	EACH
0072	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	1225.00	LFT
0073	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	420.00	LFT
0074	808-10077	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, LANE INDICATION ARROW	70.00	EACH
0075	808-10119	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW, 24 IN.	611.00	LFT
0076	808-12032	GROOVING FOR PAVEMENT MARKINGS	435159.00	LFT
0077	808-12567	LINE, PREFORMED PLASTIC, SOLID, WHITE WITH BLACK TRIM, 6 IN.	137802.00	LFT
0078	808-12568	LINE, PREFORMED PLASTIC, SOLID, YELLOW WITH BLACK TRIM, 6 in.	135157.00	LFT
0079	808-12781	LINE, MULTI-COMPONENT, SOLID, WHITE, 10 IN.	46148.00	LFT
0080	808-12783	LINE, PREFORMED PLASTIC, BROKEN, BLACK, 6 IN.	81100.00	LFT
0081	808-75055	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 6 IN.	81100.00	LFT
0082	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	191.00	EACH
0083	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	191.00	EACH

Call: 121

Contract: R -41450-A

Section No.: 1            SMALL STRUCTURE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463		PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0012	203-02020		EXCAVATION, UNCLASSIFIED	1585.00	CYS
0013	205-11626		PUMP AROUND	1.00	EACH
0014	205-12108		STORMWATER MANAGEMENT BUDGET	22308.00	DOL
0015	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	205-12618		SWQCP PREPARATION	1.00	LS
0017	207-09935		SUBGRADE TREATMENT, TYPE IC	805.00	SYS
0018	207-12151		SUBGRADE TREATMENT, TYPE IVA	84.00	SYS
0019	211-09268		STRUCTURE BACKFILL, TYPE 5	100.00	CYS
0020	214-07202		GEOGRID, TYPE IA	1441.00	SYS
0021	214-12239		GEOTEXTILE FOR PAVEMENT, TYPE 2B	805.00	SYS
0022	303-01180		COMPACTED AGGREGATE, NO. 53	124.00	TON
0023	306-08034		MILLING, ASPHALT, 1 1/2 IN.	1302.00	SYS
0024	401-07328		QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	135.00	TON
0025	401-07398		QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	91.00	TON
0026	401-07408		QC/QA-HMA, 3, 64, BASE, 25.0 mm	291.00	TON
0027	401-10258		JOINT ADHESIVE, SURFACE	560.00	LFT
0028	401-10259		JOINT ADHESIVE, INTERMEDIATE	260.00	LFT
0029	401-11785		LIQUID ASPHALT SEALANT	1160.00	LFT
0030	406-05520		ASPHALT FOR TACK COAT	2.00	TON
0031	606-12400		MILLED HMA CORRUGATIONS, SINUSOIDAL	1200.00	LFT

0032	615-06490	RIGHT-OF-WAY MARKER	20.00	EACH
0033	616-05688	RIPRAP, CLASS 1	2608.00	TON
0034	616-06451	RIPRAP, UNIFORM	67.00	TON
0035	616-06451	RIPRAP, UNIFORM	104.00	TON
0036	616-09395	GEOMEMBRANE	104.00	SYS
0037	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	104.00	SYS
0038	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	4675.00	SYS
0039	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0040	621-02770	EROSION CONTROL BLANKET	285.00	SYS
0041	621-06545	FERTILIZER	1.00	TON
0042	621-06553	SEED MIXTURE, TYPE R	59.00	LBS
0043	621-06559	MULCHED SEEDING, TYPE R	355.00	SYS
0044	621-06565	MULCHING MATERIAL	1.00	TON
0045	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0046	628-12683	FIELD OFFICE, TYPE D	12.00	MOS
0047	715-05597	PIPE EXTENSION, CIRCULAR, DIAMETER 24 IN.	3.00	LFT
0048	715-09951	PIPE, TYPE 1, DEFORMED, MIN. AREA 42.4 SFT	68.00	LFT
0049	715-12172	CONCRETE ANCHOR, MIN. AREA 40 SFT	2.00	EACH
0050	801-04308	ROAD CLOSURE SIGN ASSEMBLY	13.00	EACH
0051	801-06625	DETOUR ROUTE MARKER ASSEMBLY	34.00	EACH
0052	801-06640	CONSTRUCTION SIGN, TYPE A	39.00	EACH
0053	801-06645	CONSTRUCTION SIGN, TYPE B	4.00	EACH
0054	801-06775	MAINTAINING TRAFFIC	1.00	LS
0055	801-07118	BARRICADE, TYPE III-A	96.00	LFT
0056	801-07119	BARRICADE, TYPE III-B	126.00	LFT
0057	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	50.00	LFT
0058	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	1000.00	LFT
0059	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	600.00	LFT
0060	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	4.00	EACH
0061	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	4.00	EACH

Call: 131

Contract: R -41802-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441		QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02271		HEADWALL, REMOVE	6.00	EACH
0013	202-96133		PIPE, REMOVE	146.00	LFT
0014	203-02000		EXCAVATION, COMMON	5070.00	CYS
0015	203-02010		EXCAVATION, ROCK	2300.00	CYS
0016	203-02070		BORROW	1220.00	CYS
0017	205-12108		STORMWATER MANAGEMENT BUDGET	22000.00	DOL
0018	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0019	205-12618		SWQCP PREPARATION	1.00	LS
0020	207-08264		SUBGRADE TREATMENT, TYPE II	149.00	SYS
0021	207-08268		SUBGRADE TREATMENT, TYPE IV	1442.00	SYS
0022	207-09935		SUBGRADE TREATMENT, TYPE IC	5216.00	SYS
0023	211-09264		STRUCTURE BACKFILL, TYPE 1	56.00	CYS
0024	211-09265		STRUCTURE BACKFILL, TYPE 2	110.00	CYS
0025	214-11796		GEOGRID, TYPE IB	49.00	SYS
0026	214-12239		GEOTEXTILE FOR PAVEMENT, TYPE 2B	5125.00	SYS
0027	301-12233		COMPACTED AGGREGATE, NO. 8	721.00	CYS
0028	301-12234		COMPACTED AGGREGATE, NO. 53	538.00	CYS
0029	302-07455		DENSE GRADED SUBBASE	7.00	CYS
0030	401-07334		QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	372.00	TON
0031	401-07403		QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	620.00	TON

0032	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	992.00 TON
0033	401-10258	JOINT ADHESIVE, SURFACE	518.00 LFT
0034	401-10259	JOINT ADHESIVE, INTERMEDIATE	518.00 LFT
0035	401-11785	LIQUID ASPHALT SEALANT	518.00 LFT
0036	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	822.00 TON
0037	406-05520	ASPHALT FOR TACK COAT	4.00 TON
0038	502-11564	PCCP, 7 IN.	350.00 SYS
0039	503-05240	D-1 CONTRACTION JOINT	247.00 LFT
0040	605-06090	CURB, INTEGRAL CONCRETE	202.00 LFT
0041	605-06125	CURB, CONCRETE, MODIFIED	1108.00 LFT
0042	605-06140	CURB AND GUTTER, CONCRETE	2293.00 LFT
0043	605-06255	CENTER CURB, D CONCRETE	9.00 SYS
0044	605-08636	CURB AND GUTTER, TURNOUT COMBINED	14.00 LFT
0045	605-97937	CURB AND GUTTER, ROLL CURB	296.00 LFT
0046	610-07487	HMA FOR APPROACHES, TYPE B	24.00 TON
0047	610-09108	PCCP FOR APPROACHES, 9 IN.	39.00 SYS
0048	611-08232	MAILBOX ASSEMBLY, RESET, SINGLE	1.00 EACH
0049	615-06490	RIGHT-OF-WAY MARKER	20.00 EACH
0050	615-06505	MONUMENT, TYPE B	14.00 EACH
0051	615-06515	MONUMENT, TYPE D	12.00 EACH
0052	615-06527	MONUMENT, SECTION CORNER	1.00 EACH
0053	616-05688	RIPRAP, CLASS 1	64.00 TON
0054	616-06405	RIPRAP, REVETMENT	149.00 TON
0055	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	425.00 SYS
0056	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	317.00 SYS
0057	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00 EACH
0058	621-06545	FERTILIZER	1.00 TON
0059	621-06554	SEED MIXTURE, TYPE U	300.00 LBS
0060	621-06565	MULCHING MATERIAL	4.00 TON
0061	621-06567	WATER	4.00 KGAL
0062	621-06574	SODDING	701.00 SYS
0063	621-06575	SODDING, NURSERY	933.00 SYS
0064	628-09403	FIELD OFFICE, TYPE C	12.00 MOS
0065	629-12029	PLANT GROWTH LAYER	2707.00 SYS
0066	715-05019	PIPE, TYPE 1, CIRCULAR, DIAMETER 36 IN.	183.00 LFT
0067	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	2193.00 LFT
0068	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	160.00 LFT



0069	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	311.00	LFT
0070	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	25.00	LFT
0071	715-46000	PIPE END SECTION, DIAMETER 12 IN.	10.00	EACH
0072	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0073	715-46040	PIPE END SECTION, DIAMETER 36 IN.	4.00	EACH
0074	718-06528	OUTLET PROTECTOR, TYPE 1	2.00	EACH
0075	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	2193.00	LFT
0076	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	1867.00	SYS
0077	718-52610	AGGREGATE FOR UNDERDRAINS	214.00	CYS
0078	720-98174	INLET, TYPE B15	10.00	EACH
0079	720-98555	INLET, TYPE C15	2.00	EACH
0080	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00	EACH
0081	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2566.00	LFT
0082	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	20.00	LFT
0083	801-06625	DETOUR ROUTE MARKER ASSEMBLY	21.00	EACH
0084	801-06640	CONSTRUCTION SIGN, TYPE A	18.00	EACH
0085	801-06775	MAINTAINING TRAFFIC	1.00	LS
0086	801-07118	BARRICADE, TYPE III-A	140.00	LFT
0087	801-12081	PORTABLE SIGNAL	1.00	LS
0088	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	2.00	EACH
0089	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	351.00	LFT
0090	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	5.00	EACH
0091	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	75.00	SFT
0092	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	38.00	SFT
0093	807-02191	HANDHOLE, LIGHTING	5.00	EACH
0094	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	117.00	LFT
0095	807-09637	WIRE, NO. 6 COPPER, IN PLASTIC DUCT, 4 1/C	117.00	LFT
0096	807-09638	WIRE, NO. 6 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1158.00	LFT
0097	807-12199	LUMINAIRE, HIGH LUMEN ROADWAY	6.00	EACH
0098	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE, WITH GROUNDING	6.00	EACH
0099	807-85752	LIGHT POLE, 40 FT E.M.H., 10 FT MAST ARM, BREAKAWAY BASE	6.00	EACH
0100	807-86805	SERVICE POINT, TYPE I	1.00	EACH
0101	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	960.00	LFT
0102	807-86910	CONNECTOR KIT, UNFUSED	6.00	EACH
0103	807-86915	CONNECTOR KIT, FUSED	6.00	EACH
0104	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	19.00	EACH
0105	807-86935	INSULATION LINK, WATERPROOFED	32.00	EACH

0106	808-11478	LINE, THERMOPLASTIC, DOTTED, WHITE, 8 IN.	39.00	LFT
0107	808-11698	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 27 IN.	49.00	LFT
0108	808-12032	GROOVING FOR PAVEMENT MARKINGS	3623.00	LFT
0109	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	144.00	LFT
0110	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	2851.00	LFT
0111	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	540.00	LFT
0112	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	3.00	EACH
0113	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	16.00	EACH
0114	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	32.00	EACH

Call: 141

Contract: R -41933-A

Section No.: 1 PEDESTRIAN FLASHING BEACONS, INSTALLED

**Line**

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	202-74035	SIGN, REMOVE	27.00	EACH
0008	801-06640	CONSTRUCTION SIGN, TYPE A	6.00	EACH
0009	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	EACH
0010	801-06775	MAINTAINING TRAFFIC	1.00	LS
0011	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	154.00	LFT
0012	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	116.00	SFT
0013	805-11799	RECTANGULAR RAPID FLASHING BEACON	10.00	EACH
0014	805-11799	RECTANGULAR RAPID FLASHING BEACON	4.00	EACH
0015	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	227.00	LFT
0016	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	477.00	LFT
0017	807-86805	SERVICE POINT, TYPE I	5.00	EACH
0018	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	706.00	LFT

Call: 161

Contract: R -42253-A

Section No.: 1 ROAD RECONSTRUCTION

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463		PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377		QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	109-12573		SPECIAL MAINTENANCE	200000.00	DOL
0012	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0013	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0014	202-04435		DELINEATOR POST, REMOVE	3.00	EACH
0015	202-51330		PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0016	203-02000		EXCAVATION, COMMON	21217.00	CYS
0017	203-02070		BORROW	1335.00	CYS
0018	205-11626		PUMP AROUND	8.00	EACH
0019	205-12108		STORMWATER MANAGEMENT BUDGET	265500.00	DOL
0020	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0021	205-12618		SWQCP PREPARATION	1.00	LS
0022	207-08264		SUBGRADE TREATMENT, TYPE II	11782.00	SYS
0023	207-09935		SUBGRADE TREATMENT, TYPE IC	1342.00	SYS
0024	207-12635		SUBGRADE TREATMENT, TYPE IBC	32718.00	SYS
0025	211-02050		B BORROW	1072.00	CYS
0026	211-09265		STRUCTURE BACKFILL, TYPE 2	728.00	CYS
0027	211-09268		STRUCTURE BACKFILL, TYPE 5	146.00	CYS
0028	214-11796		GEOGRID, TYPE IB	1342.00	SYS
0029	301-12233		COMPACTED AGGREGATE, NO. 8	82.00	CYS
0030	301-12234		COMPACTED AGGREGATE, NO. 53	439.00	CYS
0031	303-01180		COMPACTED AGGREGATE, NO. 53	12133.00	TON

0032	304-12627	HMA PATCHING, FULL DEPTH, TYPE D	1933.00 TON
0033	304-12628	HMA PATCHING, PARTIAL DEPTH, TYPE D	2150.00 TON
0034	306-08043	MILLING, TRANSITION	4280.00 SYS
0035	306-08432	MILLING, APPROACH	4329.00 SYS
0036	306-10163	MILLING, ASPHALT, 2 1/2 IN.	156375.00 SYS
0037	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	15657.00 TON
0038	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	30967.00 TON
0039	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	15126.00 TON
0040	401-10258	JOINT ADHESIVE, SURFACE	93998.00 LFT
0041	401-10259	JOINT ADHESIVE, INTERMEDIATE	93998.00 LFT
0042	401-11785	LIQUID ASPHALT SEALANT	93998.00 LFT
0043	401-12169	INERTIAL PROFILER, HMA	1.00 LS
0044	402-10087	HMA FOR TEMPORARY PAVEMENT, TYPE D	3111.00 TON
0045	406-05520	ASPHALT FOR TACK COAT	159.10 TON
0046	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	219.00 LFT
0047	601-94689	GUARDRAIL END TREATMENT, TYPE OS	6.00 EACH
0048	605-06120	CURB, CONCRETE	50.00 LFT
0049	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	42756.00 LFT
0050	610-07487	HMA FOR APPROACHES, TYPE B	1980.00 TON
0051	611-06497	MAILBOX ASSEMBLY, SINGLE	7.00 EACH
0052	615-06490	RIGHT-OF-WAY MARKER	103.00 EACH
0053	615-06505	MONUMENT, TYPE B	42.00 EACH
0054	615-06510	MONUMENT, TYPE C	1.00 EACH
0055	615-06527	MONUMENT, SECTION CORNER	15.00 EACH
0056	616-05688	RIPRAP, CLASS 1	284.00 TON
0057	616-06405	RIPRAP, REVETMENT	828.00 TON
0058	616-06451	RIPRAP, UNIFORM	1345.00 TON
0059	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	4196.00 SYS
0060	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	3051.00 SYS
0061	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.00 EACH
0062	621-06545	FERTILIZER	3.00 TON
0063	621-06553	SEED MIXTURE, TYPE R	1473.00 LBS
0064	621-06565	MULCHING MATERIAL	15.00 TON
0065	621-06567	WATER	15.00 KGAL
0066	621-06574	SODDING	3761.00 SYS
0067	628-09409	MOBILE INTERNET SERVICE	22.00 MOS
0068	628-11729	CELLULAR TELEPHONE, TYPE A	1.00 EACH

0069	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0070	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0071	628-11977	COMPUTER SYSTEM	1.00 EACH
0072	628-12683	FIELD OFFICE, TYPE D	22.00 MOS
0073	628-12923	CELLULAR TELEPHONE SERVICE, UNLIMITED MINUTES	22.00 MOS
0074	714-11705	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 8 FT X 4 FT	60.00 LFT
0075	714-11767	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 10 FT X 5 FT	60.00 LFT
0076	714-12089	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 4 FT X 2 FT	52.00 LFT
0077	714-12091	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 7 FT X 4 FT	63.00 LFT
0078	714-12499	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 5 FT X 3 FT	109.00 LFT
0079	714-12516	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 3 FT X 2 FT	125.00 LFT
0080	714-12920	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 4 FT X 3 FT	56.00 LFT
0081	715-03475	SAFETY METAL END SECTION, 4:1, DIAMETER 15 IN.	62.00 EACH
0082	715-05019	PIPE, TYPE 1, CIRCULAR, DIAMETER 36 IN.	119.00 LFT
0083	715-05052	PIPE, TYPE 4, CIRCULAR, DIAMETER 12 IN.	100.00 LFT
0084	715-05119	PIPE, TYPE 1, CIRCULAR, DIAMETER 15 IN.	76.00 LFT
0085	715-05168	PIPE, TYPE 3, CIRCULAR, DIAMETER 12 IN.	774.00 LFT
0086	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	2020.00 LFT
0087	715-05171	PIPE, TYPE 3, CIRCULAR, DIAMETER 18 IN.	128.00 LFT
0088	715-05173	PIPE, TYPE 3, CIRCULAR, DIAMETER 24 IN.	35.00 LFT
0089	715-05363	PIPE, TYPE 3, DEFORMED, MIN. AREA 1.8 SFT	61.00 LFT
0090	715-08307	HMA FOR STRUCTURE INSTALLATION, TYPE D	497.00 TON
0091	715-09064	VIDEO INSPECTION FOR PIPE	115.00 LFT
0092	715-09307	GRATED BOX END SECTION, TYPE I, 3:1, MIN. AREA 6.28 SFT	2.00 EACH
0093	715-09307	GRATED BOX END SECTION, TYPE I, 3:1, MIN. AREA 6.28 SFT	2.00 EACH
0094	715-12068	GRATED BOX END SECTION, TYPE I, 3:1, MIN. AREA 8.9 SFT	2.00 EACH
0095	715-12071	GRATED BOX END SECTION, TYPE I, 3:1, MIN. AREA 12.9 SFT	2.00 EACH
0096	715-26822	GRATED BOX END SECTION, TYPE I, 3:1, MIN. AREA 15.0 SFT	2.00 EACH
0097	715-26822	GRATED BOX END SECTION, TYPE I, 3:1, MIN. AREA 15.0 SFT	2.00 EACH
0098	715-46000	PIPE END SECTION, DIAMETER 12 IN.	50.00 EACH
0099	715-46005	PIPE END SECTION, DIAMETER 15 IN.	40.00 EACH
0100	715-46010	PIPE END SECTION, DIAMETER 18 IN.	8.00 EACH
0101	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00 EACH
0102	715-46055	PIPE END SECTION, MIN. AREA 1.8 SFT	4.00 EACH
0103	715-97691	GRATED BOX END SECTION, TYPE I, 3:1, DIAMETER 36 IN.	4.00 EACH
0104	720-12796	CASTING, CATCH BASIN, ADJUST TO GRADE	1.00 EACH
0105	720-45410	MANHOLE, TYPE C4	4.00 EACH

0106	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00	ACH
0107	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	148646.00	LFT
0108	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	7604.00	LFT
0109	801-06625	DETOUR ROUTE MARKER ASSEMBLY	69.00	ACH
0110	801-06640	CONSTRUCTION SIGN, TYPE A	35.00	ACH
0111	801-06645	CONSTRUCTION SIGN, TYPE B	12.00	ACH
0112	801-06710	FLASHING ARROW SIGN	2.00	DAY
0113	801-06775	MAINTAINING TRAFFIC	1.00	LS
0114	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	24.00	ACH
0115	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0116	801-07119	BARRICADE, TYPE III-B	48.00	LFT
0117	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	6520.00	LFT
0118	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	8.00	ACH
0119	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	241.00	LFT
0120	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	106.00	LFT
0121	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	41.00	SFT
0122	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	187.00	SFT
0123	804-06725	DELINEATOR WITH POST, TYPE D1	19.00	ACH
0124	808-06716	LINE, REMOVE	38210.00	LFT
0125	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0126	808-12032	GROOVING FOR PAVEMENT MARKINGS	153555.00	LFT
0127	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	95754.00	LFT
0128	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	46720.00	LFT
0129	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	897.00	LFT
0130	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	42.00	LFT
0131	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	5.00	ACH
0132	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1001.00	ACH
0133	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1001.00	ACH
0134	808-96075	LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN.	4209.00	LFT
0135	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	8863.00	LFT

Call: 165

Contract: R -42304-B

Section No.: 1 ROAD RECONSTRUCTION

**Line**

<b>Item No</b>	<b>Item Code</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-96133	PIPE, REMOVE	679.00	LFT
0013	202-99187	FENCE, FARM FIELD, REMOVE	1533.00	LFT
0014	203-02000	EXCAVATION, COMMON	19986.00	CYS
0015	203-02070	BORROW	6217.00	CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	133207.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	1043.00	SYS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	1302.00	SYS
0021	211-02050	B BORROW	244.00	CYS
0022	211-09264	STRUCTURE BACKFILL, TYPE 1	344.00	CYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	13.00	CYS
0024	211-09268	STRUCTURE BACKFILL, TYPE 5	233.00	CYS
0025	214-11796	GEOGRID, TYPE IB	565.00	SYS
0026	302-07455	DENSE GRADED SUBBASE	174.00	CYS
0027	303-01180	COMPACTED AGGREGATE, NO. 53	5783.00	TON
0028	304-07493	WIDENING WITH HMA, TYPE B	203.00	TON
0029	306-08038	MILLING, ASPHALT, 4 IN.	37831.00	SYS
0030	306-08042	MILLING, SCARIFICATION	48151.00	SYS
0031	306-08043	MILLING, TRANSITION	963.00	SYS

0032	307-12253	CORRECTIVE AGGREGATE, FDR	9177.00 TON
0033	307-12254	FULL DEPTH RECLAMATION	48151.00 SYS
0034	307-12256	STABILIZING MATERIAL, PORTLAND CEMENT	1561.00 TON
0035	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	3984.00 TON
0036	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	6621.00 TON
0037	401-10258	JOINT ADHESIVE, SURFACE	15870.00 LFT
0038	401-10259	JOINT ADHESIVE, INTERMEDIATE	15870.00 LFT
0039	401-11785	LIQUID ASPHALT SEALANT	15870.00 LFT
0040	401-12169	INERTIAL PROFILER, HMA	1.00 LS
0041	406-05520	ASPHALT FOR TACK COAT	25.00 TON
0042	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	47871.00 LFT
0043	610-07487	HMA FOR APPROACHES, TYPE B	686.00 TON
0044	610-08446	PCCP FOR APPROACHES, 6 IN.	479.00 SYS
0045	610-09108	PCCP FOR APPROACHES, 9 IN.	565.00 SYS
0046	611-06497	MAILBOX ASSEMBLY, SINGLE	15.00 EACH
0047	615-06490	RIGHT-OF-WAY MARKER	63.00 EACH
0048	615-06505	MONUMENT, TYPE B	21.00 EACH
0049	615-06527	MONUMENT, SECTION CORNER	7.00 EACH
0050	616-05688	RIPRAP, CLASS 1	123.00 TON
0051	616-06405	RIPRAP, REVETMENT	35.00 TON
0052	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	314.00 SYS
0053	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00 EACH
0054	621-06545	FERTILIZER	8.00 TON
0055	621-06553	SEED MIXTURE, TYPE R	3757.00 LBS
0056	621-06565	MULCHING MATERIAL	38.00 TON
0057	628-09403	FIELD OFFICE, TYPE C	16.00 MOS
0058	714-11193	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 4 FT X 2 FT	40.00 LFT
0059	715-04522	PIPE END SECTION, DIAMETER 42 IN.	2.00 EACH
0060	715-05019	PIPE, TYPE 1, CIRCULAR, DIAMETER 36 IN.	41.00 LFT
0061	715-05118	PIPE, TYPE 1, CIRCULAR, DIAMETER 12 IN.	800.00 LFT
0062	715-05119	PIPE, TYPE 1, CIRCULAR, DIAMETER 15 IN.	182.00 LFT
0063	715-05121	PIPE, TYPE 1, CIRCULAR, DIAMETER 18 IN.	364.00 LFT
0064	715-05122	PIPE, TYPE 1, CIRCULAR, DIAMETER 21 IN.	220.00 LFT
0065	715-05123	PIPE, TYPE 1, CIRCULAR, DIAMETER 24 IN.	644.00 LFT
0066	715-05125	PIPE, TYPE 1, CIRCULAR, DIAMETER 30 IN.	162.00 LFT
0067	715-05127	PIPE, TYPE 1, CIRCULAR, DIAMETER 42 IN.	43.00 LFT
0068	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	243.00 LFT



0069	715-05171	PIPE, TYPE 3, CIRCULAR, DIAMETER 18 IN.	68.00	LFT
0070	715-09064	VIDEO INSPECTION FOR PIPE	1967.00	LFT
0071	715-46005	PIPE END SECTION, DIAMETER 15 IN.	20.00	EACH
0072	715-46010	PIPE END SECTION, DIAMETER 18 IN.	16.00	EACH
0073	715-46015	PIPE END SECTION, DIAMETER 21 IN.	8.00	EACH
0074	715-46020	PIPE END SECTION, DIAMETER 24 IN.	24.00	EACH
0075	715-46030	PIPE END SECTION, DIAMETER 30 IN.	6.00	EACH
0076	715-46040	PIPE END SECTION, DIAMETER 36 IN.	2.00	EACH
0077	801-03290	CONSTRUCTION SIGN, TYPE C	3.00	EACH
0078	801-04308	ROAD CLOSURE SIGN ASSEMBLY	10.00	EACH
0079	801-06625	DETOUR ROUTE MARKER ASSEMBLY	52.00	EACH
0080	801-06640	CONSTRUCTION SIGN, TYPE A	19.00	EACH
0081	801-06775	MAINTAINING TRAFFIC	1.00	LS
0082	801-07119	BARRICADE, TYPE III-B	288.00	LFT
0083	802-04893	REFERENCE POST	3.00	EACH
0084	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	247.00	LFT
0085	802-05705	SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	140.00	LFT
0086	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	38.00	EACH
0087	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH
0088	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	155.00	SFT
0089	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	123.00	SFT
0090	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0091	808-12032	GROOVING FOR PAVEMENT MARKINGS	49036.00	LFT
0092	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	31324.00	LFT
0093	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	14987.00	LFT
0094	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	46.00	LFT
0095	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	2725.00	LFT

Call: 175

Contract: R -42979-B

Section No.: 1            SMALL STRUCTURES AND DRAINS CONSTRUCTION

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-02271		HEADWALL, REMOVE	4.00	EACH
0012	202-96133		PIPE, REMOVE	98.00	LFT
0013	203-02000		EXCAVATION, COMMON	140.00	CYS
0014	203-02070		BORROW	10.00	CYS
0015	205-12108		STORMWATER MANAGEMENT BUDGET	7093.00	DOL
0016	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	213-09269		FLOWABLE BACKFILL, NON-REMOVABLE	79.00	CYS
0018	303-01180		COMPACTED AGGREGATE, NO. 53	6.00	TON
0019	306-08034		MILLING, ASPHALT, 1 1/2 IN.	777.00	SYS
0020	401-07328		QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	66.00	TON
0021	401-10258		JOINT ADHESIVE, SURFACE	655.00	LFT
0022	401-10259		JOINT ADHESIVE, INTERMEDIATE	55.00	LFT
0023	401-11785		LIQUID ASPHALT SEALANT	655.00	LFT
0024	406-05521		ASPHALT FOR TACK COAT	990.00	SYS
0025	606-12399		MILLED HMA CORRUGATIONS, CONVENTIONAL	109.50	LFT
0026	611-08232		MAILBOX ASSEMBLY, RESET, SINGLE	1.00	EACH
0027	616-06405		RIPRAP, REVETMENT	9.00	TON
0028	616-12248		GEOTEXTILE FOR RIPRAP, TYPE 2A	22.00	SYS
0029	621-01004		MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0030	621-06559		MULCHED SEEDING, TYPE R	683.00	SYS
0031	621-06560		MULCHED SEEDING, TYPE U	265.00	SYS

0032	702-51005	CONCRETE, A, SUBSTRUCTURE	0.60	CYS
0033	703-06029	REINFORCING BARS, EPOXY COATED	60.00	LBS
0034	715-05121	PIPE, TYPE 1, CIRCULAR, DIAMETER 18 IN.	58.00	LFT
0035	715-05123	PIPE, TYPE 1, CIRCULAR, DIAMETER 24 IN.	53.00	LFT
0036	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	50.00	TON
0037	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	EACH
0038	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00	EACH
0039	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00	EACH
0040	801-06625	DETOUR ROUTE MARKER ASSEMBLY	25.00	EACH
0041	801-06640	CONSTRUCTION SIGN, TYPE A	32.00	EACH
0042	801-06775	MAINTAINING TRAFFIC	1.00	LS
0043	801-07118	BARRICADE, TYPE III-A	56.00	LFT
0044	801-07119	BARRICADE, TYPE III-B	60.00	LFT
0045	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	436.00	LFT
0046	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	436.00	LFT

Call: 191

Contract: R -43628-B

Section No.: 1 DRAINAGE DITCH CORRECTION

**Line**

<b>Item No</b>	<b>Item Code</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	203-08607	LINEAR GRADING	365988.00	LFT
0009	628-09403	FIELD OFFICE, TYPE C	12.00	MOS
0010	715-01662	PIPE CLEANING, DIAMETER 12 IN. TO 48 IN.	770.00	LFT
0011	720-01355	INLET, CLEAN EXISTING	1.00	EACH
0012	801-06710	FLASHING ARROW SIGN	6.00	DAY
0013	801-06775	MAINTAINING TRAFFIC	1.00	LS
0014	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0015	801-12042	TRUCK MOUNTED ATTENUATOR	18.00	DAY
0016	801-12324	LAW ENFORCEMENT OFFICER	170.00	HRS
0017	801-92448	CONSTRUCTION SIGNS MOBILE	54.00	DAY

Call: 201

Contract: R -44206-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-02240		PAVEMENT REMOVAL	894.00	SYS
0012	202-02273		CENTER CURB, CONCRETE, REMOVE	9.00	SYS
0013	202-02278		CURB, CONCRETE, REMOVE	86.00	LFT
0014	202-02279		CURB AND GUTTER, REMOVE	398.00	LFT
0015	202-52710		SIDEWALK CONCRETE, REMOVE	90.00	SYS
0016	202-74035		SIGN, REMOVE	15.00	EACH
0017	202-93741		GUARDRAIL END TREATMENT, REMOVE	4.00	EACH
0018	202-96430		FENCE AND POSTS, REMOVE	1.00	LS
0019	203-02000		EXCAVATION, COMMON	2359.00	CYS
0020	203-02070		BORROW	2451.00	CYS
0021	203-05591		CLAY	1650.00	CYS
0022	205-12108		STORMWATER MANAGEMENT BUDGET	72515.00	DOL
0023	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0024	205-12618		SWQCP PREPARATION	1.00	LS
0025	207-08264		SUBGRADE TREATMENT, TYPE II	9325.00	SYS
0026	211-09265		STRUCTURE BACKFILL, TYPE 2	22.00	CYS
0027	301-12234		COMPACTED AGGREGATE, NO. 53	48.00	CYS
0028	305-07471		WIDENING WITH PCC BASE, 8 IN.	206.00	SYS
0029	306-08041		MILLING, PCCP	1597.00	SYS
0030	401-07321		QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1524.00	TON
0031	401-07390		QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	308.00	TON

0032	406-05520	ASPHALT FOR TACK COAT	2.00 TON
0033	601-02241	GUARDRAIL, REMOVE	2154.00 LFT
0034	601-94689	GUARDRAIL END TREATMENT, TYPE OS	4.00 EACH
0035	603-03692	FENCE, WOOD	1005.00 LFT
0036	603-91714	FENCE RAIL, WOOD	794.00 LFT
0037	603-91714	FENCE RAIL, WOOD	3234.00 LFT
0038	604-06070	SIDEWALK, CONCRETE	24.00 SYS
0039	604-08086	CURB RAMP, CONCRETE	29.00 SYS
0040	604-12083	DETECTABLE WARNING SURFACES	9.00 SYS
0041	605-06120	CURB, CONCRETE	1900.00 LFT
0042	605-06140	CURB AND GUTTER, CONCRETE	65.00 LFT
0043	616-06405	RIPRAP, REVETMENT	16.00 TON
0044	616-12247	GEOTEXTILE FOR RIPRAP, TYPE 1B	36.00 SYS
0045	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0046	621-02770	EROSION CONTROL BLANKET	12690.00 SYS
0047	621-06545	FERTILIZER	2.00 TON
0048	621-06554	SEED MIXTURE, TYPE U	531.00 LBS
0049	621-06560	MULCHED SEEDING, TYPE U	12690.00 SYS
0050	621-06565	MULCHING MATERIAL	5.00 TON
0051	621-06567	WATER	64.00 kGAL
0052	621-06575	SODDING, NURSERY	3301.00 SYS
0053	628-09403	FIELD OFFICE, TYPE C	12.00 MOS
0054	629-12029	PLANT GROWTH LAYER	15991.00 SYS
0055	702-51015	CONCRETE, B, FOOTINGS	43.00 CYS
0056	715-05118	PIPE, TYPE 1, CIRCULAR, DIAMETER 12 IN.	104.00 LFT
0057	715-46000	PIPE END SECTION, DIAMETER 12 IN.	7.00 EACH
0058	720-01888	ADJUST MONITORING WELL TO GRADE	1.00 EACH
0059	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	1.00 EACH
0060	732-11810	MODULAR BLOCK WALL	2460.00 SFT
0061	732-11811	MODULAR BLOCK WALL ERECTION	2460.00 SFT
0062	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2632.00 LFT
0063	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	40.00 LFT
0064	801-06640	CONSTRUCTION SIGN, TYPE A	5.00 EACH
0065	801-06645	CONSTRUCTION SIGN, TYPE B	4.00 EACH
0066	801-06775	MAINTAINING TRAFFIC	1.00 LS
0067	801-07118	BARRICADE, TYPE III-A	44.00 LFT
0068	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	205.00 LFT

0069	801-11990	TEMPORARY CURB RAMP	1.00	EACH
0070	801-12081	PORTABLE SIGNAL	1.00	LS
0071	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	54.00	SYS
0072	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	4.00	EACH
0073	802-03896	BOLLARD	4.00	EACH
0074	802-04314	SIGN	3.00	EACH
0075	802-04314	SIGN	7.00	EACH
0076	802-04314	SIGN	5.00	EACH
0077	802-04314	SIGN	5.00	EACH
0078	802-04314	SIGN	5.00	EACH
0079	802-04314	SIGN	7.00	EACH
0080	802-04314	SIGN	1.00	EACH
0081	805-01842	HANDHOLE, SIGNAL, TYPE 1	1.00	EACH
0082	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	4.00	EACH
0083	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	4.00	EACH
0084	805-04133	SIGNAL POLE, PEDESTAL, 12 FT	4.00	EACH
0085	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	100.00	LFT
0086	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	79.00	LFT
0087	805-11817	PEDESTRIAN PUSH BUTTON, APS	4.00	EACH
0088	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GAUGE	179.00	LFT
0089	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	179.00	LFT
0090	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	220.00	LFT
0091	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	7982.00	LFT
0092	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	43.00	LFT

Call: 211

Contract: R -44227-A

Section No.: 1 INSTITUTION AND PARK ROAD MAINTENANCE

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358		INSPECTION HOLE, DEEPER THAN 3 FT	3.00	EACH
0003	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360		CONTRACT LIENS	1.00	DOL
0005	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02278		CURB, CONCRETE, REMOVE	238.00	LFT
0013	202-02772		CASTING, REMOVE	2.00	EACH
0014	202-04791		PARKING BARRIER, REMOVE	76.00	EACH
0015	202-52710		SIDEWALK CONCRETE, REMOVE	344.00	SYS
0016	203-02000		EXCAVATION, COMMON	1967.00	CYS
0017	205-12108		STORMWATER MANAGEMENT BUDGET	20955.00	DOL
0018	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0019	207-08264		SUBGRADE TREATMENT, TYPE II	381.00	SYS
0020	207-12635		SUBGRADE TREATMENT, TYPE IBC	8037.00	SYS
0021	211-09267		STRUCTURE BACKFILL, TYPE 4	40.00	CYS
0022	214-11796		GEOGRID, TYPE IB	381.00	SYS
0023	301-12234		COMPACTED AGGREGATE, NO. 53	112.00	CYS
0024	303-01180		COMPACTED AGGREGATE, NO. 53	1118.00	TON
0025	304-12623		HMA PATCHING, FULL DEPTH, TYPE B	105.00	TON
0026	306-08034		MILLING, ASPHALT, 1 1/2 IN.	3463.00	SYS
0027	306-08042		MILLING, SCARIFICATION	1567.00	SYS
0028	306-08043		MILLING, TRANSITION	152.00	SYS
0029	306-08432		MILLING, APPROACH	525.00	SYS
0030	401-07321		QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1136.00	TON
0031	401-07390		QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1772.00	TON



0032	401-10258	JOINT ADHESIVE, SURFACE	6084.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	8033.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	6084.00	LFT
0035	406-05520	ASPHALT FOR TACK COAT	8.00	TON
0036	605-06120	CURB, CONCRETE	35.00	LFT
0037	605-52807	CURB AND GUTTER, COMBINED	159.00	LFT
0038	605-52807	CURB AND GUTTER, COMBINED	14.00	LFT
0039	615-11537	PARKING BARRIER, CONCRETE	130.00	EACH
0040	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00	EACH
0041	621-06545	FERTILIZER	1.00	TON
0042	621-06560	MULCHED SEEDING, TYPE U	2417.00	SYS
0043	621-06567	WATER	3.00	KGAL
0044	621-06570	TOPSOIL	3.00	CYS
0045	628-09403	FIELD OFFICE, TYPE C	6.00	MOS
0046	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0047	715-04965	WATER SERVICE LINE	30.00	LFT
0048	715-07794	WATER MAIN CONNECTIONS	2.00	EACH
0049	715-11896	WATER SERVICE CONNECTION	2.00	EACH
0050	715-91739	WATER SERVICE LINE, 0.75 IN.	40.00	LFT
0051	715-93403	WATER SERVICE CONNECTION, 0.75 IN.	2.00	EACH
0052	715-96629	WATER SERVICE LINE, 1 IN.	30.00	LFT
0053	720-12797	CASTING, INLET, ADJUST TO GRADE	6.00	EACH
0054	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	9.00	EACH
0055	801-04308	ROAD CLOSURE SIGN ASSEMBLY	12.00	EACH
0056	801-06640	CONSTRUCTION SIGN, TYPE A	23.00	EACH
0057	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	EACH
0058	801-06775	MAINTAINING TRAFFIC	1.00	LS
0059	801-07118	BARRICADE, TYPE III-A	337.00	LFT
0060	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	180.00	LFT
0061	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	94.00	SFT
0062	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	3258.00	LFT
0063	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	210.00	LFT
0064	808-09314	LINE, PAINT, SOLID, BLUE, 4 IN.	390.00	LFT
0065	808-97222	PAVEMENT MESSAGE MARKING, PAINT, ADA ACCESSIBLE SYMBOL	6.00	EACH

Call: 311

Contract: B -41467-A

Section No.: 1            SMALL STRUCTURE PIPE LINING

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463		PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02240		PAVEMENT REMOVAL	860.00	SYS
0013	202-51330		PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0014	202-51330		PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0015	202-90277		DETECTOR HOUSING, REMOVE	2.00	EACH
0016	202-96022		CONCRETE FOUNDATION, REMOVE	2.00	EACH
0017	202-96133		PIPE, REMOVE	526.00	LFT
0018	203-02000		EXCAVATION, COMMON	6351.00	CYS
0019	203-02070		BORROW	7519.00	CYS
0020	205-11626		PUMP AROUND	5.00	EACH
0021	205-12108		STORMWATER MANAGEMENT BUDGET	28636.00	DOL
0022	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0023	205-12618		SWQCP PREPARATION	1.00	LS
0024	206-51230		EXCAVATION, FOUNDATION, UNCLASSIFIED	213.00	CYS
0025	206-51235		COFFERDAM	1.00	LS
0026	206-51817		SHEET PILING STEEL	854.00	SFT
0027	207-08264		SUBGRADE TREATMENT, TYPE II	11112.00	SYS
0028	207-09935		SUBGRADE TREATMENT, TYPE IC	3284.00	SYS
0029	211-02050		B BORROW	57.00	CYS
0030	211-09265		STRUCTURE BACKFILL, TYPE 2	657.00	CYS
0031	211-09268		STRUCTURE BACKFILL, TYPE 5	1932.00	CYS

0032	214-11796	GEOGRID, TYPE IB	309.00	SYS
0033	214-12237	GEOTEXTILE FOR PAVEMENT, TYPE 1B	40.00	SYS
0034	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	2277.00	SYS
0035	301-12232	COMPACTED AGGREGATE, NO. 5	137.00	CYS
0036	301-12233	COMPACTED AGGREGATE, NO. 8	13.00	CYS
0037	301-12234	COMPACTED AGGREGATE, NO. 53	18.00	CYS
0038	302-06464	SUBBASE FOR PCCP	114.00	CYS
0039	303-01180	COMPACTED AGGREGATE, NO. 53	324.00	TON
0040	304-07493	WIDENING WITH HMA, TYPE B	433.00	TON
0041	306-08034	MILLING, ASPHALT, 1 1/2 IN.	8988.00	SYS
0042	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	365.00	TON
0043	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	374.00	TON
0044	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	241.00	TON
0045	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	60.00	TON
0046	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	195.00	TON
0047	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	62.00	TON
0048	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	841.00	TON
0049	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	24.00	TON
0050	401-10258	JOINT ADHESIVE, SURFACE	4245.00	LFT
0051	401-10259	JOINT ADHESIVE, INTERMEDIATE	2593.00	LFT
0052	401-11785	LIQUID ASPHALT SEALANT	4245.00	LFT
0053	402-10086	HMA FOR TEMPORARY PAVEMENT, TYPE C	7130.00	TON
0054	406-05521	ASPHALT FOR TACK COAT	10118.00	SYS
0055	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	1.00	TON
0056	601-02241	GUARDRAIL, REMOVE	1713.00	LFT
0057	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	682.00	LFT
0058	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED, 6 FT 3 IN. SPACING	494.00	LFT
0059	601-12288	GUARDRAIL, MGS, LONG SPAN, TYPE 2	2.00	EACH
0060	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	6.00	EACH
0061	601-94689	GUARDRAIL END TREATMENT, TYPE OS	8.00	EACH
0062	601-94690	GUARDRAIL END TREATMENT, TYPE MS	2.00	EACH
0063	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	50.00	LFT
0064	601-99132	GUARDRAIL HEIGHT TRANSITION, VH, 6 FT 3 IN. SPACING	2.00	EACH
0065	602-06729	BARRIER DELINEATOR	8.00	EACH
0066	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	3645.00	LFT
0067	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	454.00	SYS
0068	610-07487	HMA FOR APPROACHES, TYPE B	172.00	TON

0069	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00 EACH
0070	616-06405	RIPRAP, REVETMENT	989.00 TON
0071	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	923.00 SYS
0072	616-12247	GEOTEXTILE FOR RIPRAP, TYPE 1B	569.00 SYS
0073	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	394.00 SYS
0074	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	656.00 SYS
0075	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00 EACH
0076	621-02770	EROSION CONTROL BLANKET	1908.00 SYS
0077	621-06559	MULCHED SEEDING, TYPE R	5951.00 SYS
0078	621-06567	WATER	4.00 KGAL
0079	621-06574	SODDING	49.00 SYS
0080	621-06575	SODDING, NURSERY	790.00 SYS
0081	628-09403	FIELD OFFICE, TYPE C	15.00 MOS
0082	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0083	701-09558	TEST PILE, INDICATOR, PRODUCTION	348.00 LFT
0084	701-09560	TEST PILE, INDICATOR, RESTRIKE	4.00 EACH
0085	701-09663	PILE, STEEL PIPE, 0.312 IN., DIAMETER 14 IN.	8400.00 LFT
0086	701-12836	AUTOMATED PILE DRIVING DATA ACQUISITION DEVICE	1.00 EACH
0087	702-51005	CONCRETE, A, SUBSTRUCTURE	189.40 CYS
0088	702-51015	CONCRETE, B, FOOTINGS	1.00 CYS
0089	702-92857	CONCRETE, C, SUBSTRUCTURE	220.80 CYS
0090	703-06028	REINFORCING BARS	44702.00 LBS
0091	703-06029	REINFORCING BARS, EPOXY COATED	59653.00 LBS
0092	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	88.00 EACH
0093	704-51002	CONCRETE, C, SUPERSTRUCTURE	141.40 CYS
0094	706-11600	RAILING, CONCRETE TYPE FC	10.00 CYS
0095	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	8.00 EACH
0096	709-51821	SURFACE SEAL	1.00 LS
0097	709-51821	SURFACE SEAL	1.00 LS
0098	711-51035	STRUCTURAL STEEL	2002.00 LBS
0099	714-11174	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT X 4 FT	295.00 LFT
0100	714-11634	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 15 FT X 4 FT	58.00 LFT
0101	715-05121	PIPE, TYPE 1, CIRCULAR, DIAMETER 18 IN.	83.00 LFT
0102	715-05146	PIPE, TYPE 2, CIRCULAR, DIAMETER 6 IN.	7.00 LFT
0103	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	51.00 LFT
0104	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	12.00 LFT
0105	715-05263	PIPE, TYPE 1, DEFORMED, MIN. AREA 29 SFT	18.00 LFT

0106	715-06004	CONCRETE ANCHOR, DIAMETER 48 IN.	1.00	EACH
0107	715-10123	CONCRETE ANCHOR, MIN. AREA 26.0 SFT	2.00	EACH
0108	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	EACH
0109	720-44025	CASTING, TYPE 4, FURNISH AND ADJUST TO GRADE	4.00	EACH
0110	720-45030	INLET, TYPE E7	2.00	EACH
0111	720-45065	INLET, TYPE N12	2.00	EACH
0112	725-08296	PIPE LINER, CURED-IN-PLACE, 48 IN.	360.00	LFT
0113	725-10245	PERPETUATION, EXISTING PIPE	2.00	EACH
0114	725-12052	PIPE LINER, CURED-IN-PLACE, MIN. AREA 26.8 SFT	200.00	LFT
0115	801-03290	CONSTRUCTION SIGN, TYPE C	8.00	EACH
0116	801-03291	CONSTRUCTION SIGN, TYPE D	6.00	EACH
0117	801-04308	ROAD CLOSURE SIGN ASSEMBLY	13.00	EACH
0118	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	31011.00	LFT
0119	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	6549.00	LFT
0120	801-06625	DETOUR ROUTE MARKER ASSEMBLY	12.00	EACH
0121	801-06640	CONSTRUCTION SIGN, TYPE A	151.00	EACH
0122	801-06645	CONSTRUCTION SIGN, TYPE B	30.00	EACH
0123	801-06710	FLASHING ARROW SIGN	450.00	DAY
0124	801-06775	MAINTAINING TRAFFIC	1.00	LS
0125	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	4.00	EACH
0126	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	4.00	EACH
0127	801-07118	BARRICADE, TYPE III-A	156.00	LFT
0128	801-07119	BARRICADE, TYPE III-B	660.00	LFT
0129	801-07606	TEMPORARY CROSSOVER DRAINAGE PIPE	660.00	LFT
0130	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	2250.00	LFT
0131	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2388.00	LFT
0132	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	590.00	LFT
0133	801-12081	PORTABLE SIGNAL	1.00	LS
0134	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	20.00	EACH
0135	801-52817	TEMPORARY CROSSOVER, TYPE B	2.00	EACH
0136	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	23.00	LFT
0137	802-07060	SIGN, SHEET, RELOCATE	3.00	EACH
0138	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	920.00	LFT
0139	805-78785	SIGNAL DETECTOR HOUSING	2.00	EACH
0140	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	320.00	LFT
0141	808-06716	LINE, REMOVE	11585.00	LFT
0142	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	360.00	LFT

0143	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	180.00	LFT
0144	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	180.00	LFT
0145	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	2404.00	LFT
0146	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	26.00	LFT
0147	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	1.00	EACH
0148	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	915.00	LFT
0149	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	195.00	LFT
0150	808-10077	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, LANE INDICATION ARROW	1.00	EACH
0151	808-12032	GROOVING FOR PAVEMENT MARKINGS	5340.00	LFT
0152	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	1826.00	LFT
0153	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	6.00	EACH
0154	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	6.00	EACH

Call: 315

Contract: B -42952-A

Section No.: 1            SMALL STRUCTURE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0011	203-02000		EXCAVATION, COMMON	5.00	CYS
0012	205-11626		PUMP AROUND	2.00	EACH
0013	205-12108		STORMWATER MANAGEMENT BUDGET	7097.00	DOL
0014	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0015	207-09935		SUBGRADE TREATMENT, TYPE IC	92.00	SYS
0016	211-02050		B BORROW	5.00	CYS
0017	211-09265		STRUCTURE BACKFILL, TYPE 2	200.00	CYS
0018	214-12239		GEOTEXTILE FOR PAVEMENT, TYPE 2B	92.00	SYS
0019	301-12233		COMPACTED AGGREGATE, NO. 8	2.00	CYS
0020	303-01180		COMPACTED AGGREGATE, NO. 53	5.00	TON
0021	306-08034		MILLING, ASPHALT, 1 1/2 IN.	355.00	SYS
0022	401-07328		QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	36.00	TON
0023	401-07398		QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	12.00	TON
0024	401-07408		QC/QA-HMA, 3, 64, BASE, 25.0 mm	36.00	TON
0025	401-10258		JOINT ADHESIVE, SURFACE	378.00	LFT
0026	401-10259		JOINT ADHESIVE, INTERMEDIATE	69.00	LFT
0027	401-11785		LIQUID ASPHALT SEALANT	378.00	LFT
0028	406-05521		ASPHALT FOR TACK COAT	596.00	SYS
0029	606-12400		MILLED HMA CORRUGATIONS, SINUSOIDAL	315.00	LFT
0030	616-05688		RIPRAP, CLASS 1	10.00	TON
0031	616-12246		GEOTEXTILE FOR RIPRAP, TYPE 1A	20.00	SYS

0032	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0033	621-06560	MULCHED SEEDING, TYPE U	542.00 SYS
0034	628-09403	FIELD OFFICE, TYPE C	3.00 MOS
0035	715-05129	PIPE, TYPE 1, CIRCULAR, DIAMETER 54 IN.	81.00 LFT
0036	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.00 EACH
0037	801-06625	DETOUR ROUTE MARKER ASSEMBLY	44.00 EACH
0038	801-06640	CONSTRUCTION SIGN, TYPE A	12.00 EACH
0039	801-06775	MAINTAINING TRAFFIC	1.00 LS
0040	801-07118	BARRICADE, TYPE III-A	48.00 LFT
0041	801-07119	BARRICADE, TYPE III-B	120.00 LFT
0042	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00 EACH
0043	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	252.00 LFT
0044	808-12032	GROOVING FOR PAVEMENT MARKINGS	284.00 LFT
0045	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	32.00 LFT
0046	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2.00 EACH
0047	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2.00 EACH



Call: 321

Contract: B -43346-A

Section No.: 1 BRIDGE DECK OVERLAY

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441		QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463		PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0013	202-02240		PAVEMENT REMOVAL	6131.00	SYS
0014	202-02637		PIPE ABANDON AND GROUT FILL	114.00	LFT
0015	202-12835		SOUND BARRIER, REMOVE	726.00	SFT
0016	202-51328		PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0017	202-51328		PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0018	202-51328		PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0019	202-51368		SLOPEWALL, REMOVE	92.00	SYS
0020	202-91385		INLET, REMOVE	2.00	EACH
0021	202-94954		BARRIER WALL, CONCRETE, REMOVE	501.00	LFT
0022	203-02000		EXCAVATION, COMMON	3662.00	CYS
0023	203-08607		LINEAR GRADING	951.00	LFT
0024	205-12108		STORMWATER MANAGEMENT BUDGET	30518.00	DOL
0025	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0026	206-51230		EXCAVATION, FOUNDATION, UNCLASSIFIED	225.00	CYS
0027	207-08264		SUBGRADE TREATMENT, TYPE II	1242.00	SYS
0028	207-09935		SUBGRADE TREATMENT, TYPE IC	6872.00	SYS
0029	211-06467		AGGREGATE FOR END BENT BACKFILL	218.00	CYS
0030	213-09269		FLOWABLE BACKFILL, NON-REMOVABLE	20.00	CYS
0031	214-12239		GEOTEXTILE FOR PAVEMENT, TYPE 2B	6872.00	SYS

0032	301-12231	COMPACTED AGGREGATE, NO. 2	8.00	CYS
0033	302-06464	SUBBASE FOR PCCP	1610.00	CYS
0034	303-01180	COMPACTED AGGREGATE, NO. 53	340.00	TON
0035	304-07493	WIDENING WITH HMA, TYPE B	581.00	TON
0036	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	103.00	TON
0037	406-05521	ASPHALT FOR TACK COAT	2484.00	SYS
0038	502-06329	PCCP, 12 IN.	2673.00	SYS
0039	503-03489	RETROFITTED TIE BARS	568.00	EACH
0040	503-05240	D-1 CONTRACTION JOINT	2580.00	LFT
0041	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT, 12 IN.	2429.00	SYS
0042	503-12478	TERMINAL JOINT, TYPE PCCP	546.00	LFT
0043	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	546.00	LFT
0044	601-02241	GUARDRAIL, REMOVE	900.00	LFT
0045	601-06035	GUARDRAIL, RESET	569.00	LFT
0046	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	288.00	LFT
0047	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	7.00	EACH
0048	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	8.00	EACH
0049	601-12294	GUARDRAIL, MGS W-BEAM, CABLE TERMINAL ANCHOR	1.00	EACH
0050	602-01064	CONCRETE BARRIER	142.00	LFT
0051	602-06729	BARRIER DELINEATOR	39.00	EACH
0052	602-11938	CONCRETE BARRIER, MODIFIED SECTION	106.10	CYS
0053	603-06065	FENCE, CHAIN LINK, RESET	130.00	LFT
0054	605-06250	CENTER CURB, C CONCRETE	6.00	SYS
0055	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	1463.00	SYS
0056	616-06405	RIPRAP, REVETMENT	256.00	TON
0057	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	471.00	SYS
0058	616-51367	SLOPEWALL, CONCRETE, 4 IN.	92.00	SYS
0059	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0060	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0061	619-51860	COAT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0062	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0063	621-06560	MULCHED SEEDING, TYPE U	1846.00	SYS
0064	621-06574	SODDING	319.00	SYS
0065	628-12683	FIELD OFFICE, TYPE D	12.00	MOS
0066	703-06029	REINFORCING BARS, EPOXY COATED	128278.00	LBS
0067	703-96512	BAR SPLICE	52.00	EACH
0068	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	1036.00	EACH

0069	704-51002	CONCRETE, C, SUPERSTRUCTURE	276.10	CYS
0070	706-11600	RAILING, CONCRETE TYPE FC	3.80	CYS
0071	706-11601	RAILING, CONCRETE TYPE FT	1.80	CYS
0072	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	4.00	ACH
0073	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	4.00	ACH
0074	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFT	4.00	ACH
0075	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0076	709-51821	SURFACE SEAL	1.00	LS
0077	709-51821	SURFACE SEAL	1.00	LS
0078	709-51821	SURFACE SEAL	1.00	LS
0079	710-09158	PATCHING CONCRETE STRUCTURES	731.00	SFT
0080	711-51038	STRUCTURAL STEEL	1.00	LS
0081	711-51864	DRILLED HOLE	128.00	ACH
0082	711-51878	JACKING AND SUPPORTING GIRDERS	1.00	LS
0083	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	114.00	LFT
0084	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	481.00	LFT
0085	715-09064	VIDEO INSPECTION FOR PIPE	114.00	LFT
0086	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	ACH
0087	716-07630	PIPE INSTALLATION, TRENCHLESS, 12 IN.	114.00	LFT
0088	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	276.00	SYS
0089	718-12306	GEOTEXTILE FOR UNDERDRAINS, TYPE 1B	314.00	SYS
0090	720-01355	INLET, CLEAN EXISTING	2.00	ACH
0091	720-09079	INLET, TYPE HA5, MODIFIED	1.00	ACH
0092	720-12797	CASTING, INLET, ADJUST TO GRADE	2.00	ACH
0093	720-44030	CASTING, TYPE 5, FURNISH AND ADJUST TO GRADE	1.00	ACH
0094	722-01066	HYDRODEMOLITION	4843.00	SYS
0095	722-12380	BRIDGE DECK OVERLAY BUDGET	76130.00	DOL
0096	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	4824.00	SYS
0097	722-12732	LONGITUDINAL GROOVING	6476.00	SYS
0098	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	1750.00	SFT
0099	722-51874	OVERLAY DAM	572.00	SFT
0100	724-12773	BRIDGE EXPANSION JOINT, TYPE PCF	516.00	LFT
0101	724-12776	BRIDGE EXPANSION JOINT, TYPE PCF, REPLACE	182.00	LFT
0102	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	53159.00	LFT
0103	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	128.00	LFT
0104	801-06640	CONSTRUCTION SIGN, TYPE A	131.00	ACH
0105	801-06645	CONSTRUCTION SIGN, TYPE B	28.00	ACH

0106	801-06710	FLASHING ARROW SIGN	380.00	DAY
0107	801-06775	MAINTAINING TRAFFIC	1.00	LS
0108	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	8.00	EACH
0109	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0110	801-07119	BARRICADE, TYPE III-B	48.00	LFT
0111	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	920.00	LFT
0112	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	4350.00	LFT
0113	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	5.00	EACH
0114	801-11990	TEMPORARY CURB RAMP	8.00	EACH
0115	801-12324	LAW ENFORCEMENT OFFICER	672.00	HRS
0116	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	18.00	EACH
0117	801-12956	TEMPORARY PAVEMENT MARKING, REMOVABLE, 10 IN.	508.00	LFT
0118	801-97643	TEMPORARY BUZZ STRIPS	288.00	LFT
0119	802-04893	REFERENCE POST	6.00	EACH
0120	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	84.00	LFT
0121	805-78785	SIGNAL DETECTOR HOUSING	1.00	EACH
0122	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	84.00	LFT
0123	808-06716	LINE, REMOVE	29505.00	LFT
0124	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	14009.00	LFT
0125	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	13973.00	LFT
0126	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	4048.00	LFT
0127	808-12032	GROOVING FOR PAVEMENT MARKINGS	29566.00	LFT
0128	808-12781	LINE, MULTI-COMPONENT, SOLID, WHITE, 10 IN.	890.00	LFT
0129	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	20.00	EACH
0130	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	16.00	EACH

Call: 321

Contract: B -43346-A

Section No.: 2 LATEX MODIFIED CONCRETE OVERLAY OPTION

**Line**

Item No	Item Code	Description	Quantity	Unit
0131	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	5053.00	SYS

Call: 321

Contract: B -43346-A

Section No.: 3            SILICA FUME MODIFIED CONCRETE OVERLAY OPTION

**Line**

**Item No Item Code Description**

**Quantity Unit**

0132    722-01061    BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

5053.00    SYS

Call: 331

Contract: B -43415-A

Section No.: 1 BRIDGE DECK OVERLAY

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463		PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-01015		CLEARING AND GRUBBING	1.00	LS
0012	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0013	202-02240		PAVEMENT REMOVAL	751.00	SYS
0014	202-51328		PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0015	202-51328		PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0016	202-51328		PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0017	202-51328		PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0018	202-62420		BRIDGE RAILING, REMOVE	272.00	LFT
0019	202-93741		GUARDRAIL END TREATMENT, REMOVE	4.00	EACH
0020	203-02000		EXCAVATION, COMMON	796.00	CYS
0021	203-02070		BORROW	93.00	CYS
0022	203-08607		LINEAR GRADING	1631.00	LFT
0023	205-11626		PUMP AROUND	1.00	EACH
0024	205-12108		STORMWATER MANAGEMENT BUDGET	61001.00	DOL
0025	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0026	206-51220		EXCAVATION, WET	240.00	CYS
0027	206-51235		COFFERDAM	1.00	LS
0028	207-08264		SUBGRADE TREATMENT, TYPE II	178.00	SYS
0029	207-09935		SUBGRADE TREATMENT, TYPE IC	2737.00	SYS
0030	211-06467		AGGREGATE FOR END BENT BACKFILL	24.00	CYS
0031	211-09265		STRUCTURE BACKFILL, TYPE 2	8.00	CYS

0032	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	4.00	EACH
0033	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	81.00	CYS
0034	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	2737.00	SYS
0035	301-12234	COMPACTED AGGREGATE, NO. 53	266.00	CYS
0036	302-06464	SUBBASE FOR PCCP	219.00	CYS
0037	303-01180	COMPACTED AGGREGATE, NO. 53	242.00	TON
0038	303-07449	COMPACTED AGGREGATE, NO. 73	68.00	TON
0039	304-07493	WIDENING WITH HMA, TYPE B	110.00	TON
0040	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	42.00	TON
0041	304-12626	HMA PATCHING, PARTIAL DEPTH, TYPE C	74.00	TON
0042	306-08034	MILLING, ASPHALT, 1 1/2 IN.	958.00	SYS
0043	306-08043	MILLING, TRANSITION	2379.00	SYS
0044	306-11553	MILLING, ASPHALT, 3/4 IN.	49.00	SYS
0045	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	307.00	TON
0046	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	162.00	TON
0047	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	707.00	TON
0048	401-10258	JOINT ADHESIVE, SURFACE	3902.00	LFT
0049	401-10259	JOINT ADHESIVE, INTERMEDIATE	927.00	LFT
0050	401-11785	LIQUID ASPHALT SEALANT	3902.00	LFT
0051	406-05520	ASPHALT FOR TACK COAT	5.00	TON
0052	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	3.00	TON
0053	503-12477	TERMINAL JOINT, TYPE HMA	311.00	LFT
0054	601-01522	GUARDRAIL TRANSITION, TYPE TGB	4.00	EACH
0055	601-01700	GUARDRAIL TERMINAL SYSTEM, W-BEAM CURVED, TYPE 1	5.00	EACH
0056	601-01701	GUARDRAIL TERMINAL SYSTEM, W-BEAM CURVED, TYPE 2	1.00	EACH
0057	601-02241	GUARDRAIL, REMOVE	2419.00	LFT
0058	601-06035	GUARDRAIL, RESET	237.00	LFT
0059	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	751.00	LFT
0060	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	2.00	EACH
0061	601-12291	GUARDRAIL TRANSITION, MGS WITH CURB	6.00	EACH
0062	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	6.00	EACH
0063	601-94689	GUARDRAIL END TREATMENT, TYPE OS	10.00	EACH
0064	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	82.00	LFT
0065	602-06729	BARRIER DELINEATOR	16.00	EACH
0066	605-05523	CURB, HMA	78.00	LFT
0067	605-06105	CURB, INTEGRAL CONCRETE, MODIFIED	235.00	LFT
0068	605-06145	CURB AND GUTTER, TYPE B, CONCRETE	203.00	LFT

0069	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	210.00	LFT
0070	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	1000.00	LFT
0071	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	888.00	SYS
0072	610-07487	HMA FOR APPROACHES, TYPE B	8.00	TON
0073	615-06515	MONUMENT, TYPE D	1.00	≡ACH
0074	615-06535	BENCHMARK POST, RESET	1.00	≡ACH
0075	616-05688	RIPRAP, CLASS 1	300.00	TON
0076	616-06405	RIPRAP, REVETMENT	1177.00	TON
0077	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	2020.00	SYS
0078	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	62.00	SYS
0079	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	409.00	SYS
0080	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	7.00	≡ACH
0081	621-03909	SEED MIXTURE, NATIVE	16.00	LBS
0082	621-06559	MULCHED SEEDING, TYPE R	744.00	SYS
0083	621-06565	MULCHING MATERIAL	2.00	TON
0084	621-06567	WATER	2.00	KGAL
0085	621-06574	SODDING	355.00	SYS
0086	621-09815	ARTICULATED CONCRETE BLOCK	250.00	SYS
0087	621-12612	SEED MIXTURE, FLOODPLAIN	7.00	LBS
0088	628-09403	FIELD OFFICE, TYPE C	12.00	MOS
0089	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	≡ACH
0090	701-93790	CLEAN AND EPOXY COAT EXISTING PILES	1.00	LS
0091	701-93790	CLEAN AND EPOXY COAT EXISTING PILES	1.00	LS
0092	702-51005	CONCRETE, A, SUBSTRUCTURE	10.60	CYS
0093	702-51863	FIELD DRILLED HOLE IN CONCRETE	738.00	≡ACH
0094	703-06029	REINFORCING BARS, EPOXY COATED	135260.00	LBS
0095	703-08247	EMBEDDED GALVANIC ANODE	448.00	≡ACH
0096	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	340.00	≡ACH
0097	704-51002	CONCRETE, C, SUPERSTRUCTURE	242.30	CYS
0098	706-11600	RAILING, CONCRETE TYPE FC	37.50	CYS
0099	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	12.00	≡ACH
0100	706-51020	RAILING, CONCRETE TYPE C	1.60	CYS
0101	707-05982	STRUCTURAL MEMBER, CONCRETE, I-BEAM, 28 IN. X 12 IN.	1068.00	LFT
0102	709-51821	SURFACE SEAL	1.00	LS
0103	709-51821	SURFACE SEAL	1.00	LS
0104	709-51821	SURFACE SEAL	1.00	LS
0105	709-51821	SURFACE SEAL	1.00	LS



0106	709-51821	SURFACE SEAL	1.00	LS
0107	709-51821	SURFACE SEAL	1.00	LS
0108	710-09158	PATCHING CONCRETE STRUCTURES	256.00	SFT
0109	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	45.00	LFT
0110	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	56.00	LFT
0111	715-06566	PIPE EXTENSION, CIRCULAR, DIAMETER 6 IN.	36.00	LFT
0112	718-06526	HMA FOR UNDERDRAINS	5.00	TON
0113	718-06529	OUTLET PROTECTOR, TYPE 2	4.00	EACH
0114	718-09979	UNDERDRAIN OUTLET CLEANING	5.00	EACH
0115	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	86.00	SYS
0116	718-52610	AGGREGATE FOR UNDERDRAINS	2.00	CYS
0117	722-01066	HYDRODEMOLITION	902.00	SYS
0118	722-12380	BRIDGE DECK OVERLAY BUDGET	17690.00	DOL
0119	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	902.00	SYS
0120	722-12732	LONGITUDINAL GROOVING	2483.00	SYS
0121	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	424.00	SFT
0122	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	950.00	SYS
0123	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	499.00	SFT
0124	722-51874	OVERLAY DAM	76.00	SFT
0125	724-03855	EXPANSION JOINT SLIDING PLATE	6.00	LFT
0126	727-90308	EPOXY INJECTION, CRACK PREPARATION	20.00	LFT
0127	727-90309	EPOXY INJECTION, EPOXY MATERIAL	1.00	GAL
0128	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0129	731-05947	CONCRETE COPING	50.00	LFT
0130	731-12677	SOIL NAILED WALL REINFORCEMENT	8.00	EACH
0131	731-12679	MSE PANEL JOINT SEALING	50.00	LFT
0132	731-93945	FACE PANELS, CONCRETE	120.00	SFT
0133	738-12855	WARRANTED POLYMER OVERLAY, BRIDGE DECK	1020.00	SYS
0134	738-12856	POLYMER OVERLAY, OTHER CONCRETE SURFACE	522.00	SYS
0135	801-03291	CONSTRUCTION SIGN, TYPE D	6.00	EACH
0136	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0137	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4884.00	LFT
0138	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	4168.00	LFT
0139	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	27959.00	LFT
0140	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	142.00	LFT
0141	801-06625	DETOUR ROUTE MARKER ASSEMBLY	31.00	EACH
0142	801-06640	CONSTRUCTION SIGN, TYPE A	169.00	EACH

0143	801-06645	CONSTRUCTION SIGN, TYPE B	11.00	EACH
0144	801-06775	MAINTAINING TRAFFIC	1.00	LS
0145	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00	EACH
0146	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	6.00	EACH
0147	801-07118	BARRICADE, TYPE III-A	144.00	LFT
0148	801-07119	BARRICADE, TYPE III-B	288.00	LFT
0149	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	176.00	LFT
0150	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1765.00	LFT
0151	801-12042	TRUCK MOUNTED ATTENUATOR	28.00	DAY
0152	801-12081	PORTABLE SIGNAL	1.00	LS
0153	801-12482	DRIVEWAY ASSISTANCE DEVICE	6.00	EACH
0154	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	12.00	EACH
0155	802-02475	SIGN, PANEL, RELOCATE	1.00	EACH
0156	802-04893	REFERENCE POST	5.00	EACH
0157	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	63.00	LFT
0158	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	45.00	LFT
0159	802-05705	SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	25.00	LFT
0160	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH
0161	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	18.00	SFT
0162	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	27.00	SFT
0163	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	20.00	SFT
0164	808-06716	LINE, REMOVE	4995.00	LFT
0165	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	3694.00	LFT
0166	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	2636.00	LFT
0167	808-12032	GROOVING FOR PAVEMENT MARKINGS	4603.00	LFT
0168	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	219.00	LFT
0169	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	1696.00	LFT
0170	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	696.00	LFT
0171	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	15.00	EACH

Call: 341

Contract: B -43433-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463		PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02240		PAVEMENT REMOVAL	758.00	SYS
0013	203-02000		EXCAVATION, COMMON	465.00	CYS
0014	203-08607		LINEAR GRADING	556.00	LFT
0015	205-12108		STORMWATER MANAGEMENT BUDGET	39945.00	DOL
0016	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	206-51230		EXCAVATION, FOUNDATION, UNCLASSIFIED	27.00	CYS
0018	206-51235		COFFERDAM	1.00	LS
0019	206-51235		COFFERDAM	1.00	LS
0020	206-51235		COFFERDAM	1.00	LS
0021	207-09935		SUBGRADE TREATMENT, TYPE IC	666.00	SYS
0022	211-06467		AGGREGATE FOR END BENT BACKFILL	7.00	CYS
0023	211-09268		STRUCTURE BACKFILL, TYPE 5	30.00	CYS
0024	214-12239		GEOTEXTILE FOR PAVEMENT, TYPE 2B	1074.00	SYS
0025	302-06464		SUBBASE FOR PCCP	194.00	CYS
0026	303-01180		COMPACTED AGGREGATE, NO. 53	378.00	TON
0027	306-08034		MILLING, ASPHALT, 1 1/2 IN.	350.00	SYS
0028	306-08043		MILLING, TRANSITION	1817.00	SYS
0029	306-08432		MILLING, APPROACH	497.00	SYS
0030	401-07322		QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	30.00	TON
0031	401-07328		QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	172.00	TON

0032	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	30.00 TON
0033	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	94.00 TON
0034	401-10258	JOINT ADHESIVE, SURFACE	1672.00 LFT
0035	401-10259	JOINT ADHESIVE, INTERMEDIATE	120.00 LFT
0036	401-11785	LIQUID ASPHALT SEALANT	1732.00 LFT
0037	406-05521	ASPHALT FOR TACK COAT	3291.00 SYS
0038	503-03489	RETROFITTED TIE BARS	60.00 EACH
0039	503-05240	D-1 CONTRACTION JOINT	60.00 LFT
0040	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT, 12 IN.	274.00 SYS
0041	503-12478	TERMINAL JOINT, TYPE PCCP	60.00 LFT
0042	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	48.00 LFT
0043	601-01128	GUARDRAIL TRANSITION, TYPE WGB	1.00 EACH
0044	601-01626	GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, TYPE 2	1.00 EACH
0045	601-01846	GUARDRAIL TERMINAL SYSTEM, W-BEAM CURVED, TYPE 3	1.00 EACH
0046	601-02241	GUARDRAIL, REMOVE	510.00 LFT
0047	601-06035	GUARDRAIL, RESET	374.00 LFT
0048	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	50.00 LFT
0049	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	4.00 EACH
0050	601-12291	GUARDRAIL TRANSITION, MGS WITH CURB	4.00 EACH
0051	601-94689	GUARDRAIL END TREATMENT, TYPE OS	1.00 EACH
0052	605-06121	CURB, CONCRETE, TYPE B	432.00 LFT
0053	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	300.00 LFT
0054	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	550.00 SYS
0055	610-07488	HMA FOR APPROACHES, TYPE C	42.00 TON
0056	616-02281	GROUT FOR RIPRAP	61.00 CYS
0057	616-06405	RIPRAP, REVETMENT	377.00 TON
0058	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	538.00 SYS
0059	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00 LS
0060	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00 LS
0061	619-12507	CLEAN AND COAT STEEL PILING, BRIDGE NO.	1.00 LS
0062	619-12507	CLEAN AND COAT STEEL PILING, BRIDGE NO.	1.00 LS
0063	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00 EACH
0064	621-06559	MULCHED SEEDING, TYPE R	1442.00 SYS
0065	628-09403	FIELD OFFICE, TYPE C	11.00 MOS
0066	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0067	702-51863	FIELD DRILLED HOLE IN CONCRETE	6.00 EACH
0068	703-06029	REINFORCING BARS, EPOXY COATED	29128.00 LBS

0069	703-08247	EMBEDDED GALVANIC ANODE	70.00	ACH
0070	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	1.00	ACH
0071	709-51821	SURFACE SEAL	1.00	LS
0072	709-51821	SURFACE SEAL	1.00	LS
0073	709-51821	SURFACE SEAL	1.00	LS
0074	709-51821	SURFACE SEAL	1.00	LS
0075	710-09158	PATCHING CONCRETE STRUCTURES	825.00	SFT
0076	715-04837	PLUG	50.00	ACH
0077	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	22.00	ACH
0078	722-01066	HYDRODEMOLITION	960.00	SYS
0079	722-12380	BRIDGE DECK OVERLAY BUDGET	18750.00	DOL
0080	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	202.00	SYS
0081	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	402.00	SYS
0082	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	356.00	SYS
0083	722-12732	LONGITUDINAL GROOVING	1499.00	SYS
0084	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	200.00	SFT
0085	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	960.00	SYS
0086	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	45.00	SFT
0087	722-51874	OVERLAY DAM	279.00	SFT
0088	738-12855	WARRANTED POLYMER OVERLAY, BRIDGE DECK	238.00	SYS
0089	801-04308	ROAD CLOSURE SIGN ASSEMBLY	16.00	ACH
0090	801-06625	DETOUR ROUTE MARKER ASSEMBLY	201.00	ACH
0091	801-06640	CONSTRUCTION SIGN, TYPE A	82.00	ACH
0092	801-06775	MAINTAINING TRAFFIC	1.00	LS
0093	801-07118	BARRICADE, TYPE III-A	128.00	LFT
0094	801-07119	BARRICADE, TYPE III-B	128.00	LFT
0095	802-04893	REFERENCE POST	8.00	ACH
0096	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	202.00	LFT
0097	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	64.00	LFT
0098	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	22.00	ACH
0099	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	49.00	SFT
0100	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	69.00	SFT
0101	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	1558.00	LFT
0102	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	422.00	LFT
0103	808-12032	GROOVING FOR PAVEMENT MARKINGS	1220.00	LFT
0104	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	70.00	LFT
0105	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	205.00	LFT

0106	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	418.00	LFT
0107	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2.00	EACH

Call: 345

Contract: B -43617-B

Section No.: 1 BRIDGE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358		INSPECTION HOLE, DEEPER THAN 3 FT	2.00	EACH
0003	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360		CONTRACT LIENS	1.00	DOL
0005	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09377		QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02928		CATCH BASIN, REMOVE	1.00	EACH
0013	202-51330		PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0014	202-96133		PIPE, REMOVE	57.00	LFT
0015	203-02000		EXCAVATION, COMMON	1575.00	CYS
0016	203-51223		EXCAVATION, WATERWAY	230.00	CYS
0017	205-11626		PUMP AROUND	1.00	EACH
0018	205-12108		STORMWATER MANAGEMENT BUDGET	10011.30	DOL
0019	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	205-12618		SWQCP PREPARATION	1.00	LS
0021	207-08266		SUBGRADE TREATMENT, TYPE III	745.00	SYS
0022	207-09935		SUBGRADE TREATMENT, TYPE IC	1067.00	SYS
0023	211-09264		STRUCTURE BACKFILL, TYPE 1	120.00	CYS
0024	211-09265		STRUCTURE BACKFILL, TYPE 2	1195.00	CYS
0025	211-09266		STRUCTURE BACKFILL, TYPE 3	1465.00	CYS
0026	211-09268		STRUCTURE BACKFILL, TYPE 5	5.00	CYS
0027	303-01180		COMPACTED AGGREGATE, NO. 53	135.00	TON
0028	304-12625		HMA PATCHING, FULL DEPTH, TYPE C	26.00	TON
0029	306-08034		MILLING, ASPHALT, 1 1/2 IN.	1502.00	SYS
0030	401-07339		QC/QA-HMA, 2, 64, SURFACE, 12.5 mm	162.00	TON
0031	401-07390		QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	41.00	TON

0032	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	65.00 TON
0033	401-10258	JOINT ADHESIVE, SURFACE	660.00 LFT
0034	401-10259	JOINT ADHESIVE, INTERMEDIATE	97.00 LFT
0035	401-11785	LIQUID ASPHALT SEALANT	660.00 LFT
0036	406-05520	ASPHALT FOR TACK COAT	1.00 TON
0037	502-11564	PCCP, 7 IN.	95.00 SYS
0038	601-02241	GUARDRAIL, REMOVE	133.00 LFT
0039	601-03667	RAILING ORNAMENTAL	595.00 LFT
0040	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	488.00 LFT
0041	601-94689	GUARDRAIL END TREATMENT, TYPE OS	4.00 EACH
0042	604-06070	SIDEWALK, CONCRETE	497.00 SYS
0043	605-06140	CURB AND GUTTER, CONCRETE	412.00 LFT
0044	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	89.00 LFT
0045	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	873.00 LFT
0046	610-08446	PCCP FOR APPROACHES, 6 IN.	70.00 SYS
0047	611-08232	MAILBOX ASSEMBLY, RESET, SINGLE	2.00 EACH
0048	615-06490	RIGHT-OF-WAY MARKER	4.00 EACH
0049	615-06505	MONUMENT, TYPE B	4.00 EACH
0050	615-06530	BENCHMARK POST	1.00 EACH
0051	616-06405	RIPRAP, REVETMENT	386.00 TON
0052	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	389.00 SYS
0053	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0054	621-06560	MULCHED SEEDING, TYPE U	2234.00 SYS
0055	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	393.00 LFT
0056	715-05203	PIPE, TYPE 4, CIRCULAR, DIAMETER 4 IN.	516.00 LFT
0057	715-09064	VIDEO INSPECTION FOR PIPE	393.00 LFT
0058	715-46000	PIPE END SECTION, DIAMETER 12 IN.	10.00 EACH
0059	720-01091	MANHOLE, TYPE C10, MODIFIED	4.00 EACH
0060	720-45045	INLET, TYPE J10	6.00 EACH
0061	720-45055	INLET, TYPE M10	5.00 EACH
0062	720-45235	CATCH BASIN, TYPE E7	1.00 EACH
0063	723-11205	STRUCTURE, REINFORCED CONCRETE, THREE-SIDED SECTIONS, 504 IN. X 256 IN.	66.00 LFT
0064	732-11811	MODULAR BLOCK WALL ERECTION	4793.00 SFT
0065	732-11812	MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	4793.00 SFT
0066	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00 EACH
0067	801-06625	DETOUR ROUTE MARKER ASSEMBLY	20.00 EACH
0068	801-06640	CONSTRUCTION SIGN, TYPE A	6.00 EACH



0069	801-06645	CONSTRUCTION SIGN, TYPE B	3.00	EACH
0070	801-06775	MAINTAINING TRAFFIC	1.00	LS
0071	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0072	801-07119	BARRICADE, TYPE III-B	72.00	LFT
0073	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	20.00	LFT
0074	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	2.00	EACH
0075	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	5.00	SFT
0076	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	9.00	SFT
0077	808-12032	GROOVING FOR PAVEMENT MARKINGS	2744.00	LFT
0078	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	1372.00	LFT
0079	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	1372.00	LFT

Call: 351

Contract: B -43833-A

Section No.: 1 BRIDGE PAINTING

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0009	201-90788		DEBRIS, REMOVE, STRUCTURE NO.	1.00	LS
0010	205-12108		STORMWATER MANAGEMENT BUDGET	12094.00	DOL
0011	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0012	206-51235		COFFERDAM	1.00	LS
0013	303-01180		COMPACTED AGGREGATE, NO. 53	29.00	TON
0014	616-05688		RIPRAP, CLASS 1	435.00	TON
0015	616-12246		GEOTEXTILE FOR RIPRAP, TYPE 1A	510.00	SYS
0016	619-11052		CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0017	619-12459		DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0018	619-51859		COAT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0019	621-01004		MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0020	621-06559		MULCHED SEEDING, TYPE R	635.00	SYS
0021	621-12612		SEED MIXTURE, FLOODPLAIN	2.00	LBS
0022	628-09409		MOBILE INTERNET SERVICE	8.00	MOS
0023	628-11729		CELLULAR TELEPHONE, TYPE A	1.00	EACH
0024	628-11731		CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0025	628-11976		COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0026	628-11977		COMPUTER SYSTEM	1.00	EACH
0027	628-12683		FIELD OFFICE, TYPE D	8.00	MOS
0028	628-12923		CELLULAR TELEPHONE SERVICE, UNLIMITED MINUTES	8.00	MOS
0029	710-09158		PATCHING CONCRETE STRUCTURES	128.00	SFT
0030	715-01354		CLEAN EXISTING PIPE	60.00	LFT
0031	801-04308		ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH

0032	801-06625	DETOUR ROUTE MARKER ASSEMBLY	31.00	EACH
0033	801-06640	CONSTRUCTION SIGN, TYPE A	16.00	EACH
0034	801-06775	MAINTAINING TRAFFIC	1.00	LS
0035	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0036	801-07119	BARRICADE, TYPE III-B	120.00	LFT

Call: 361

Contract: B -44547-A

Section No.: 1 BRIDGE PAINTING

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463		PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	303-01180		COMPACTED AGGREGATE, NO. 53	24.00	TON
0009	619-11052		CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0010	619-11052		CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0011	619-11052		CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0012	619-12459		DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0013	619-12459		DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0014	619-12459		DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0015	619-51859		COAT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0016	619-51859		COAT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0017	619-51859		COAT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0018	628-11976		COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0019	628-12683		FIELD OFFICE, TYPE D	8.00	MOS
0020	801-03291		CONSTRUCTION SIGN, TYPE D	2.00	EACH
0021	801-04308		ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0022	801-06209		TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	26633.00	LFT
0023	801-06218		TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	38.00	LFT
0024	801-06469		TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	5126.00	LFT
0025	801-06625		DETOUR ROUTE MARKER ASSEMBLY	8.00	EACH
0026	801-06640		CONSTRUCTION SIGN, TYPE A	153.00	EACH
0027	801-06645		CONSTRUCTION SIGN, TYPE B	4.00	EACH
0028	801-06710		FLASHING ARROW SIGN	91.00	DAY
0029	801-06775		MAINTAINING TRAFFIC	1.00	LS
0030	801-07024		ENERGY ABSORBING TERMINAL, CZ, TL-3	6.00	EACH
0031	801-07118		BARRICADE, TYPE III-A	85.00	LFT

0032	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	3720.00	LFT
0033	801-12031	TEMPORARY PORTABLE RUMBLE STRIPS	168.00	DAY
0034	801-12042	TRUCK MOUNTED ATTENUATOR	15.00	DAY
0035	801-12081	PORTABLE SIGNAL	1.00	LS
0036	801-12482	DRIVEWAY ASSISTANCE DEVICE	2.00	EACH
0037	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	16.00	EACH

Call: 401

Contract: M -45433-A

Section No.: 1 PAVEMENT PATCHING

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377		QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	202-02240		PAVEMENT REMOVAL	390.00	SYS
0011	202-90277		DETECTOR HOUSING, REMOVE	4.00	EACH
0012	207-08264		SUBGRADE TREATMENT, TYPE II	550.00	SYS
0013	214-11796		GEOGRID, TYPE IB	550.00	SYS
0014	214-12238		GEOTEXTILE FOR PAVEMENT, TYPE 2A	550.00	SYS
0015	304-12623		HMA PATCHING, FULL DEPTH, TYPE B	1303.00	TON
0016	304-12624		HMA PATCHING, PARTIAL DEPTH, TYPE B	670.00	TON
0017	401-10258		JOINT ADHESIVE, SURFACE	15032.00	LFT
0018	401-11785		LIQUID ASPHALT SEALANT	15032.00	LFT
0019	406-05520		ASPHALT FOR TACK COAT	4.60	TON
0020	720-44055		CASTING, TYPE 10, FURNISH AND ADJUST TO GRADE	2.00	EACH
0021	801-06640		CONSTRUCTION SIGN, TYPE A	53.00	EACH
0022	801-06775		MAINTAINING TRAFFIC	1.00	LS
0023	805-78470		SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	324.00	LFT
0024	805-78785		SIGNAL DETECTOR HOUSING	4.00	EACH
0025	805-78795		SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	96.00	LFT
0026	808-09381		RETRO-REFLECTIVITY TESTING	1.00	LS
0027	808-10047		TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 12 IN.	1014.00	LFT
0028	808-10049		LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	18834.00	LFT
0029	808-10051		TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	302.00	LFT
0030	808-10056		TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	2063.00	LFT
0031	808-10057		LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	24716.00	LFT

0032	808-12032	GROOVING FOR PAVEMENT MARKINGS	44220.00	LFT
0033	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	670.00	LFT
0034	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	5.00	EACH
0035	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	5.00	EACH

Call: 511

Contract: T -42395-A

Section No.: 1            ACCESS CONTROL

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358		INSPECTION HOLE, DEEPER THAN 3 FT	5.00	EACH
0003	107-09367		INSPECTION HOLE, 3 FT DEEP OR LESS	5.00	EACH
0004	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360		CONTRACT LIENS	1.00	DOL
0006	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0007	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-09377		QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0010	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0011	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0012	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0013	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0014	202-02240		PAVEMENT REMOVAL	690.00	SYS
0015	202-02273		CENTER CURB, CONCRETE, REMOVE	1009.00	SYS
0016	202-02278		CURB, CONCRETE, REMOVE	4798.00	LFT
0017	202-02279		CURB AND GUTTER, REMOVE	4562.00	LFT
0018	202-02637		PIPE ABANDON AND GROUT FILL	257.00	LFT
0019	202-02928		CATCH BASIN, REMOVE	1.00	EACH
0020	202-06580		CONTAMINATED SOIL, REMOVE	879.00	CYS
0021	202-52710		SIDEWALK CONCRETE, REMOVE	831.00	SYS
0022	202-91385		INLET, REMOVE	20.00	EACH
0023	202-93047		MANHOLE, REMOVE	2.00	EACH
0024	202-96133		PIPE, REMOVE	211.00	LFT
0025	203-02000		EXCAVATION, COMMON	16695.00	CYS
0026	203-02070		BORROW	1135.00	CYS
0027	205-12108		STORMWATER MANAGEMENT BUDGET	28846.00	DOL
0028	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0029	205-12618		SWQCP PREPARATION	1.00	LS
0030	207-08264		SUBGRADE TREATMENT, TYPE II	3895.00	SYS
0031	207-09935		SUBGRADE TREATMENT, TYPE IC	10949.00	SYS



0032	211-09264	STRUCTURE BACKFILL, TYPE 1	655.00	CYS
0033	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	36.00	CYS
0034	214-11796	GEOGRID, TYPE IB	606.00	SYS
0035	214-12238	GEOTEXTILE FOR PAVEMENT, TYPE 2A	3749.00	SYS
0036	301-12232	COMPACTED AGGREGATE, NO. 5	625.00	CYS
0037	301-12234	COMPACTED AGGREGATE, NO. 53	580.00	CYS
0038	302-07455	DENSE GRADED SUBBASE	101.00	CYS
0039	304-07789	WIDENING WITH HMA, TYPE D	514.00	TON
0040	304-12627	HMA PATCHING, FULL DEPTH, TYPE D	572.00	TON
0041	306-08034	MILLING, ASPHALT, 1 1/2 IN.	24408.00	SYS
0042	306-11872	MILLING, PROFILE	2169.00	SYS
0043	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	2977.00	TON
0044	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	1217.00	TON
0045	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	6434.00	TON
0046	401-10258	JOINT ADHESIVE, SURFACE	16659.00	LFT
0047	401-10259	JOINT ADHESIVE, INTERMEDIATE	3314.00	LFT
0048	401-11785	LIQUID ASPHALT SEALANT	16659.00	LFT
0049	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0050	402-07787	HMA WEDGE AND LEVEL, TYPE D	160.00	TON
0051	402-10086	HMA FOR TEMPORARY PAVEMENT, TYPE C	1234.00	TON
0052	406-05520	ASPHALT FOR TACK COAT	14.00	TON
0053	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	100.00	TON
0054	502-11543	PCCP, 4 IN.	128.00	SYS
0055	604-06070	SIDEWALK, CONCRETE	1473.00	SYS
0056	604-08086	CURB RAMP, CONCRETE	251.00	SYS
0057	604-12083	DETECTABLE WARNING SURFACES	33.00	SYS
0058	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	3.00	SYS
0059	605-06120	CURB, CONCRETE	20076.00	LFT
0060	605-06240	CENTER CURB, A CONCRETE	320.00	SYS
0061	605-06255	CENTER CURB, D CONCRETE	1558.00	SYS
0062	605-09137	CURB, TURNOUT	14.00	LFT
0063	605-52807	CURB AND GUTTER, COMBINED	3806.00	LFT
0064	610-09108	PCCP FOR APPROACHES, 9 IN.	606.00	SYS
0065	615-06490	RIGHT-OF-WAY MARKER	19.00	EACH
0066	615-06505	MONUMENT, TYPE B	13.00	EACH
0067	615-06510	MONUMENT, TYPE C	2.00	EACH
0068	616-06405	RIPRAP, REVETMENT	37.00	TON

0069	616-06425	RIPRAP, GROUTED, 12 IN.	25.00	SYS
0070	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	30.00	SYS
0071	621-06560	MULCHED SEEDING, TYPE U	5275.00	SYS
0072	621-06567	WATER	78.00	KGAL
0073	621-06570	TOPSOIL	2685.00	CYS
0074	621-06574	SODDING	19325.00	SYS
0075	628-09403	FIELD OFFICE, TYPE C	24.00	MOS
0076	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0077	628-11977	COMPUTER SYSTEM	1.00	EACH
0078	629-12029	PLANT GROWTH LAYER	5275.00	SYS
0079	702-51863	FIELD DRILLED HOLE IN CONCRETE	12.00	EACH
0080	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	2286.00	LFT
0081	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	998.00	LFT
0082	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	368.00	LFT
0083	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	450.00	LFT
0084	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	6.00	TON
0085	715-09064	VIDEO INSPECTION FOR PIPE	1816.00	LFT
0086	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00	EACH
0087	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0088	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	1721.00	SYS
0089	718-52610	AGGREGATE FOR UNDERDRAINS	120.00	CYS
0090	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	3.00	EACH
0091	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	12.00	EACH
0092	720-45235	CATCH BASIN, TYPE E7	2.00	EACH
0093	720-45410	MANHOLE, TYPE C4	12.00	EACH
0094	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	3.00	EACH
0095	720-98174	INLET, TYPE B15	15.00	EACH
0096	720-98555	INLET, TYPE C15	11.00	EACH
0097	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00	EACH
0098	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	28789.00	LFT
0099	801-06625	DETOUR ROUTE MARKER ASSEMBLY	40.00	EACH
0100	801-06640	CONSTRUCTION SIGN, TYPE A	51.00	EACH
0101	801-06645	CONSTRUCTION SIGN, TYPE B	53.00	EACH
0102	801-06710	FLASHING ARROW SIGN	120.00	DAY
0103	801-06775	MAINTAINING TRAFFIC	1.00	LS
0104	801-07119	BARRICADE, TYPE III-B	70.00	LFT
0105	801-12042	TRUCK MOUNTED ATTENUATOR	20.00	DAY

0106	801-12324	LAW ENFORCEMENT OFFICER	1500.00	HRS
0107	801-12863	AUDIBLE INFORMATION DEVICE	21.00	EACH
0108	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	1428.00	LFT
0109	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	11.00	LFT
0110	802-05706	SIGN POST, SQUARE, TYPE 3, UNREINFORCED ANCHOR BASE	22.00	LFT
0111	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	109.00	EACH
0112	802-07060	SIGN, SHEET, RELOCATE	20.00	EACH
0113	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	1164.00	SFT
0114	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	353.00	SFT
0115	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	376.00	SFT
0116	802-74050	SIGN, OVERHEAD, REMOVE	31.00	EACH
0117	802-74070	OVERHEAD SIGN STRUCTURE, CABLE SPAN, REMOVE	6.00	EACH
0118	804-11920	DELINEATOR POST, FLEXIBLE, TYPE I	4.00	EACH
0119	804-97955	DELINEATOR POST, FLEXIBLE, RESET	26.00	EACH
0120	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	8.00	EACH
0121	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0122	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	21.00	EACH
0123	805-01842	HANDHOLE, SIGNAL, TYPE 1	31.00	EACH
0124	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0125	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	21.00	EACH
0126	805-02437	CONTROLLER, RELOCATE AND REWIRE	1.00	EACH
0127	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	22.00	EACH
0128	805-03980	EMERGENCY VEHICLE CONFIRMATION LIGHT KIT	24.00	EACH
0129	805-06742	SOLAR POWERED FLASHING BEACON ASSEMBLY	2.00	EACH
0130	805-08129	SIGNAL CABLE	1672.00	LFT
0131	805-08244	CELLULAR MODEM KIT	1.00	EACH
0132	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	2.00	EACH
0133	805-09540	LOOP DETECTOR RACK	5.00	EACH
0134	805-10234	CONTROLLER AND CABINET, TYPE R	2.00	EACH
0135	805-11759	GPS MAST MOUNT RADIO UNIT	12.00	EACH
0136	805-11814	CONDUIT, HDPE, 2 IN. SCHEDULE 40	4941.00	LFT
0137	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	2483.00	LFT
0138	805-11817	PEDESTRIAN PUSH BUTTON, APS	21.00	EACH
0139	805-11842	CONDUIT, HDPE, 3 IN. SCHEDULE 40	132.00	LFT
0140	805-12650	SIGNAL POLE, PEDESTAL, 5 FT	1.00	EACH
0141	805-12830	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 4 CHANNEL	6.00	EACH
0142	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	94.00	EACH

0143	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	2.00	EACH
0144	805-78225	TRAFFIC SIGNAL HEAD, NO. 4 SECTION, 12 IN.	18.00	EACH
0145	805-78415	SPAN, CATENARY, AND TETHER	20.00	EACH
0146	805-78420	DISCONNECT HANGER	35.00	EACH
0147	805-78445	SIGNAL SERVICE	4.00	EACH
0148	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	106.00	LFT
0149	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	10833.00	LFT
0150	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GAUGE	14573.00	LFT
0151	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	15539.00	LFT
0152	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	1177.00	LFT
0153	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	486.00	LFT
0154	805-78500	SIGNAL CABLE, CONTROL, COPPER, 11C/14 GAUGE	8614.00	LFT
0155	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	11948.00	LFT
0156	805-78785	SIGNAL DETECTOR HOUSING	24.00	EACH
0157	805-78790	LOOP DETECTOR DELAY AMPLIFIER, NONCOUNTING 4 CHANNEL	2.00	EACH
0158	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	3445.00	LFT
0159	805-78925	CONTROLLER CABINET FOUNDATION, TYPE P1	2.00	EACH
0160	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	21.00	EACH
0161	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	21.00	EACH
0162	807-02191	HANDHOLE, LIGHTING	12.00	EACH
0163	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	287.00	LFT
0164	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	2794.00	LFT
0165	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	21.00	EACH
0166	807-12398	LIGHT POLE, 40 FT E.M.H., 15 FT MAST ARM, ANCHOR BASE	15.00	EACH
0167	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE, WITH GROUNDING	21.00	EACH
0168	807-83502	LIGHT POLE, 30 FT E.M.H., 15 FT MAST ARM, ANCHOR BASE	6.00	EACH
0169	807-86810	SERVICE POINT, TYPE II	1.00	EACH
0170	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	2358.00	LFT
0171	807-86910	CONNECTOR KIT, UNFUSED	21.00	EACH
0172	807-86915	CONNECTOR KIT, FUSED	21.00	EACH
0173	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	36.00	EACH
0174	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	32.00	EACH
0175	807-86930	INSULATION LINK, NON-WATERPROOFED	42.00	EACH
0176	807-86935	INSULATION LINK, WATERPROOFED	48.00	EACH
0177	807-86950	SIGN, UNDERPASS, AND ROADWAY LIGHTING, LOCATION IDENTIFICATION	21.00	EACH
0178	807-86955	CABLE-DUCT MARKER	2.00	EACH
0179	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	287.00	LFT

0180	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	976.00	LFT
0181	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	8.00	SYS
0182	808-06368	TRANSVERSE MARKING, REMOVE	444.00	LFT
0183	808-06716	LINE, REMOVE	4382.00	LFT
0184	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0185	808-10118	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 24 IN.	72.00	LFT
0186	808-11960	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 24 IN.	144.00	LFT
0187	808-12032	GROOVING FOR PAVEMENT MARKINGS	47041.00	LFT
0188	808-12782	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 6 IN.	129.00	LFT
0189	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	793.00	LFT
0190	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	210.00	LFT
0191	808-75052	LINE, PREFORMED PLASTIC, SOLID, WHITE, 6 IN.	11720.00	LFT
0192	808-75055	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 6 IN.	950.00	LFT
0193	808-75057	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 6 IN.	32981.00	LFT
0194	808-75071	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, LANE INDICATION ARROW	64.00	EACH
0195	808-75073	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, ONLY	4.00	EACH
0196	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	1204.00	LFT
0197	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	483.00	LFT
0198	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	369.00	LFT
0199	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	456.00	LFT
0200	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	128.00	LFT
0201	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	11.00	EACH
0202	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	194.00	EACH
0203	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	15.00	EACH
0204	809-03983	PHASE SELECTORS	12.00	EACH

Call: 521

Contract: T -44356-B

Section No.: 1            WRONG WAY WARNING SIGN INSTALLATION

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09377		QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0007	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	202-74035		SIGN, REMOVE	26.00	EACH
0009	628-09401		FIELD OFFICE, TYPE A	18.00	MOS
0010	628-11976		COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0011	801-06640		CONSTRUCTION SIGN, TYPE A	92.00	EACH
0012	801-06775		MAINTAINING TRAFFIC	1.00	LS
0013	801-11642		PORTABLE CHANGEABLE MESSAGE SIGN	3.00	EACH
0014	801-12042		TRUCK MOUNTED ATTENUATOR	52.00	DAY
0015	801-12324		LAW ENFORCEMENT OFFICER	52.00	HRS
0016	802-05704		SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	748.00	LFT
0017	802-07058		SIGN, SHEET ASSEMBLY, RELOCATE	2.00	EACH
0018	802-09840		SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	278.75	SFT
0019	805-01579		MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0020	805-01842		HANDHOLE, SIGNAL, TYPE 1	13.00	EACH
0021	805-02645		SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	79.00	EACH
0022	805-04133		SIGNAL POLE, PEDESTAL, 12 FT	66.00	EACH
0023	805-04952		CONTROLLER AND CABINET	13.00	EACH
0024	805-08244		CELLULAR MODEM KIT	13.00	EACH
0025	805-11689		SIGNAL POLE, PEDESTAL, 20 FT	13.00	EACH
0026	805-11815		CONDUIT, HDPE, 2 IN. SCHEDULE 80	260.00	LFT
0027	805-11965		SOLAR POWERED FLASHING LED SIGN ASSEMBLY	29.00	EACH
0028	805-11965		SOLAR POWERED FLASHING LED SIGN ASSEMBLY	24.00	EACH
0029	805-11965		SOLAR POWERED FLASHING LED SIGN ASSEMBLY	13.00	EACH
0030	808-06716		LINE, REMOVE	36623.00	LFT
0031	808-09381		RETRO-REFLECTIVITY TESTING	1.00	LS

0032	808-10066	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, WRONG WAY RAMP ARROW	51.00	EACH
0033	808-11650	LINE, THERMOPLASTIC, DOTTED, WHITE, 6 IN.	141.00	LFT
0034	808-12667	LINE, THERMOPLASTIC, SOLID, WHITE, 10 IN.	3703.00	LFT
0035	808-12849	LINE, THERMOPLASTIC, DOTTED, YELLOW, 6 IN.	141.00	LFT
0036	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	19024.00	LFT
0037	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	11560.00	LFT
0038	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	794.00	LFT
0039	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1005.00	EACH
0040	808-96075	LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN.	1260.00	LFT

Call: 541

Contract: T -45438-A

Section No.: 1            WRONG WAY WARNING SIGN INSTALLATION

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09377		QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0007	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	202-74035		SIGN, REMOVE	15.00	EACH
0009	628-11976		COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0010	628-12683		FIELD OFFICE, TYPE D	16.00	MOS
0011	801-06640		CONSTRUCTION SIGN, TYPE A	40.00	EACH
0012	801-06775		MAINTAINING TRAFFIC	1.00	LS
0013	801-11642		PORTABLE CHANGEABLE MESSAGE SIGN	3.00	EACH
0014	801-12042		TRUCK MOUNTED ATTENUATOR	16.00	DAY
0015	801-12324		LAW ENFORCEMENT OFFICER	16.00	HRS
0016	802-05704		SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	198.00	LFT
0017	802-07058		SIGN, SHEET ASSEMBLY, RELOCATE	1.00	EACH
0018	802-09840		SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	133.00	SFT
0019	805-01579		MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0020	805-01842		HANDHOLE, SIGNAL, TYPE 1	4.00	EACH
0021	805-02645		SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	44.00	EACH
0022	805-04133		SIGNAL POLE, PEDESTAL, 12 FT	40.00	EACH
0023	805-04952		CONTROLLER AND CABINET	4.00	EACH
0024	805-08244		CELLULAR MODEM KIT	4.00	EACH
0025	805-11689		SIGNAL POLE, PEDESTAL, 20 FT	4.00	EACH
0026	805-11815		CONDUIT, HDPE, 2 IN. SCHEDULE 80	80.00	LFT
0027	805-11965		SOLAR POWERED FLASHING LED SIGN ASSEMBLY	20.00	EACH
0028	805-11965		SOLAR POWERED FLASHING LED SIGN ASSEMBLY	16.00	EACH
0029	805-11965		SOLAR POWERED FLASHING LED SIGN ASSEMBLY	4.00	EACH
0030	808-06716		LINE, REMOVE	16274.00	LFT
0031	808-09381		RETRO-REFLECTIVITY TESTING	1.00	LS



0032	808-10066	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, WRONG WAY RAMP ARROW	17.00	EACH
0033	808-12667	LINE, THERMOPLASTIC, SOLID, WHITE, 10 IN.	1768.00	LFT
0034	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	6894.00	LFT
0035	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	7318.00	LFT
0036	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	68.00	LFT
0037	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	226.00	LFT
0038	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	352.00	EACH

Call: 551

Contract: T -45440-A

Section No.: 1            SIGN MODERNIZATION (SERIES OF UNITS)

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358		INSPECTION HOLE, DEEPER THAN 3 FT	2.00	EACH
0003	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360		CONTRACT LIENS	1.00	DOL
0005	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0009	202-06541		REMOVE	11.00	EACH
0010	801-03290		CONSTRUCTION SIGN, TYPE C	10.00	EACH
0011	801-06640		CONSTRUCTION SIGN, TYPE A	26.00	EACH
0012	801-06645		CONSTRUCTION SIGN, TYPE B	14.00	EACH
0013	801-06710		FLASHING ARROW SIGN	50.00	DAY
0014	801-06775		MAINTAINING TRAFFIC	1.00	LS
0015	801-08401		TEMPORARY TRAFFIC BARRIER, TYPE 2	200.00	LFT
0016	801-11642		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0017	801-11880		VEHICLES FOR ADVANCED SLOWDOWN	9.00	DAY
0018	801-12324		LAW ENFORCEMENT OFFICER	40.00	HRS
0019	801-12883		TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	2.00	EACH
0020	802-03783		SIGN, PANEL, REMOVE	22.00	EACH
0021	802-05706		SIGN POST, SQUARE, TYPE 3, UNREINFORCED ANCHOR BASE	128.00	LFT
0022	802-07057		SIGN, PANEL, WITH LEGEND	11746.00	SFT
0023	802-12222		WIDE FLANGE SIGN POST SUPPORT FOUNDATION, TYPE A	48.00	EACH
0024	802-12223		WIDE FLANGE SIGN POST SUPPORT FOUNDATION, TYPE B	22.00	EACH
0025	802-12224		WIDE FLANGE SIGN POST SUPPORT FOUNDATION, TYPE C	18.00	EACH
0026	802-74040		SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	37.00	EACH
0027	802-74050		SIGN, OVERHEAD, REMOVE	22.00	EACH
0028	802-76095		STRUCTURAL STEEL, BREAKAWAY	37158.00	LBS