


-R-SI-	Road Systems Inc. Technical Support (330) 346–0721 www.roadsystems.com	Sequential Kinking Terminal (SKT)
		SHEET NO. 8 OF 10 DATE: 03/08/2013



Impact Head Mounting Detail




Road Systems Inc. Technical Support (330) 346-0721 www.roadsystems.com

Sequential Kinking Terminal (SKT) SHEET NO.

9 OF 10

DATE:

03/08/2013



Steel Post SKT Inspection Checklist

State:	Date:		
Projec	t #: Location:		
	The rail height is in accordance with the contract plans. This is approximately 27 ³ / ₄ " above the edge of the shoulder or the finished grade.		
	The rail in the terminal is not curved and is not attached to the post at post location #1.		
	The end rail panel has special slots and all rails are lapped in the proper direction.		
	The $\frac{3}{4}$ " x 8 $\frac{1}{2}$ " Hinge Bolt at posts #2 to #8 is on the downstream side of the post.		
	The 5/8" x 9" Hinge Bolt at post location #1 is on the upstream side of the post.		
	If the posts are Plug Welded, the splice plates are secure and the weld has not failed.		
	At post #2, the open-ended slot for the post bolt is on the upstream side of the post.		
	The guide chute of the impact head is parallel to the top of the rail and the impact head does not encroach on the shoulder (a maximum 25:1 taper is permitted to eliminate the potential for encroachment).		
	The two hex bolts ($\frac{1}{4}$ " x 4" or 5/16" x 3") holding the impact head to post 1 are secured.		
	The 8" x 8" bearing plate at post 1 is correctly positioned with the 5" dimension up & the 3" dimension down. The anchor cable is taut and correctly installed. A retainer/tie has been placed over the bearing plate to prevent rotation.		
	The cable anchor bracket shoulder bolts are properly attached to the W-beam guardrail and the cable anchor bracket is fully seated on the shoulder portion of the bolts.		
	If the posts were augered, be sure the backfill material around the posts is compacted.		
	No washers are used on the face of the rail except at the cable anchor bracket bolts.		
	If used, the foundation tubes do not protrude more than 4" above the ground line (measured by the AASHTO 5' cord method). Site grading may be necessary to meet this requirement.		
	The finished SKT installation is in accordance with all specific State DOT guidelines.		
Additi	onal notes:		

Inspection performed by:_____