nty	Warrick	Κ	Route	SR 62		Des. No.	1702071
(	CATE	GORICAL EXCI	LUSION	ENVIRO	ental Document NMENTAL A NFORMATION	ASSESSM	IENT FORM
Ro	oad No./	County:	State Road	(SR) 62, Warr	ick County		
De	signatio	on Number:	1702071				
Afte	er comple	escription/Termini: ting this form, I conclude to the if Level 4 CE):			nent/SR 62, approximent/SR 62, approximent/SR 62, approximent	<u> </u>	
X		ntegorical Exclusion, L vel 2 - table 1, CE Leve					
		tegorical Exclusion, L					
		tegorical Exclusion, L vel 4 - table 1, CE Leve					cal Exclusion Manu
		vironmental Assessme					
Ар	oproval _	ESM Signature		Date	ES Signatur	re	Date
			FHWA	Signature	Date		
Re	lease for	<b>Public Involvement</b>					
$\mathcal{D}$	1	:	5/21/2020				
/\	ES	M Initials	Date		ES Initials		Pate
Ce	rtificatio	on of Public Involveme		of Public Invol	vement Γ	Date	
Not	te: Do not	approve until after Section	n 106 public in	volvement and a	ll other environmenta	l requirements	have been satisfied.
	OOT ES/Dis				Date:		
Nan	ne and Org	anization of CE/EA Preparer:	Harlan M. F	ord, GAI Consul	tants, Inc.		
'hia ia	page 1 o	f 22 Project name:	SR 62 ove	r UNT to Otter	Creek	Dat	e: May 15, 2020

			•		•			
County _	Warrick		Route	SR 62		Des. No.	1702071	
		Pa	rt I - PU	BLIC INV	<u>OLVEMENT</u>	Γ		
		res some level of s. <b>The level of pu</b>						
		ave a historic bridg	e processed	under the Histor	ic Bridges PA*?	Yes	No X	
	o, then: opportunity for a	a Public Hearing R	equired?			X		
	aring is required O, and the ACH	d for all historic bri HP.	idges process	sed under the H	istoric Bridges Pro	ogrammatic Aç	greement bei	ween INDOT,
	Notice of Ent 2018 notifyin may be seen The project v	ement activities (Inneetings, newspapery letters were maining them about the print the area. A sandill meet the miniman (INDOT) Public	per articles, en iled to potenti project and the apple copy of to um requirement	tc.) have occurre ally affected pro at individuals re- he Notice of Ent ents described in	perty owners nea sponsible for land ry letter is include in the current <i>India</i>	r the project an surveying and d in Appendix ana Departmen	rea on Augus I field activitie C, page C4.	st 13, es
	opportunity to publication co	o submit comment ontingent upon the lic involvement req	and/or reque release of th	st a public heari is document for	ng. Therefore, a	legal notice wi	ll appear in a	local
		nvironmental Gro stantial controvers		community and	or natural resour	ce impacts?	Yes	No X
Remarks:	At this time, resources.	there is no substa	ntial public co	ontroversy conce	erning impacts to	the community	or to natura	Ī
		ral Project		•				
Sponsor of Local Name	the Project: of the Facility:		Department o ad (SR) 62	f Transportation	(INDOT)	INDOT Distric	t: Vincenn	<u> </u>
Funding So	urce ( <i>mark all t</i>	hat apply): Fed	deral X	State X Lo	cal Other*			
*If other is s	elected, please	e indentify the fund	ling source:					
PURPOSE	AND NEED	:						
		problem that the p CE Manual, Sect				oblem should	NOT be disc	ussed
14 foot (ft.) An Indiana delaminatio efflorescend southeast w INDOT Culv	span by 8 ft. ris Department of n and spalling ce in the beams vingwall and mo vert Inspection	tems from the dete se concrete slab to Transportation (IN with exposed reinfo s. The substructure oderate spalling the Report, this structur ructure and "9" be	p, approxima DOT) Culvertorcement, and exhibited maroughout. The ure has an over the properties of the	tely 30 ft. in leng Inspection Rep d severe section ap cracking and e channel displa erall condition ra	oth that carries SR ort dated August 2 I loss in the super minor efflorescen yed minor widesp ating of "5". Condi	R 62 over UNT 23, 2018 docu structure, and ce at the east read erosion.	to Otter Cree mented cracking with abutment an According to	ek. n d the
This is p	page 2 of 22	Project name:	SR 62 over	UNT to Otter C	·eek	Date	: May 15,	2020

County Warrie	ok	Route _	SR 62	Des. No.	1702071		
	s project is to provide a struct e structure having an overall o				n. This project		
PROJECT DESC	CRIPTION (PREFERRED	ALTERNA	ΓΙVE):				
County: Warrick	<	Municipalit	ty: SR 62				
Limits of Proposed	Work: Approximately 180	ft. west and	180 ft. east on SR 62	from the center of the	structure.		
Total Work Length	.: 0.07 Mile(s)		Total Work Area	0.73 Acre	e(s)		
	Modification Study / Interchar e FHWA grant a conditional a			equired?	Yes¹ No X Date:		
If an IMS or IJS is approval of the IMS	required; a copy of the approv/IJS.	ved CE/EA de	ocument must be sub	mitted to the FHWA wi	ith a request for final		
In the remarks box below, describe existing conditions, provide in detail the scope of work for the project, including the proferred alternative. Include a discussion of logical termini. Discuss any major issues for the project and how the project will improve safety or roadway deficiencies if these are issues.  Location  The project is located on SR 62 over Otter Creek, approximately 4.79 miles east of SR 61 in Skelton Township, Warrick County, Indiana. Specifically, this project is in Section 33, Township 5 South, Range 7 West, as shown on the DeGonia U.S. Geological Survey (USGS) 7.5 Minute Topographic Map (Appendix B, page B2).							
Existing Conditions  SR 62 within the project area, is a two lane, east to west, rural major collector, consisting of a 12 ft. eastbound (EB) travel lane and a 14 ft. westbound (WB) travel lane both with accompanying 2 ft. stone shoulders. SR 62 had an Average Annual Daily Traffic (AADT) count of 3,439 vehicles per day (VPD) in 2014 (source: INDOT Traffic County Database System). Culvert No. 062-087-48.79 is a 14 ft. span by 8 ft. rise concrete slab top, approximately 30 ft. in length and is showing signs of deterioration. This culvert carries SR 62 over UNT to Otter Creek. Surrounding land use is primarily agricultural and rural residential. There is a small forested area within the southern extents of the project area that would be considered suitable summer habitat for bat species.							
Preferred Alternative The Indiana Department of Transportation (INDOT) and the Federal Highway Administration (FHWA) are proposing a small structure replacement in Warrick County, IN. The project proposes replacing the existing culvert with a new 14 ft. span by 8 ft. rise reinforced concrete box (RCB) culvert. The scope of work for this project includes:							
<ul><li>Place ripi</li><li>Install ne</li><li>Roadway</li><li>Full depth</li></ul>	the existing culvert rap as a scour countermeasu w guardrail along the north ar work necessary to accommon pavement replacement over and regrade the stream chann	nd south side date the new the culvert t	v guardrails and 4 ft. prench		ea		
Please refer to Ap	pendix B, pages B14 to B15 f	or plan sheet	ts that illustrate the ab	oove stated work.			
This project demo dependent on any	e made to avoid, minimize and nstrates independent utility by other planned projects. The approximately 180 ft. west ar	ecause it will project area	replace the existing a is localized to the in	structure as a stand-al nmediate area surrour	lone project and is not		

This is page 3 of 22 Project name:

County	Warrick		Route	SR 62		Des. N	o. <u>1</u>	702071	
	scope of work, di h an official detoui						projec	ct will utilize a road	
	the above informativert that carries S				ne purpose and	d need of the	projec	ct by replacing the	
OTHER A	LTERNATIVES	CONSIDERE	D:						
Describe all was not sele	discarded alternat	tives, including t	he Do-Nothin	g Alternative a	nd an explanat	tion of why ea	ch disc	arded alternative	
The "No B The "No-Bu impacts by	uild" Alternative uild" alternative wa utilizing the existi urpose and need o	ng structure with	no expenditu	are of funds for	r improvement.	However, this			
This alternation, the alternative	ed Flat Top Culve ative proposed rep is alternative woul would result in sin purpose and need	lacing the existi d include placer nilar environmer	ng structure v ment of Class ital impacts ai	1 revetment rind cost as the	prap at the out preferred alter	let as a scour native. Althou	counte	ermeasure. This	
This alternation, the alternative	Three-Sided Arch Top Culvert (Alternative #3)  This alternative proposed replacing the existing structure with a 14 ft. span by 8 ft. rise three-sided arch top culvert. In addition, this alternative would include placement of Class 1 revetment riprap at the outlet as a scour countermeasure. This alternative would result in similar environmental impacts and cost as the preferred alternative. Although this alternative meets the purpose and need of the project it was dismissed for a more feasible and prudent alternative.								
It would no It would no It would no It would no It would res	The Do Nothing Alternative is not feasible, prudent or practicable because (Mark all that apply):  It would not correct existing capacity deficiencies;  It would not correct existing safety hazards;  It would not correct the existing roadway geometric deficiencies;  It would not correct existing deteriorated conditions and maintenance problems; or  It would result in serious impacts to the motoring public and general welfare of the economy.  Other (Describe)								
ROADWA	Y CHARACTER	R: SR 62							
Current AD Design Ho	Classification: DT: ur Volume (DHV): Speed (mph):	Rural Major 3,439 143 55 Existing	Collector VPD (201 Truck Percen Legal Speed	itage (%)	n Year ADT: 7 55	3,980	VPD	(2022)	
Number of	Lance	2		2					
Type of La	nes:	12 ft. (EB) & 1		12 ft. (EE	3) & 14 ft. (WB)				
Pavement Shoulder V Median Widewalk V	Vidth: dth:	26 ft. 2-3 ft. N/A ft. N/A ft.		26 4 N/A N/A	ft. ft. ft. ft.				
Setting: Topograph		Urban X Level	Subu Rollin	rban X	Rural Hilly				
This is	page 4 of 22 Pro	oject name:	SR 62 over	UNT to Otter (	Creek		Date:	May 15, 2020	

County Warric	Rou	te SR 62	Des. No. <u>1702071</u>
If the proposed actio	n has multiple roadways, this secti	ion should be filled out for each roa	adway.
DESIGN CRITERIA	A FOR BRIDGES:		
Structure/NBI Numl	per(s): _CV # 062-087-48.79	Sufficiency Rating:	N/A (Rating, Source of Information)
	Existing	Proposed	
Remarks: T to e p re p s	N/A    N/A   ft.     N/A   ft.     Width: N/A   ft.     2-3   ft.     Work:   ft.     Work:   ft.     Work:   ft.     Other Creek. Specifically, this structure is a 14 ft. span by roposed project includes a new resplacement over the culvert trench accement of riprap, and the realign tructures are included with this program in the process of the replaced as part of the rehabilitated or replaced as part of the rehabilitation of the rehabi		Ictures. 18.79 that carries SR 62 over UNT 19 miles east of SR 61. The 17 kimately 30 ft. in length. The 18 rt, full depth pavement 18 ening of the roadway shoulders, 19 litches. No other bridges or  Yes No N/A
MAINTENANCE	OF TRAFFIC (MOT) DURING	CONSTRUCTION:	
Provisions will b Provisions will b Provisions will b Will the proposed M	way proposed?  Ive the use of a detour or require as a made for access by local traffic as a made for through-traffic depended and to accommodate any local	ent businesses. I special events or festivals. ronmental consequences of the act	X X X
Remarks:	Routes. The best available detor and opposite for eastbound. This to plan sheets illustrating the MC The closures/lane restrictions wi buses and emergency services):	ur route would be SR 161 to SR 68 s route would add distance of 23.10 DT in Appendix B, page B13.  Il pose a temporary inconvenience ; however, no significant delays are	d closure and official detour on State 8 to SR 61 to SR 62 for westbound traffic 0 miles for traveling motorists. Please refe to traveling motorists (including school e anticipated, and all inconveniences will ion but will cease with project completion.
This is page 5 c	f 22 Project name: SR 62	over UNT to Otter Creek	Date: May 15, 2020

County Warrick	Route SF	R 62	Des. No.	1702071				
ESTIMATED PROJECT COST AND SCHEDULE:								
Please note that this project is included under Lead Des No. 1700170 in the 2020-2024 STIP under contract R-40551. The PE costs come from the 2018-2021 STIP, as funding was utilized in 2019 for PE.								
Engineering: <u>\$ 138,800 (2019)</u>	Right-of-Way: \$ 18	,000.00 (2020)	Construction: \$ 2	2,042,438.00 (2020)				
Anticipated Start Date of Construction:	Spring of 2022		_					
Date project incorporated into STIP	July 2, 2019							
Is the project in an MPO Area? X								
If yes,								
Name of MPO Evansville Metrop	olitan Planning Organiza	ation						
Location of Project in TIP Page 45								
Date of incorporation by reference int	o the STIP July 2, 2	019						

#### **RIGHT OF WAY:**

	Amount (acres)			
Land Use Impacts	Permanent	Temporary		
Residential	0.150	0		
Commercial	0	0		
Agricultural	0.027	0		
Forest	0.347	0		
Wetlands	0	0		
Other:	0	0		
Other:	0	0		
TOTAL	0.524	0		

Describe both Permanent and Temporary right-of-way and describe their current use. Typical and Maximum right-of-way widths (existing and proposed) should also be discussed. Any advance acquisition or reacquisition, either known or suspected, and there impacts on the environmental analysis should be discussed.

#### Remarks:

Existing right-of-way (ROW) ends approximately 30 ft. north from the roadway centerline and approximately 30-35 ft. south from the roadway centerline. The ROW within the project area is currently used to maintain the existing roadway, shoulders and ditches.

This project will require approximately 0.792 acre of reacquired ROW and approximately 0.524 acre of permanent right-of-way from three parcels on the north side of SR 62 and one parcel on the south side of SR 62. No temporary ROW is needed for this project.

If the scope of work or permanent or temporary right-of-way amounts change, the INDOT Environmental Services Division (ESD) and the INDOT District Environmental Section will be contacted immediately.

This is page 6 of 22	Project name:	SR 62 over UNT to Otter Creek	Date:	May 15, 2020
			_	

		<b>-</b>	00.00		4700074
County	Warrick	Route	SR 62	Des. No.	1702071

#### <u>Part III – Identification and Evaluation of Impacts of the Proposed</u> <u>Action</u>

SECTION A – ECOLOGICAL RESOURCES			
Streams, Rivers, Watercourses & Jurisdictional Ditches Federal Wild and Scenic Rivers State Natural, Scenic or Recreational Rivers Nationwide Rivers Inventory (NRI) listed Outstanding Rivers List for Indiana Navigable Waterways	<u>X</u>	Impacts Yes No X	

Remarks:

Based on a desktop review, a site visit on October 11, 2018 by GAI, the aerial map of the project area (Appendix B, page B3), and the water resources map in the Red Flag Investigation (RFI) report (Appendix E, pages E1 to E7), there are three stream segments located within the 0.5-mile search radius. There are two stream segments, UNT to Otter Creek and UNT 1, present within the project area.

A Waters of the U.S. Determination / Wetland Delineation Report was approved by INDOT Ecology and Waterway Permitting Office on July 18, 2019. Please refer to Appendix F, pages F1 to F19 for the Waters of the U.S. Determination / Wetland Delineation Report. It was determined that UNT to Otter Creek and UNT 1 would likely be considered Waters of the U.S. Additional roadside ditches were observed in the northeast and southeast quadrants of the project area; however, due to their lack of a defined bed and bank or flow regime, they would not likely be designated as Waters of the U.S. The USACE makes all final determinations regarding jurisdiction.

UNT to Otter Creek is an intermittent stream that flows north to south through the project area and exhibits an ordinary high-water mark (OHWM) of 6 ft. wide and 6 ft. deep. UNT to Otter Creek has a riparian zone that consists of maintained lawn on the north side of the creek and is forested on the south side of the creek. Approximately 246 linear ft. of UNT to Otter Creek is present within the project area with 30 linear ft. encapsulated within the existing culvert. Total impacts to UNT to Otter Creek due to the riprap scour countermeasures, replacement of the culvert, dewatering, and regrading of the channel is approximately 246 linear ft. and or 0.05 acre. Approximately 223 linear ft. of new impacts will occur to UNT to Otter Creek. UNT 1 is a roadside ditch with intermittent flow towards UNT to Otter Creek and is located in the southeast quadrant of the project area. UNT-1 exhibited an OHWM of 3 ft. wide and 3 in. deep. Total impacts to UNT 1 due to realigning of the stream channel is approximately 190 linear ft, and/or 0.03 acre. Cumulatively impacts to UNT to Otter Creek and UNT-1 will equal 413 linear ft. and/or 0.08 acre. Stream mitigation will be required for this project as cumulative stream impacts will exceed 300 linear ft. Permits for the impacts to UNT to Otter Creek and UNT 1 will be necessary. Please refer to the *Permits* section of this document for details.

Early coordination letters were sent on November 8, 2018 to the Indiana Department of Natural Resources, Division of Fish and Wildlife (IDNR-DFW), the U.S. Army Corps of Engineers (USACE), and the U.S. Fish and Wildlife Service (USFWS) (Appendix C, pages C1 to C2). The IDNR-DFW indicated in their letter dated December 7, 2018 (Appendix C, pages C21 to C23), that the project would not require formal IDNR approval under the programs administered by the Division of Water. The IDNR-DFW letter also provided a list of recommendations to help avoid and minimize impacts to UNT to Otter Creek and UNT 1. All applicable recommendations can be found in the *Environmental Commitments* section of this CE document.

The USACE did not respond to the early coordination letter.

The USFWS responded in a letter dated November 14, 2018 (Appendix C, pages C24 to C26) stating, "Based on a review of the information you provided, the U.S. Fish and Wildlife Service has no objections to the project as currently proposed." The USFWS also provided a list of standard recommendations. All applicable recommendations can be found in the *Environmental Commitments* section of this CE document.

This is page 7 of 22	Project name:	SR 62 over UNT to Otter Creek	Date: May 15, 2020

County _	Warrick		Route	SR 62	Des. No.	1702071
Other Surface Waters Reservoirs Lakes Farm Ponds Detention Basins Storm Water Management Facilities Other:		ties		Prese X	Yes No	
Remarks:	Based on a desktop review, a site visit on October 11, 2018 by GAI, the aerial map of the project area (Appendix B, page B3), and the water resources map in the RFI report (Appendix E, page E7), there are 8 lakes located within the 0.5 mile search radius. No other surface waters are present within the project area; therefore, no impacts are expected.  Early coordination letters were sent on November 8, 2018 to the IDNR-DFW, the USACE, and the USFWS (Appendix C, pages C1 to C2). The IDNR-DFW responded on December 7, 2018 (Appendix C, pages C21 C23) with no specific comments in regard to other surface waters. However, the IDNR-DFW letter did provi a list of standard recommendations. All applicable recommendations can be found in the <i>Environmental Commitments</i> section of this CE document.  The USACE did not respond to the early coordination letter.  The USFWS responded in a letter dated November 14, 2018 (Appendix C, pages C24 to C26) stating, "Bas on a review of the information you provided, the U.S. Fish and Wildlife Service has no objections to the project of the commitments of the project of the comments of the project of the proj					
	provided a list of st Environmental Con				mmendations can be found	d in the
Wetlands				Prese	ence <u>Impac</u> Yes	ts No
Total wetla	nd area: N/A	acre(s)	) Total	wetland area impac	cted: N/A acre	(s)
(If a determi	nation has not been	made for no	on-isolated/isola	ated wetlands, fill in	the total wetland area imp	pacted above.)
Wetland N	o. Classification	Total Size (Acres)	Impacted Acres	Comments		
N/A	N/A	N/A	N/A	N/A		
Wetlands (Mark all that apply) Wetland Determination Wetland Delineation USACE Isolated Waters Determination			X	<u>ES App</u> July 18, 2019	roval Dates	
Mitigation P	lan					

Date: May 15, 2020

SR 62 over UNT to Otter Creek

This is page 8 of 22 Project name:

		indiana Depai	rtment of Trans	portation		
County	Warrick	Route	SR 62	Des. No.	1702071	
would res Subst Subst Uniqu Subst	ult in (Mark all that app antial adverse impacts a antially increased proje e engineering, traffic, m	to adjacent homes, busing to costs; laintenance, or safety pro conomic, or environmenta	ess or other improved blems;		ance	
Measures	to avoid, minimize, and	mitigate wetland impacts	need to be discussed	in the remarks box.		
Remarks:	Based on a review of (https://www.fws.gov) map (Appendix B, p. located within the 0. therefore, no impact	of the National Wetlands I wetlands/data/Mapper.hage B2), and the RFI reposition for the search radius. No sare expected.	nventory (NWI) online tml), a site visit on Ocort (Appendix E, pages wetlands are present v	mapper tober 11, 2018, the USG s E1 to E9), there are tw within or adjacent to the	venty-five wetlands project area,	
	Waterway Permitting the U.S. Determinat	. Determination / Wetland g Office on July 18, 2019. ion / Wetland Delineation a. The USACE makes all	Please refer to Apper Report. It was determ	ndix F, pages F1 to F19 ined that there are no w	for the Waters of	
Early coordination letters were sent on November 8, 2018 to the IDNR-DFW, the USACE, and the USFWS (Appendix C, pages C1 to C2). The IDNR-DFW responded on December 7, 2018 (Appendix C, pages C21 C23) with recommendations on wetland mitigation. The IDNR-DFW letter also provided a list of standard recommendations. All applicable recommendations can be found in the <i>Environmental Commitments</i> section of this CE document.						
	The USACE did not	respond to the early coor	dination letter.			
	on a review of the in as currently propose	ded in a letter dated Nove formation you provided, t d." The USFWS provided an be found in the <i>Enviro</i>	he U.S. Fish and Wildl I a list of standard reco	life Service has no obje ommendations and all a	ctions to the project applicable	
<b>Terrestria</b> Unique or	ı <b>l Habitat</b> High Quality Habitat		<u>Presence</u>	Impacts Yes No X		
Use the ren Remarks:	Based on a desktop (Appendix B, page E quadrant of the proje asiatic dayflower (Codeltoids), hackberry considered prime or culvert, placement of paved shoulders. Apsouthern quadrants approximately 0.65 ameet the purpose ar practicable required this project.	review, a site visit on Oci 33), there is forested ripar ect area. Vegetation cons commelina communis), rece (Celtis occidentalis), and unique. Impacts to this hard friprap, the realignment of proximately 0.16 acre of of the project area. Total acre. Avoidance alternative and need of the project. Ho to complete this project.	tober 11, 2018 by GAI ian habitat in both sou ists primarily of spotte of canary grass ( <i>Phala</i> pokeweed ( <i>Phytolacc</i> abitat will be necessar of UNT to Otter Creek tree trimming and/or carea of soil disturbances are not practical for wever, impacts have to mitigation for impacts	and the aerial map of the athern quadrants and the deady's thumb ( <i>Polygonaris arundinacea</i> ), cotton a americana). This habity for the replacement of and UNT 1, and to accelering is anticipated in the associated with this part this project as impacts of the project to the greats to terrestrial habitat	he project area e northeast num persicaria), nwood (Populus itat would not be if the existing ommodate 4 ft. the northeast and project is a are necessary to extest extent is anticipated for	
	The IDNR-DFW resp	oonded on December 7, 2 ommendations to help av	2018 (Appendix C, pag	ges to C21 to C23). The	IDNR-DFW letter	

County	Warrick	Route	SR 62	_ Des	s. No.	1702071			
	recommendations can be found in	the <i>Envir</i> o	onmental Commitmer	nts section of this	CE docur	ment.			
	If there are high incidences of animal movements observed in the project area, or if bridges and other areas appear to be the sole corridor for animal movement, consideration of utilizing wildlife crossings should be taken.								
	roposed project located within or ad st features located within or adjacer	nt to the foo	tprint of the proposed		Yes	No X X			
Use the rema	If yes, will the project impact any arks box to identify any karst feature			t investiaation mus	st comply	with the Karst			
	October 13, 1993)  Based on a desktop review, the p the October 13, 1993 Memorandu (Appendix B, page B2), and the R within the project area. In the earl indicate that karst features may estated that there is high liquefaction encounter bedrock resources. Re 2019. No impacts are expected.	roject is loc im of Unde FI report (A y coordinat kist in the p on potentia	rated outside the des rstanding (MOU). Acc Appendix E, pages E ion response, the Inc roject area (Appendi , a 1% Annual Chan	ignated karst region cording to the topon to E9), there are diana Geological S x C, page C15 to ce Flood Hazard,	on of Indi o map of no karst Survey (IC C17). The and a hig	ana as outlined in the project area features identified GS) did not eir response ph potential to			
Within th Any critic Federal State sp	d or Endangered Species he known range of any federal specical habitat identified within project at species found in project area (based ecies found in project area (based upon 7 formal consultation required for	rea d upon info pon consu	tation with IDNR)  Yes	No X	[	Impacts Yes No X			
Remarks:	Based on a desktop review and the 2019, the IDNR Warrick County Eis included in (Appendix E, pages identified ETR species located with letter dated December 7, 2018 (A has been checked the Natural He species listed as state or federally vicinity.	ndangered E8 to E9). hin the cou ppendix C, ritage Prog	, Threatened and Ra The highlighted spec inty. According to the pages C21 to C23), ram's Database has	re (ETR) Species sies on the list refle IDNR-DFW early the Natural Herita been checked and	List has ect the fe coordinate ge Prograd to date	been checked and deral and state ation response am's Database no plant or animal			
	Project information was submitted portal, and an official species list of the federally endangered Indian (NLEB) ( <i>Myotis septentrionalis</i> ). Number than the Indiana bat and northern	was genera na bat ( <i>My</i> o lo additiona	ated (Appendix C, page totis sodalis) and the f al species were found	ges C27 to C32). <sup>-</sup> ederally threatene	The proje d northe	ect is within range rn long-eared bat			
	The project qualifies for the Rang long-eared bat (NLEB), dated Mar Administration (FRA), Federal Tracompleted on December 20, 3019 to Adversely Affect" the Indiana be verified the effect finding on Decepages C50 to C52). No response	y 2016 (rev Insit Admin ), and base at and/or th mber 20, 2	ised February 2018), istration (FTA), and U d on the responses p e NLEB (Appendix C 019 and requested U	between FHWA, JSFWS. An effect provided, the proje c, pages C35 to C4 JSFWS's review of	Federal   t determi ect was fo 49). INDO f the findi	Railroad nation key was bund to "Not Likely DT reviewed and ing (Appendix C,			

Date: May 15, 2020

This is page 10 of 22 Project name: SR 62 over UNT to Otter Creek

County	Warrick	Route	SR 62		Des. No.	1702071
	concluded they concur with the commitments in the Environm Structure CV 062-087-48.79 GAI. No migratory birds/nests  This precludes the need for full Species Act, as amended. If reproject plans are changed, US	nental Commitm was inspected for were found durither consultationew information	nents section of the presence ring the inspection on this project on endangere	if this document.  e of migratory biretion.  ect as required used species at the	ds/nests on Oc	tober 11, 2018 by
SECTION	B – OTHER RESOURCES					
Wellhea Public W Residen Source \	Vater Resources d Protection Area Vater System(s) tial Well(s) Vater Protection Area(s) urce Aquifer (SSA)			<u>Presence</u>	Yes	No
ls ti Is ti Initi	is present, answer the following the Project in the St. Joseph Aquate FHWA/EPA SSA MOU Appli al Groundwater Assessment Re ailed Groundwater Assessment	uifer System? cable? equired?		Yes	No	
Remarks:	The project is located in Warr Aquifer, the only legally desig Source Aquifer Memorandum expected.  In an early coordination letter wellhead area (Appendix C, p. The Indiana Department of No. (https://www.in.gov/dnr/water.project. Therefore, no impacts Based on a desktop review of 2, 2018, and the RFI report (ABoundary location. No impact Based on a desktop review, a (Appendix B, page B3), no put	dated Septembage C14). No interest and cated Septembage C14). No interest attract Resource (3595.htm) was a are expected. It the INDOT MS appendix E, pags are expected a site visit on October 1995.	ce aquifer in thing (MOU) is not per 10, 2019, Ill mpacts are expess Water Well accessed on 164 website (http://ges.E1 to E9), actober 11, 2018	DEM stated the poected.  Record Database May 23, 2019 GA  Des://entapps.indo this project is not	a. Therefore, the his project. No roject is not located in an Ual map of the p	ated within a  located near this  by GAI on October Irban Area

Date: May 15, 2020

This is page 11 of 22 Project name: SR 62 over UNT to Otter Creek

County	Warrick	Route	SR 62	Des. No.	1702071
FL . 151.			<u>Pr</u>	esence Impa	
Transve Project	ns dinal Encroachment erse Encroachment located within a regulated located in floodplain withir		m from project	Yes   X   X   X   X   X   X   X   X   X	No X
Discuss imp	acts according to classific	ation system describe	ed in the "Procedura	al Manual for Preparing Ei	nvironmental Studies".
Remarks:	Based on a desktop revented website (http://dr (Appendix E, pages E1 IDNR floodplain maps (local Floodplain Adminional Floodplain Fl	view of The Indiana Darmaps.dnr.in.gov/app to E9); this project is Appendix F, page F1 strator. The floodplair is a Category 3 per the g drainage structures. antial change in their is and flood limits. The and beneficial floodplair on thave substantial refore, it has been det both longitudinal and ecessary for the work ecessary for the replair etter was sent to the II aded on December 7, latory programs admir the IDNR Bridge Ex	epartment of Natural psphp/fdms/) by GA located in a regular 2). An early coordinated administrator did reasonable in administrator did remained that this endicated in the roadway, did rement of the existence in the roadway, did rement of the existence in a contract of the existence in the roadway, did rement of the existence in the roadway in	al Resources Indiana Floral on October 2, 2018, and tory floodplain as determination letter was sent on Monot respond within the 30-bl, which includes projects to drainage structures incod water. This change compared within the substantial of the substantial of the flood control within of the flood tiches and stream channels.	odway Information If the RFI report Ined from approved May 14, 2019, to the Iday time frame.  Ithat involve Isluded in this project Isluded in this pr
	ural Lands armland (per NRCS)		<u>Presence</u>		o X
	nts (from Section VII of CF r greater, see CE Manual for	<del>-</del>			
See CE Mar Remarks:	(Appendix B, page B3) Policy Act (FPPA) with project; therefore, no in  An early coordination le	eview, a site visit or, there is no land that in or adjacent to the apacts are expected.  etter was sent on Novesponded on November	n October 11, 2018 at meets the definiti project area. The r wember 8, 2018, to per 19, 2018 (Appe	your project.  B by GAI, the aerial may on of farmland under the requirements of the FPP, the Natural Resources Cendix C, page C18) stating	Farmland Protection A do not apply to this Conservation Services

Date: May 15, 2020

This is page 12 of 22 Project name: SR 62 over UNT to Otter Creek

County _	Warrick	Route _	SR 62	Des. No.	1702071
SECTION (	C – CULTURAL RES	OURCES			
Minor Projects	s PA Clearance	Category Type B 9  Eligible and/or	March 26, 202		N/A
Results of Re	esearch	Resource Pre	<u>esent</u>		
Archaeology NRHP Buildir NRHP Distric NRHP Bridge	et(s)				
Project Effec	et				
No Historic P	roperties Affected X	No Adverse Eff	fect Adve	rse Effect	
Historic Prope Historic Prope Archaeologica Archaeologica Archaeologica Archaeologica Archaeologica APE, Eligibilit 800.11 Docur Memorandum	al Records Check/ Revieus Reports In Survey Reports In Survey Reports In Phase It Survey Reports It Investigation In Phase III Data Recovery and Effect Determinat	ort X ort X ort	the Section 106 proces name of paper(s) and	ary of the Section 100 s requires that a Lega d the comment perioo	5 process, using the I Notice be published I deadline. Likewise
Remarks:	guidelines of Category Agreement, (Appendix	,	ry A, Types 6 & 9 unde	r the Minor Projects Pr	ogrammatic
		<b>ype 9:</b> Includes the inst res within undisturbed s		epair, lining, or extensi	on of culverts and
		ype 6: Includes the reparriers, glare screens, ar			
		ype 9: Includes the instrways, and bridge piers			trol measures
	As this project takes p	lace in undisturbed soils	s an archaeological sur	vey was required. The	archaeological
This is p	age 13 of 22 Project r	name: SR 62 over l	JNT to Otter Creek	Dat	e: May 15, 2020

County	Warrick	Route	SR 62	Des. No.	1702071
	survey concluded that no archaer recommended that the project be consultation is required. This con Section 106 have been fulfilled.	allowed to	proceed as plan	nned (Appendix D, pages D7 to	D8). No further
SECTION	D – SECTION 4(f) RESOURCE	S/ SECTI	ON 6(f) RESC	OURCES	
Section 4(	f) Involvement (mark all that apply)		Presence	Haa	
Public Public	ther Recreational Land ly owned park ly owned recreation area (school, state/national forest, bikewa	ay, etc.)	Fresence	Yes No	
			Evaluations Prepared		
"D	ogrammatic Section 4(f)* e minimis" Impact* dividual Section 4(f)			FHWA Approval date	
Nation Nation State \	Waterfowl Refuges al Wildlife Refuge al Natural Landmark Wildlife Area Nature Preserve		Presence	Yes No	
"De	ogrammatic Section 4(f)* e minimis" Impact* lividual Section 4(f)		Evaluations Prepared	FHWA Approval date	l
Historic Pr Sites e	roperties eligible and/or listed on the NRHP		<u>Presence</u>	Yes No	
"De	ogrammatic Section 4(f)* e minimis" Impact* lividual Section 4(f)		Evaluations Prepared	<u>FHWA</u> <u>Approval date</u>	
	roval of the environmental documental documents)	nt also sen	es as approval	of any Section 4f Programma	tic and/or De minimis
Discuss Pro documentati Individual S	grammatic Section 4(f) and "de mi ion must be separate Draft and Fi ection 4(f) evaluations please refe posed alternatives that satisfy the re	inal docum r to the "F	ents. For furthe Procedural Man	er discussions on Programma ual for the Preparation of En	tic, "de minimis" and

Date: May 15, 2020

This is page 14 of 22 Project name: SR 62 over UNT to Otter Creek

County _	Warrick	Route	SR 62	Des. No.	1702071
Remarks:	Section 4(f) of the U.S. Department historic lands for federally funded. The law applies to significant pubeligible or listed historic properties 4(f) resources.	transportation	ion facilities unless parks, recreation a	there is no feasible and proreas, wildlife/waterfowl refu	udent alternative. Iges, and NRHP
	Based on a desktop review, a site (Appendix B, page B3), and the F within the 0.5 mile search radius. Therefore, no use is expected.	RFI report (A	Appendix E, pages I	E1 to E9), there are no 4(f)	resources located
Section 6(f)	Involvement		<u>Presence</u>	<u>Use</u>	
Section 6(f)	Property			Yes No	
Discuss propo	osed alternatives that satisfy the re	auirements	of Section 6(f). Dis	scuss any Section 6(f) invol	vement.
Remarks:	The U.S. Land and Water Conser (LWCF), which was created to pr Section 6(f) of this Act prohibits c	rvation Funeserve, dev	d Act of 1965 establelop, and assure ac	lished the Land and Water accessibility to outdoor recre	Conservation Fund ation resources.
	A review of 6(f) properties on the https://www.lwcfcoalition.com/too addition to the LWCF website revhttps://www.in.gov/indot/files/LWC (Appendix I, page I2). This list revlocated within or adjacent to the particle agriculture.	Is revealed riew, the IDI CF%20India realed 3 pro	a total of 2 properting NR's Division of Outename NR's Division of Outename NR's Division of Outename NR's Division NR's NR's NR's NR's NR's NR's NR's NR's	es in Warrick County (Appet tdoor Recreation list locate List_02-25-2020.pdf was a lick County. None of these	d at Iso reviewed properties are
	of this project.				
SECTION	E – Air Quality				
0_0	_ / <u></u>				
Air Q	uality				
ls th If YI	Informity Status of the Project The project in an air quality non-attaines, then: Its the project in the most current Most the project exempt from conform the project is NOT exempt from the Is the project in the Transportal Is a hot spot analysis required	IPO TIP? nity? conformity, tion Plan (T	then:	Yes No X	
Leve	el of MSAT Analysis required?				
Lev	el 1a 🗶 Level 1b 🔙 Leve	12 L	evel 3 Level	4 Level 5	
Remarks:	The FY 2020-2024 STIP is list this contract is 1700170. The contract number R-40551 (App	FY 2020-2	024 STIP includes		
	This project is located in Warrie to IDEM's website: https://www				
This is pa	age 15 of 22 Project name:	SR 62 over	UNT to Otter Creek	c Dat	e: _May 15, 2020

County	Warrick	Route	SR 62	_ Des. No.	1702071
	CFR Part 93 do not apply	V.			
	This project is of a type of under the Clean Air Act analysis is not required.	qualifying as a ca			
SECTION	E NOISE				
SECTION	F - NOISE				
Noise					Yes No
Is a noise a	analysis required in accordance	ce with FHWA reg	gulations and INDOT's	s traffic noise policy?	X
		No Yes/ Da	ate		
ES Review	v of Noise Analysis	X	110		
Remarks:	This project is a Type III p	roject. In accorda	ance with 23 CFR 77	2 and the current <i>Indiana</i>	a Department of
	Transportation Traffic Nois				
SECTION	G - COMMUNITY IMPAC	CTS			
Will the pro Will the pro Will the pro Will constru Does the co If No, a	Community & Neighborhood posed action comply with the posed action result in substant posed action result in substant posed action result in substant posed action activities impact community have an approved the steps being made to advant project comply with the transition.  This project will benefit the ensure continued passage impact the tax base for the economic impacts from the within the project area, SR project is not required to have	local/regional de ntial impacts to contial impacts to lo unity events (festi transition plan? nce the community on plan? (explain community by profor motorists on sarea or result in a project.	ommunity cohesion? cal tax base or propervals, fairs, etc.)? y's transition plan? in the remarks box)  oviding a structurally SR 62 over UNT to Otal a division of the community	and hydraulically sufficienter Creek. The project is nunity. There are no long-	not anticipated to term, foreseeable
	nd Cumulative Impacts reposed action result in substan	ntial indirect or cu	mulative impacts?		Yes No X
Remarks:	Indirect impacts are effects but are still reasonably fore related to induced changes affect the environment which present, and reasonably fo actions.	eseeable. Indirects in the pattern of the character characters of the character in the cha	t effects may include pland use, population incremental impact of	growth inducing effects and density, or growth rate. C f the action when added t	nd other effects Cumulative impacts to other past,
	There have been no significemerge later in time or farth				
This is	page 16 of 22 Project name	e: <u>SR 62</u> over	UNT to Otter Creek	Dat	e: <u>May 15, 2020</u>

		•		Transportation			
County _	Warrick	Route	SR 62		Des. No.	17020	71
	no significant effects identified of growth rate, or related effects of regard to cumulative impacts, no result from the incremental impacts foreseeable future actions. This project will not cause any indirest or negative impacts to the commentation.	on air and wate to significant it act of the propertion of sproject involvect or cumulation	er or other nat impacts on the posed project ves the replactive impacts. Fi	ural systems, includi environment have b when added to other ement of Culvert No	ing ecosyste been identifier past, prese . 062-087-48	ems. Add ed which ent, and r 8.79. As s	itionally, in could easonably such, this
Will the prop private utilitie	ities & Services osed action result in substantial es, emergency services, religious acilities? Discuss how the main	s institutions,	airports, public	transportation or pe	olic and edestrian	Yes X	No
Remarks:	Based on a desktop review, a s area (Appendix B, page B3), ar within the 0.5 mile search radiu to all properties will be maintain	nd the RFI rep s. There are	oort, (Appendix no public facili	E, pages E1 to E9) ties within or adjace	, there are nent to the pro	no public oject area	facilities
Early Coordination letters were sent on August 8, 2018 to AT&T, Boonville Chandler Natural Gas, the T Tennyson, Vectren, Citizens Energy Group and Veolia Water. Vectren – Distribution Electric responded September 6, 2018 stating that they have an overhead electric conductor and facilities within the project AT&T responded on January 25, 2019 stating that there are two aerial copper cables on AT&T owned pon the south side of SR 62. Boonville Chandler Natural Gas responded on February 21, 2019 stating the there is a 2-inch plastic high pressure (35 PSI) gas main on the south side of SR 62 and a 4-inch steel pressure valve (400PSI) on the north side of SR 62. Utility coordination will be ongoing as this project advances.							ded on bject area. ed poles g that eel high
	It is the responsibility of the pro- weeks prior to any construction						
During the d Does the pro If YES, then Are an	ntal Justice (EJ) (Presidential Edevelopment of the project were Edect require an EJ analysis?  Ey EJ populations located within the project result in adversely high	EJ issues iden he project are	ea?	to EJ populations?		X	X X X
Remarks:	Under FHWA Order 6640.23A, responsible to ensure that their adverse effect on minority or low an Environmental Justice (EJ) A of additional permanent right-of way from three parcels on the n EJ Analysis is required.  Potential EJ impacts are detective.	programs, pow-income pop Analysis is receively. The proportion of South	olicies, and act oulations. Per quired for any p oject will requir SR 62 and one	ivities do not have a the current INDOT ( project that has two e approximately 0.52 parcel on the south	disproportion  Categorical If or more relocated acre of positions acres of the side of SR (	onately hi Exclusion ocations o ermanen 62. There	gh and Manual, or 0.5 acre t right-of- efore, an
	population to determine if popul and adverse impacts to them. To community of comparison (COC overlaps the project area is called An AC has a population of conclow-income or minority population. American Community Survey 5 <a href="https://factfinder.census.gov/">https://factfinder.census.gov/</a> or populations within the AC are s	lations of EJ of the reference C). In this project the affecte tern for EJ if the contract on is 125% of Year Estimated January 24,	concern exists population madect, the COC is described community (the population of the COC. Dates was obtain 2020 by GAI.	and whether there only be a county, city of seconds. In this project, is more than 50% may a from the US Censed from the US Cen	could be disport own and andiana. The the AC is Coinority or lowest Bureau, sus Bureau	oroportion is called to community ensus Tra w-income 2013 – 2 Website	nately high the that that acts 301. or if the 017

County	Warrick	Route SR 62	Des. No1702071
	Table: Minority and Lo	w-Income Data (US Census Bureau,	ACS 5-year estimates 2013-2017)
		COC – Warrick Count	y AC-1 - Census Tract 301
	Percent Minority	7.20%	0.27%
	125% of COC	9.00	AC < 125% COC
	EJ Population of Conc	ern	No
	Percent Low-Income	7.69%	9.20%
	125% of COC	9.61%	AC < 125% COC
	EJ Population of Cond	ern	No
	threshold. Therefore, this A AC-1, Census Tract 301 ha threshold. Therefore, this A Conclusion	AC does not contain minority populations as a percent low-income of 9.20% which does not contain low-income populations, and calculations can be found in	ich is below 50% and is below the 125% COC
Will the prossing a Busing s a Conce	n of People, Businesses or I oposed action result in the rela- cess Information Survey (BIS) reptual Stage Relocation Study relocation coordination been in relocations: Residence	ocation of people, businesses or farm equired? (CSRS) required? nitiated for this project?	Yes         No           X         X           X         X           X         X   Farms: 0 Other: 0
	CSRS is required, discuss the		
Remarks:	No relocations of people, b	usinesses, or farms will take place as	s a result of this project.
SECTION	I H – HAZARDOUS MATE	RIALS & REGULATED SUBSTA	ANCES
Red Flag I Phase I Er Phase II E	s Materials & Regulated Substruction Survivonmental Site Assessment	(Phase I ESA) t (Phase II ESA) equired?	Documentation  X
ES Reviev	v of Investigations	No Yes/ Date September 19, 2019	
	mmary of findings for each in Based on a review of GIS a September 19, 2019 by IN (hazmat sites) or sites invo	vestigation. and available public records, a Red F DOT (Appendix E, pages E1 to E9). No lived with regulated substances were	lag Investigation (RFI) was approved on No sites with hazardous material concerns identified in or within 0.5 mile of the project regulated substances is not required at this
This is	page 18 of 22 Project name	e: SR 62 over UNT to Otter Creek	c Date: May 15, 2020

County	Warrick	Route	SR 62	Des. No.	1702071
SECTIO	ON I - PERMITS CHECKLIST				
Permits	(mark all that apply)		Likely Required		
IDEM  SIDNR  IDNR  US Coas	orps of Engineers (404/Section10 Pendividual Permit (IP) Nationwide Permit (NWP) Regional General Permit (RGP) Pre-Construction Notification (PCN) Other Wetland Mitigation required Stream Mitigation required Section 401 WQC solated Wetlands determination Rule 5 Other Wetland Mitigation required Stream Mitigation required Stream Mitigation required Construction in a Floodway Navigable Waterway Permit Lake Preservation Permit Other Mitigation Required St Guard Section 9 Bridge Permit (Please discuss in the remarks box	below)	X X X X		
Remarks	<ul> <li>The following permits will likely be</li> <li>IDEM Individual 401 Western the permits will likely be</li> <li>be required from IDEM required.</li> <li>USACE 404 Regional (</li> </ul>	ater Quality as stream	/ Certification (WQC) – impacts exceed 300 lin	near ft. and stream mit	igation will likely be

 USACE 404 Regional General Permit (RGP): A Section 404 RGP from USACE is anticipated as impacts to UNT to Otter Creek and UNT 1 will be necessary. However, stream mitigation with the USACE will not be required as stream impacts are less than 1,500 linear ft.

Applicable recommendations provided by the IDNR and IDEM are included in the *Environmental Commitments* section of this document. If permits are found to be necessary, the conditions of the permit will be requirements of the project and will supersede these recommendations.

An early coordination letter was sent to the IDNR-DFW on November 8, 2018 (Appendix C, pages C1 to C2). The IDNR-DFW responded on December 7, 2018 (Appendix C, pages C21 to C23) stating "Formal approval by the DNR under regulatory programs administered by the Division of Water is not required for this project."

Early coordination was accomplished electronically with IDEM on November 8, 2018. They provided a standard automated response (Appendix C, pages C5 to C13) with a list of standardized recommendations and permitting requirements regarding impacts to water and biotic quality.

It is the responsibility of the project sponsor to identify and obtain all required permits.

County	Warrick	Route	SR 62	Des. No.	1702071
	_				

#### **SECTION J- ENVIRONMENTAL COMMITMENTS**

The following information should be provided below: List all commitments, name of agency/organization requesting the commitment(s) and indicating which are firm and which are for further consideration. The commitments should be numbered.

Remarks:

#### Firm:

- If the scope of work or permanent or temporary right-of-way amounts change, the INDOT Environmental Services Division (ESD) and the INDOT District Environmental Section will be contacted immediately. (INDOT ESD and INDOT Vincennes District)
- 2. It is the responsibility of the project sponsor to notify school corporations and emergency services at least two weeks prior to any construction that would block or limit access. (INDOT ESD)
- 3. Structure CV 062-087-48.79 located on SR 62 over UNT to Otter Creek has shown no evidence of use (for example, nests) by a bird species protected under the Migratory Bird Treaty Act (MBTA) during previous inspections. However, the structure is located over or near water which is preferred habitat for migratory birds. Avoidance and minimization measures must be implemented prior to the start of and during the nesting season. Nests without eggs or young should be removed prior to construction during the non-nesting season (September 8 April 30) and during the nesting season if no eggs or young are present. Nests with eggs or young cannot be removed or disturbed during the nesting season (May 1 September 7). Nests with eggs or young should be screened or buffered from active construction. Details of the required procedures are outlined in the "Potential Migratory Bird on Structure Unique Special Provision". (INDOT EWPO)
- 4. USFWS Bridge/Structure Assessment shall take place no earlier than two (2) years prior to the start of construction. If construction will begin after October 11, 2020 an inspection of the structure, by a qualified individual, must be performed. Inspection of the structure should check for presence of bats/bat indicators and/or presence of birds. The results of the inspection must indicate no signs of bats or birds. If signs of bats or birds are documented during this inspection, the INDOT District Environmental Manager must be contacted immediately. (INDOT ES)
- GENERAL AMM 1: Ensure all operators, employees, and contractors working in areas of known or presumed bat habitat are aware of all FHWA/FRA/FTA (Transportation Agencies) environmental commitments, including all applicable AMM's. (USFWS)
- 6. LIGHTING AMM 1: Direct temporary lighting away from suitable habitat during the active season. (USFWS)
- 7. TREE REMOVAL AMM 1: Modify all phases/aspects of the project (e.g., temporary work areas, alignments) to avoid tree removal. (USFWS)
- 8. TREE REMOVAL AMM 2: Apply time of year restrictions for tree removal when bats are not likely to be present, or limit tree removal to 10 or fewer trees per project at any time of year within 100 feet of existing road/rail surface and outside of documented roosting/foraging habitat or travel corridors; visual emergence survey must be conducted with no bats observed. (USFWS)
- TREE REMOVAL AMM 3: Ensure tree removal is limited to that specified in project plans and ensure that contractors understand clearing limits and how they are marked in the field (e.g., install bright colored flagging/fencing prior to any tree clearing to ensure contractors stay within clearing limits). (USFWS)
- 10. TREE REMOVAL AMM 4: Do not remove documented Indiana bat or NLEB roosts that are still suitable for roosting, or trees within 0.25 miles of roosts, or documented foraging habitat any time of year. (USFWS)

#### For Consideration:

- Do not cut any trees suitable for Indiana bat or Northern Long-eared bat roosting (greater than 3
  inches dbh, living or dead, with loose hanging bark, or with cracks, crevices, or cavities) from April 1
  through September 30. (IDNR-DFW)
- Do not excavate in the low flow area except for the placement of piers, foundations, and riprap, or removal of the old structure. (IDNR-DFW)
- Do not construct any temporary runarounds, causeways, cofferdams, pump around or stream diversion systems. (IDNR-DFW)
- 4. Use minimum average 6-inch graded riprap stone extended below the normal water level to provide habitat for aquatic organisms in the voids. (IDNR-DFW)
- 5. Plant native hardwood trees along the top of the bank and right-of way to replace the vegetation destroyed during construction. (IDNR-DFW)
- 6. Post "Do Not Mow or Spray" signs along the right-of-way. (IDNR-DFW)

This is page 20 of 22 Project name:	SR 62 over UNT to Otter Creek	Date: May 15, 2020

County Warrick Route SR 62 Des. No. 1702071

- 7. If box or pipe culverts are used, the bottoms should be buried to a minimum of 6" (or 20% of the culvert height/pipe diameter, whichever is greater up to a maximum of 2') below the stream bed elevation to allow a natural streambed to form within or under the crossing structure. Crossings should: span the entire channel; width (a minimum of 1.2 times the OHWM width); maintain the natural stream substrate within the structure; have a minimum openness ratio (height x width/length) of 0.25; and have stream depth, channel width, and water velocities during low-flow conditions that are approximate to those in the natural stream channel. (IDNR-DFW)
- 8. The new, replacement, or rehabbed structure, and any bank stabilization under the structure should not create conditions that are less favorable for wildlife passage under the structure. (IDNR-DFW)
- 9. Riprap placed at the culvert's outlet should match the outlet/invert elevation at the upstream edge of the riprap apron. Smaller stone and fines should be mixed in to match the existing stream substrate particle distribution and provide impermeability of the riprap apron/substrate, so the flow does not percolate through the voids below the riprap apron's surface. The slope of the riprap should be no steeper than 20:1 from the lip of the culvert pipe to the streambed. Riprap on the inlet side should have a slope no steeper than 5:1. (IDNR-DFW)
- 10. Riprap can be used as stream bank toe protection and placed from the toe of the bank top to the ordinary high-water mark (OHWM). From the OHWM to the top of the bank, erosion control blankets, turf reinforcement mats and other similar materials should be seeded with native plants to allow a natural, vegetated stream bank to develop. (IDNR-DFW)
- 11. Impacts to non-wetland forest of one (1) acre or more should be mitigated at a minimum 2:1 ratio. If less than one acre of non-wetland forest is removed in a rural setting, replacement should be at a 1:1 ratio based on area. Impacts to non-wetland forest under one (1) acre in an urban setting should be mitigated by planting five trees, at least 2 inches in diameter-at-breast height (dbh), for each tree which is removed that is 10 inches dbh or greater (5:1 mitigation based on the number of large trees). (IDNR-DFW)
- 12. Restrict below low-water work in streams to placement of culverts, piers, pilings and/or footings, shaping of the spill slopes around the bridge abutments, and placement of riprap. (USFWS)
- 13. Culverts should span the active stream channel, should be either embedded or a 3-sided or openarch culvert, and be installed where practicable on an essentially flat slope. When an open-bottomed culvert or arch is used in a stream, which has a good natural bottom substrate, such as gravel, cobbles and boulders, the existing substrate should be left undisturbed beneath the culvert to provide natural habitat for the aquatic community. (USFWS)
- 14. Minimize the extent of hard armor (riprap) in bank stabilization by using bioengineering techniques whenever possible. If rip rap is utilized for bank stabilization, extend it below low-water elevation to provide aquatic habitat. (USFWS)
- 15. Avoid all work within the inundated part of the stream channel (in perennial streams and larger intermittent streams) during the fish spawning season (April 1 through June 30), except for work within sealed structures such as caissons or cofferdams that were installed prior to the spawning season. No equipment shall be operated below Ordinary High-Water Mark during this time unless the machinery is within the caissons or on the cofferdams. (USFWS)
- 16. Evaluate wildlife crossings under bridge/culverts projects in appropriate situations. Suitable crossings include flat areas below bridge abutments with suitable ground cover, high water shelves in culverts, amphibian tunnels and diversion fencing. (USFWS)

This is page 21 of 22 Project name: SR 62 over UNT to Otter Creek Date: May 15, 2020

County	Warrick	Route	SR 62	Des. No.	1702071
		•		_	

#### **SECTION K-EARLY COORDINATION**

Please list the date coordination was sent and all agencies that were contacted as a part of the development of this Environmental Study. Also, include the date of their response or indicate that no response was received. INDOT and FHWA are automatically considered early coordination participants and should only be listed if a response is received.

Remarks

Early coordination letters were sent to the below listed agencies. If no response was received, it was assumed the agency did not feel the project would result in substantial impacts. Please see a copy of the early coordination letter and agencies responses in Appendix C. INDOT and FHWA are automatically considered early coordination participants and are only listed if a response is received.

The following agencies/individuals were contacted during early coordination.

Agency	Coordination Sent	Response Received	Appendix Page(s)
U.S. Fish Wildlife Service	11/8/2018	11/14/2018	C24 to C26
Natural Resources Conservation Service	11/8/2018	11/19/2018	C18
Department of the Army, Louisville District, Corps of Engineers	11/8/2018	No Response	-
National Park Service, Midwest Regional Office	11/8/2018	No Response	-
U.S. Department of Housing & Urban Development, Chicago Regional Office	11/8/2018	No Response	-
Indiana Geological Survey, Environmental Geology Section	11/8/2018	11/8/2018	C15 to C17
IDNR, Division of Fish and Wildlife	11/8/2018	1/21/2018	C21 to C23
IDEM	11/26/2018	11/27/2018	C5 to C13
INDOT Aviation Section	11/8/2018	No Response	-
INDOT, Public Hearings	11/8/2018	11/15/2018	C19 to C20
Warrick County Surveyor	11/8/2018	No Response	-
Warrick County Highway Department	11/8/2018	No Response	-
Floodplain Administrator	5/14/2019	No Response	-
IDEM, Office of Water Quality	8/21/2019	9/21/2019	C14
Evansville Metropolitan Planning Organization	12/12/2019	No Response	-

This is page 22 of 22 Project name: SR 62 over UNT to Otter Creek Date: May 15, 2020

## **Table of Appendices**

Appendix A: INDOT Supporting Documentation	
Threshold Chart	A1
Appendix B: Graphics	
Maps of the Project Area	B1
Photo Key Map	
Photographs of the Project Area	
Project Plans.	
Appendix C: Early Coordination	
Early Coordination Example Letter	C1
Early Coordination Distribution List	
Notice of Entry Letters	
Early Coordination Responses	
USFWS Official Species List	
INDOT Bat Database Email Correspondence	
USFWS Concurrence Verification Letter	
USFWS Concurrence Email for NLAA	
Bridge/Structure Assessment Form	
Bridge/Outdetdie 133633ment 1 orm	
Appendix D: Section 106 Consultation	
MPPA Determination	D1
INDOT CRO Email Correspondence	
Phase 1a Archaeological Report	
rnase ta Atchaeologicai Report	D/
Appendix E: Red Flag and Hazardous Materials	
	E1
Red Flag Investigation	EI
Annandiz E. Water Desaymon	
Appendix F: Water Resources	T:1
Wetland Delineation and Stream Identification Report	
INDOT EWPO Approval Email	F20
Appendix G: Air Quality	
	C1
Statewide Transportation Improvement Plan (STIP), approved on 07/02/19	
Evansville Metropolitan Planning Organization (TIP)	G2
Appendix H: Environmental Justice	
EJ Analysis	111
EJ Aliatysis	П1
Appendix I: Additional Studies	
Land & Water Conservation Fund Grants	T1
IDNR-DOR LWCF Property List	



## Appendix A

## INDOT Supporting Documentation

Item	Appendix Page
Threshold Chart	A1



#### **Categorical Exclusion Level Thresholds**

	PCE	Level 1	Level 2	Level 3	Level 4 <sup>1</sup>
Section 106	Falls within guidelines of Minor Projects PA	"No Historic Properties Affected"	"No Adverse Effect"	-	"Adverse Effect" Or Historic Bridge involvement <sup>2</sup>
Stream Impacts	No construction in waterways or water bodies	< 300 linear feet of stream impacts	≥ 300 linear feet of stream impacts	-	Individual 404 Permit
Wetland Impacts	No adverse impacts to wetlands	< 0.1 acre	-	< 1 acre	≥ 1 acre
Right-of-way <sup>3</sup>	Property acquisition for preservation only or none	< 0.5 acre	≥ 0.5 acre	-	-
Relocations	None	-	=	< 5	≥ 5
Threatened/Endangered Species (Species Specific Programmatic for Indiana bat & northern long eared bat)	"No Effect", "Not likely to Adversely Affect" (Without AMMs <sup>4</sup> or with AMMs required for all projects <sup>5</sup> )	"Not likely to Adversely Affect" (With any other AMMs)	-	"Likely to Adversely Affect"	Project does not fall under Species Specific Programmatic
Threatened/Endangered Species (Any other species)	Falls within guidelines of USFWS 2013 Interim Policy	"No Effect", ""Not likely to Adversely Affect"	-	-	"Likely to Adversely Affect"
Environmental Justice	No disproportionately high and adverse impacts	-	-	-	Potential <sup>6</sup>
Sole Source Aquifer	Detailed Assessment Not Required	-	-	-	Detailed Assessment
Floodplain	No Substantial Impacts	-	-	-	Substantial Impacts
Coastal Zone Consistency	Consistent	-	-	-	Not Consistent
National Wild and Scenic River	Not Present	-	-	-	Present
New Alignment	None	-	-	-	Any
Section 4(f) Impacts	None	-	-	-	Any
Section 6(f) Impacts	None	-	-	-	Any
Added Through Lane	None	-	-	-	Any
Permanent Traffic Alteration	None	-	-	-	Any
Coast Guard Permit	None	-	-	-	Any
Noise Analysis Required	No	-	-	-	Yes
Air Quality Analysis Required Approval Level	No Concurrence by INDOT District	-	-	-	Yes <sup>7</sup>
<ul><li>District Env. Supervisor</li><li>Env. Services Division</li><li>FHWA</li></ul>	Environmental or Environmental Services	Yes	Yes	Yes Yes	Yes Yes Yes

<sup>&</sup>lt;sup>1</sup>Coordinate with INDOT Environmental Services. INDOT will then coordinate with the appropriate FHWA Environmental Specialist.

<sup>&</sup>lt;sup>2</sup>Any involvement with a bridge processed under the Historic Bridge Programmatic Agreement.

<sup>&</sup>lt;sup>3</sup>Permanent and/or temporary right-of-way.

<sup>&</sup>lt;sup>4</sup>AMMs = Avoidance and Mitigation Measures.

<sup>&</sup>lt;sup>5</sup>AMMs determined by the IPAC decision key to be needed that are listed in the USFWS *User's Guide for the Range-wide Programmatic Consultation for Indiana bat and Northern long-eared bat* as "required for all projects".

<sup>&</sup>lt;sup>6</sup>Potential for causing a disproportionately high and adverse impact.

<sup>&</sup>lt;sup>7</sup>Hot Spot Analysis and/or MSAT Quantitative Emission Analysis.


<sup>\*</sup>Substantial public or agency controversy may require a higher-level NEPA document.


## Appendix B

## Graphics

Item	Appendix Page
Maps of the Project Area	B1 to B3
Photo Key Map	B4
Photographs of the Project Area	B5 to B9
Project Plans	B10 to B15











SR 62 over UNT Otter Creek Small Structure Replacement Project Warrick County, Indiana Des No. 1702071





0 25 50 100 Feet

Service Layer Credits: INDOT © 2020 Microsoft Corporation © 2020 DigitalGlobe ©CNES (2020) Distribution Airbus DS © 2020 HERE



Photo 1. Looking east down SR 62 west of the structure.



Photo 3. Looking northeast at the UNT to Otter Creek from the north side of the structure.



Photo 2. Looking west up SR 62 just west of the structure.



Photo 4. Looking northwest at a roadside ditch in the northwest quadrant of the project area.

gai consultants
transforming lideas into reality



Photo 5. Looking northeast at the northeast project quadrant. Also looking a the UNT to Otter Creek.



Photo 7. Looking east down SR 62 from the project structure.



Photo 6. Looking west down SR 62 form the project structure.



Photo 8. Looking south at the UNT to Otter Creek from the project structure.

gai consultants
transforming ideas into reality



Photo 9. Looking southeast at UNT-1 lined with riprap in the southeast quadrant.



Photo 11. Looking southwest at UNT-1 located in the southeast quadrant.



Photo 10. Looking southwest from the structure at the southwest quadrant.



Photo 12. Looking west down UNT-1 in the southeast quadrant from the UNT to Otter Creek.

gai consultants
transforming ideas into reality



Photo 13. Looking northeast from SR 62 at the UNT to Otter Creek located in the northeast quadrant.



Photo 15. Looking southwest at the structure and UNT to Otter Creek.



Photo 14. Looking northwest at the UNT to Otter creek in the northeast quadrant.



Photo 16. Looking north at the UNT to Otter Creek and the structure.

gai consultants
transforming ideas into reality



Photo 17. Looking north up the UNT to Otter Creek towards the structure.



Photo 18. Looking east down UNT-1 located in the southeast quadrant from the UNT to Otter Creek.

DDC 1ECT	DECICNATION
PROJECT	DESIGNATION
1700170	1700170
CONTRACT	1702071
R-40551	1701058
	1702072

CULVERT ASSETS			
DES. NO.	CULVERT ASSET ID	WORK TYPE	
1700170	CV 161-087-10.46	Small Structure Replacement	
1701058	CV 062-087-52.74	Small Structure Replacement	
1702071	CV 062-087-48.79	Small Structure Replacement	
1702072	CV 062-087-53.01	Small Structure Replacement	

## INDIANA DEPARTMENT OF TRANSPORTATION



# ROAD PLANS

SMALL STRUCTURE REPLACEMENTS

PROJECT NO.

1700170 P.E. 1700170 R/W 1700170 CONST.


Four small structure replacements on SR 62 and SR 161.

Des. 1702071: Located 0.29 miles west of SR 62/SR 161 west junction, in Section 33, T-5-S, R-7-W, Skelton Township, Warrick County, Indiana

Des. 1700170: Located at the SR 62/SR 161 west junction, in

Sections 33 & 34, T-5-S, R-7-W, Skelton Township, Warrick County, Indiana Des. 1701058: Located 1.52 miles west of SR 62/SR 161 east junction, in

Section 24 & 25, T-5-S, R-7-W, Skelton Township, Warrick County, Indiana



LOCATION MAP

WARRICK AND SPENCER COUNTY

TRAFFIC DATA		DES. 170	0170
A.A.D.T.	(2022)	774	V.P.D.
A.A.D.T.	(2042)	559	V.P.D.
D.H.V	(10.3%)	69	V.P.H.
DIRECTIONAL DISTRIBUTION		51.5%(EB)	%
TRUCKS		9.0%	A.A.D.T.
		9.0%	D.H.V.

<b>DESIGN</b>	DATA
DESIGN	

DESIGN DATA	
DESIGN SPEED	55 M.P.H.
PROJECT DESIGN CRITERIA	3R Non-Freeway
FUNCTIONAL CLASSIFICATION	Major Collector
RURAL/URBAN	Rural
TERRAIN	Level
ACCESS CONTROL	None

TRAFFIC DA	$\mid$ AT $\!\!\!\!/$	DES. 170	2071
A.A.D.T.	(2022)	3980	V.P.D.
A.A.D.T.	(2042)	5362	V.P.D.
D.H.V	(10.3%)	143	V.P.H.
DIRECTIONAL DISTRIBUTION		49.8%(EB)	%
TRUCKS		7.0%	A.A.D.T.
		7.0%	D.H.V.

## **DESIGN DATA**

DESIGN SPEED	55 М.Р.Н.
PROJECT DESIGN CRITERIA	3R Non-Freeway
FUNCTIONAL CLASSIFICATION	Major Collector
RURAL/URBAN	Rural
TERRAIN	Level
ACCESS CONTROL	None

TRAFFIC D	ATA			1058 2072
A.A.D.T.	(2022)		2351	V.P.D.
A.A.D.T.	(2042)		2883	V.P.D.
D.H.V	(12.3%)		317	V.P.H.
DIRECTIONAL DISTRIBUTIO	N	49.8	%(EB)	%
TRUCKS			8.0%	A.A.D.T.
			8.0%	D.H.V.

## **DESIGN DATA**

DESIGN SPEED	55 M.P.H
PROJECT DESIGN CRITERIA	3R Non-Freewa
FUNCTIONAL CLASSIFICATION	Major Collecto
RURAL/URBAN	Rura
TERRAIN	Leve
ACCESS CONTROL	None

#### DES. 1701058 0.05 MI. **GROSS LENGTH:** 0.05 MI. NET LENGTH: MAX. GRADE: <u>0.30</u> %

DES. 1702071	
GROSS LENGTH:	0.07 MI.
NET LENGTH:	0.07 MI.
MAX. GRADE:	<u>0.33</u> %

DES. 1702072	
GROSS LENGTH:	0.06 MI.
NET LENGTH:	0.06 MI.
MAX. GRADE:	<u>2.20</u> %

INDIANA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS DATED 2020 TO BE USED WITH THESE PLANS

> DESIGNATION 1700170 SURVEY BOOK SHEETS of CONTRACT PROJECT R-40551 1700170

gai consultants

317-570-6800 PHONE NUMBER PREPARED BY: GAI Consultants Inc. DATE FOR LETTING: DATE INDIANA DEPARTMENT OF TRANSPORTATION

PROJECT LOCATION SHOWN BY -WARWICK COUNTY

LONGITUDE: 38°02'24"N

LONGITUDE: 38°03'40"N

LONGITUDE: 38°02'23"N

LONGITUDE: 38°03'39"N

LATITUDE: 87°11'24"W

LATITUDE: 87°08'46"W

LATITUDE: 87°11'31"W

LATITUDE: 87°08'26"W

DES. 1700170

DES. 1701058

DES. 1702071

DES. 1702072

<u>Gas</u>	<u>Electric</u>	<b>Communications</b>
Booneville/Chandler Natural Gas 1425 N. Rockport Rd. Boonville, IN. 47601 Contact: Butch Leslie O: (812)897-2260 Contact: John Lewellyn O: (812)897-2260 Vectren Distribution Contact: Shelby Williams O: (812) 228-7631	Southern Indiana Power P.O. Box 219 Tell City, IN. 47586 Contact: Dale Kaufman O: (812) 547-2316  Vectren Distribution Contact: Jefferson Jackson O: (812) 204-9095 Contact: Shelby Williams O: (812) 228-7631	At&t Distribution 134 NW 6th St. Evansville, IN 47601 Contact: Jeremy Hile O: (812) 464-6055 Contact: Matt Spindler O: (317) 265-3050
Vectren Transmission Contact: Nathan Winkley O: (317) 718-3631	Vectren Transmission Contact: Jackson Traylor O: (812) 213-6022	
Water	Other	
Veolia Water - City of Boonville Water 117 E. Locust Street Boonville, IN. 47601 Contact: Shawn Wright O: (812) 897-2118 Contact: Jill Car O: (317) 263-6446	Town of Tennyson 112 N. Main Street Tennyson, IN. 47637 Contact: Sara Adams O: (812) 567-8816 Contact: Robert Fisher O: (812) 641-6400	


SHEET NO.	DATE	REVISED
·		

# **GENERAL NOTES**

All earth shoulder and cut and fill slopes shall be plain or mulch seeded except where sodding is specified.


The plans show some of the utilities located within the limits of the contract according to information obtained from the various utility companies. The accuracy of the plans in this respect is not guaranteed by GAI Consultants Inc.


INDEX		
SHEET NO.	DRAWINGS INDEX	
1	TITLE SHEET	
2	INDEX AND GENERAL NOTES	
3	TYPICAL CROSS SECTIONS	
4 - 6	MAINTENANCE OF TRAFFIC	
7 - 11	PLAN AND PROFILE	
12 - 15	CULVERT DETAIL	
16 - 36	CROSS SECTIONS	







RECOMMENDED FOR APPROVAL	DESIGN ENGINEER DAT	Ē
DESIGNED: ARW	DRAWN: KTH	_
CHECKED: BWC	CHECKED: BWC	_











WING	TOP ELEV. 1	TOP ELEV. 2	BOT. ELEV. 3	AREA (SF)
"A"	389.00	389.00	377.50	X
"B"	389.00	385.00	377.50	х
"C"	389.30	388.68	377.80	х
"D"	389.30	386.50	377.80	Х



WINGWALL LAYOUT DETAIL
Scale: NTS



Limits of Pavement removal and new full depth pavement varies by trench depth. approximately 25' for Structure 100.
 Tc varies 0.9' to 1.1' (assuming 12" Pavement Depth)

REINFORCED CONCRETE BOX STRUCTURE 59'-0" LONG AT 14' SPAN x 8' RISE 24'-0" CLEAR ROADWAY 0.03 miles west of SR 161 WARRICK COUNTY, IN.

W MILL & OVERLAY (See Typical Section)

gai consultants

RECOMMENDED FOR APPROVAL	INDIANA DEPARTMENT OF TRANSPORTATION	SCALE  1" = 10'  VERTICAL SCALE  1" = 2'	ASSET NUMBER CV 062-087-48.79 DESIGNATION 1702071
DESIGNED: ARW DRAWN: KTH	GENERAL PLAN	SURVEY BOOK	SHEETS 12 of 37
CHECKED: BWC CHECKED: BWC	STRUCTURE 100	CONTRACT R-40551	PROJECT 1700170

# Appendix C

# Early Coordination

Item	Appendix Page
Early Coordination Example Letter	C1 to C2
Early Coordination Distribution List	C3
Notice of Survey Example Letter	C4
Response – IDEM	C5 to C13
Response – IDEM Wellhead	C14
Response – Indiana Geological Survey	C15 to C17
Response – NRCS	C18
Response – INDOT PI	C19 to C20
Response – IDNR	C21 to C23
Response – USFWS	C24 to C26
USFWS Official Species List (IPaC)	C27 to C32
INDOT Bat Database Email Correspondence	C33 to C34
USFWS Concurrence Verification Letter	C35 to C49
INDOT Concurrence Email for NLAA	C50 to C52
Bridge/Structure Assessment Form	C53 to C54





November 08, 2018

GAI Project No. D180014.07

### SAMPLE EC LETTER

Early Coordination
Designation No. 1702071
SR 62 over UNT Otter Creek
Small Structure Replacement with Bridge
Warrick County, Indiana

Dear Interested Agency:

The Indiana Department of Transportation (INDOT) and Federal Highway Administration (FHWA) intends to proceed to rehabilitate the structure carrying State Road (SR) 62 over Otter Creek (CV 062-087-48.79) located in Warrick County, Indiana. This letter is part of the early coordination phase of the environmental review process. We are requesting comments from your area of expertise regarding any possible environmental effects associated with this project. Please use the above designation number and description in your reply. We will incorporate your comments into a study of the project's environmental impacts.

This project is located on SR 62, approximately 4.79 miles east of SR 61 in Section 33 of Township 5 South, Range 7 West, as shown on the De Gonia Springs USGS 7.5 Minute Topographic Map. The existing culvert is a 14ft. span by 6.2ft. rise slab top that is approximately 30ft. in length. The existing structure is showing signs of exposed rebar, minor section loss, and efflorescence. As the project is currently proposed, there are three replacement options being considered and they are:

Option #1: 14' x 8' RCB

• Option #2: 14' x 8' 3-Sided Flat Top

Option #3: 14' x 8' 3-Sided Arch Top

In order to maintain a low structure elevation and to avoid a grade raise, these options would need to be sumped 18 inches. Class 1 revetment riprap would need to be placed at the structure outlet as a scour countermeasure. No tree removal is expected to occur as part of this project. No right-of-way is expected to be required for this project. The project limits will extend approximately 300ft. along SR 62. No relocations will be required to complete this project as it is proposed.

A Red Flag Investigation is currently being performed to determine items of concern within the project area. Land use in the vicinity is primarily rural residential and agricultural fields. A Wetland Delineation/Determination and Waters of the United States investigation will be conducted in accordance with the 1987 United States Army Corps of Engineers (USACE) Corps of Engineers Wetlands Delineation Manual (1987) and the Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Midwest Region (Version 2.0, USACE, 2010) and coordinated with the INDOT Ecology & Permits Office. The Range-Wide Programmatic Informal Consultation process using "USFWS's IPaC System for Listed Bat Consultation for INDOT Projects" will be completed. This will be used to evaluate potential impacts to the Indiana Bat and the Northern Long-Eared Bat.

In regard to Section 106, coordination with INDOT Vincennes District and INDOT Cultural Resource Office (CRO) will occur. This project will be evaluated under the Minor Projects Programmatic Agreement (MPPA) between INDOT, FHWA, State Historic Preservation Officer (SHPO), and the Advisory Council on Historic Preservation. If this project is determined to be outside of the MPPA, as the Section 106 process advances, the project area will be surveyed by individuals satisfying the Secretary of the Interior Professional Qualification Standards to determine an area of potential effect (APE), make recommendations on eligibility determinations and assess effects on potential historic resources. Additionally, the project area will be subjected to an archaeological reconnaissance by a qualified archaeologist. Coordination with the SHPO and the identified consulting parties will be ongoing for the duration of the Section 106 process.

Should we not receive your response **within thirty (30) calendar days** from the date of this letter, it will be assumed that your agency or organization feels that there will be no adverse effects incurred as a result of the proposed project. However, should you find that an extension to the response time is necessary; a reasonable extension may be granted upon request.

Project location maps and photo documentation are attached. If you have any questions regarding this matter, please contact me at <a href="mailto:h.ford@gaiconsultants.com">h.ford@gaiconsultants.com</a> or (317) 436-9142.

Sincerely,

**GAI Consultants, Inc.** 

Harlan Ford

Senior Environmental Specialist

Enc.: Project Location Maps, Photo Documentation

Project Location Maps and Photo Documentation have been removed and included in Appendix B to avoid duplication.

SR 62 over UNT Otter Creek Bridge Rehabilitation Project Des. No. 1702071

#### **Agencies Receiving Early Coordination Packet:**

Distributed on November 8, 2018

Mr. Scott Pruitt, Field Supervisor U.S. Fish and Wildlife Service Indiana Field Office 620 S. Walker Street Bloomington, Indiana 47403 Attn: Ms. Robin McWilliams Robin\_McWillimas@fws.gov

Mr. Rick Neilson, State Conservationist Natural Resources Conservation Service 6013 Lakeside Boulevard Indianapolis, IN 46278 Rick.neilson@in.usda.gov

Ms. Nancy Hasenmueller, Section Head Indiana Geological Survey, Environmental Geology 611 North Walnut Grove Bloomington, IN 47405 IGSenvir@indiana.edu https://igs.indiana.edu/eAssessment/ (Website Submittal)

Mr. Adam French, Development Specialist IN Dept. of Transportation, Aviation Division 100 North Senate Avenue, Rm N955, IGCN Indianapolis, IN 46204 afrench2@indot.in.gov

Regional Environmental Coordinator National Park Service, Midwest Regional Office 601 Riverfront Drive Omaha, NE 68102

Mr. Antonio Johnson
Planning & Enviornmental Specialist
Federal Highway Administration, Indiana Division
Federal Office Building, Room 254
575 North Pennsylvania Street,
Indianapolis, IN 46204
Antonio.Johnson@dot.gov

Ms. Christie Stanifer, Environmental Coordinator IN Dept. of Natural Resources Division of Water, Fish & Wildlife Unit 402 West Washington Street, Rm W273, IGCS Indianapolis, IN 46204 environmentalreview@dnr.in.gov

Field Environmental Officer U.S. Dept. of Housing & Urban Development Chicago Regional Office, Metcalf Fed. Bldg. 77 West Jackson Boulevard, Room 2401 Chicago, IL 60604 Mr. Rickie Clark, Public Involvement Manager IN Dept. of Transportation
Office of Public Involvement
100 N. Senate Ave., Room N642
Indianapolis, IN 46204
rclark@indot.in.gov

Mr. Doug Shelton, Chief, Environmental Resources Department of the Army, Corps of Engineers Louisville District P.O. Box 59 Louisville, KY 40201 Attn: CEMP-P-E

IN Dept. of Environmental Management Office of Planning and Assessment http://www.in.gov/idem/5284.htm (Website Submittal)

Wellhead Proximity Determinator http://www.in.gov/idem/cleanwater/pages/wellhead/ (Website Investigation)

Mr. Alan Davis, Project Manager IN Dept. of Transportation, Vincennes District 3650 S US Highway 41 Vincennes, IN 47591 aldavis@indot.in.gov

Mr. Ernie Stoops, Environmental/Design Manager IN Dept. of Transportation, Vincennes District 3650 S US Highway 41 Vincennes, IN 47591 estoops@indot.in.gov

Warrick County Highway Department County Administration 107 W. Locust Street Courthouse, Room 208 Boonville, IN 47601

Mr. Phil Baxter, Warrick County Surveyor County Administration 107 W. Locust St. Suite 206 Courthouse Boonville, IN 47601 surveyor@warrickcounty.gov



Fishers Office 9998 Crosspoint Boulevard Suite 110 Indianapolis, Indiana 46256

August 13, 2018 GAI Project No. D180014.07

### SAMPLE NOS LETTER

Des. No. 1702071 SR 62 Culvert Replacement CV062-087-48.79 Warrick County, Boonville, Indiana

Notice of Entry for Survey Beginning August 20, 2018

#### Dear Property Owner:

Our information indicates that you own or occupy property located near the above proposed transportation project. As representatives of the Indiana Department of Transportation (INDOT), GAI Consultants, Inc., or other consultants, will be conducting field and environmental surveys in the future. It may be necessary for them to enter onto your property to complete this work. This is permitted under Indiana Code § 8-23-7-26. Anyone performing this type of work has been instructed to identify himself or herself to you, if you are available, before they enter your property. If you no longer own this property or it is currently occupied by someone else, please provide us the name of the new owner or occupant and their contact information so we can contact regarding the survey.

Please read the attached notice to inform you of what the "Notice of Entry for Survey or Investigation" means. The field survey(s) may include but is/are not limited to topographic survey including the mapping of locations of features such as trees, buildings, fences and drives, and obtaining ground elevations and geotechnical investigation. The environmental survey(s) may include but is/are not limited to archaeological investigations (which may involve the survey, testing, or excavation of identified archaeological sites), identification and mapping of wetlands and waterways, taking photographs of the area (which may include infrastructure, roads, residential properties, and commercial properties), a historical review of the properties within the vicinity of the proposed project area, evaluation of land use for completion of environmental documentation and various other environmental studies. The information we obtain from such surveys and studies is necessary for the proper planning and design of this project.

It is our sincere desire to cause you as little inconvenience as possible during these surveys. If problems arise, please contact me at b.craig@gaiconsultants.com or 317.570.6800. However, please keep in mind that **no specific information regarding this project is available at this time.** Thank you in advance for your cooperation.

Sincerely,

#### **GAI Consultants, Inc.**

Brian W. Craig

Digitally signed by Brian W. Craig

Div. Craibian W. Craibian W. Craibian

Div. Craibian W. Craibian

Div. Craibian W. Craibian

Div.

BC/SW

Enc.: Indiana Department of Transportation Notice of Entry for Survey or Investigation

# Indiana Department of Environmental Management

We Protect Hoosiers and Our Environment.

100 North Senate Avenue - Indianapolis, IN 46204 (800) 451-6027 - (317) 232-8603 - www.idem.IN.gov

INDOT Nickolas Meeks 3650 S. US Highway 41 Vincennes , IN 47591 Date GAI Consultants Inc. Harlan Ford 201 N. Illinois Street Indianapolis , IN 46204

To Engineers and Consultants Proposing Roadway Construction Projects:

RE: The Indiana Department of Transportation (INDOT) and Federal Highway Administration (FHWA) intends to proceed to rehabilitate the structure carrying State Road (SR) 62 over Otter Creek (CV 062-087-48.79) located in Warrick County, Indiana. This project is located on SR 62, approximately 4.79 miles east of SR 61 in Section 33 of Township 5 South, Range 7 West, as shown on the De Gonia Springs USGS 7.5 Minute Topographic Map. The existing culvert is a 14ft. span by 6.2ft. rise slab top that is approximately 30ft. in length. The existing structure is showing signs of exposed rebar, minor section loss, and efflorescence. As the project is currently proposed, there are three replacement options being considered and they are: • Option #1: 14' x 8' RCB • Option #2: 14' x 8' 3-Sided Flat Top • Option #3: 14' x 8' 3-Sided Arch Top In order to maintain a low structure elevation and to avoid a grade raise, these options would need to be sumped 18 inches. Class 1 revetment riprap would need to be placed at the structure outlet as a scour countermeasure. No tree removal is expected to occur as part of this project. No right-of-way is expected to be required for this project. The project limits will extend approximately 300ft. along SR 62. No relocations will be required to complete this project as it is proposed.

This letter from the Indiana Department of Environmental Management (IDEM) serves as a standardized response to enquiries inviting IDEM comments on roadway construction, reconstruction, or other improvement projects within existing roadway corridors when the proposed scope of the project is beneath the threshold requiring a formal National Environmental Policy Act-mandated Environmental Assessment or Environmental Impact Statement. As the letter attempts to address all roadway-related environmental topics of potential concern, it is possible that not every topic addressed in the letter will be applicable to your particular roadway project.

For additional information on specific roadway-related topics of interest, please visit the appropriate Web pages cited below, many of which provide contact information for persons within the various program areas who can answer questions not fully addressed in this letter. Also please be mindful that some environmental requirements may be subject to change and so each person

intending to include a copy of this letter in their project documentation packet is advised to download the most recently revised version of the letter; found at: http://www.in.gov/idem/5283.htm (http://www.in.gov/idem/5283.htm).

To ensure that all environmentally-related issues are adequately addressed, IDEM recommends that you read this letter in its entirety, and consider each of the following issues as you move forward with the planning of your proposed roadway construction, reconstruction, or improvement project:

## WATER AND BIOTIC QUALITY

1. Section 404 of the Clean Water Act requires that you obtain a permit from the U.S. Army Corps of Engineers (USACE) before discharging dredged or fill materials into any wetlands or other waters, such as rivers, lakes, streams, and ditches. Other activities regulated include the relocation, channelization, widening, or other such alteration of a stream, and the mechanical clearing (use of heavy construction equipment) of wetlands. Thus, as a project owner or sponsor, it is your responsibility to ensure that no wetlands are disturbed without the proper permit. Although you may initially refer to the U.S. Fish and Wildlife Service National Wetland Inventory maps as a means of identifying potential areas of concern, please be mindful that those maps do not depict jurisdictional wetlands regulated by the USACE or the Department of Environmental Management. A valid jurisdictional wetlands determination can only be made by the USACE, using the 1987 Wetland Delineation Manual.

USACE recommends that you have a consultant check to determine whether your project will abut, or lie within, a wetland area. To view a list of consultants that have requested to be included on a list posted by the USACE on their Web site, see USACE Permits and Public Notices (http://www.lrl.usace.army.mil/orf/default.asp) (http://www.lrl.usace.army.mil/orf/default.asp)) and then click on "Information" from the menu on the right-hand side of that page. Their "Consultant List" is the fourth entry down on the "Information" page. Please note that the USACE posts all consultants that request to appear on the list, and that inclusion of any particular consultant on the list does not represent an endorsement of that consultant by the USACE, or by IDEM.

Much of northern Indiana (Newton, Lake, Porter, LaPorte, St. Joseph, Elkhart, LaGrange, Steuben, and Dekalb counties; large portions of Jasper, Starke, Marshall, Noble, Allen, and Adams counties; and lesser portions of Benton, White, Pulaski, Kosciusko, and Wells counties) is served by the USACE District Office in Detroit (313-226-6812). The central and southern portions of the state (large portions of Benton, White, Pulaski, Kosciosko, and Wells counties; smaller portions of Jasper, Starke, Marshall, Noble, Allen, and Adams counties; and all other Indiana counties located in north-central, central, and southern Indiana) are served by the USACE Louisville District Office (502-315-6733).

Additional information on contacting these U.S. Army Corps of Engineers (USACE) District Offices, government agencies with jurisdiction over wetlands, and other water quality issues, can be found at http://www.in.gov/idem/4396.htm (http://www.in.gov/idem/4396.htm). IDEM recommends that impacts to wetlands and other water resources be avoided to the fullest extent.

- 2. In the event a Section 404 wetlands permit is required from the USACE, you also must obtain a Section 401 Water Quality Certification from the IDEM Office of Water Quality Wetlands Program. To learn more about the Wetlands Program, visit: http://www.in.gov/idem/4384.htm (http://www.in.gov/idem/4384.htm).
- 3. If the USACE determines that a wetland or other water body is isolated and not subject to Clean Water Act regulation, it is still regulated by the state of Indiana . A State Isolated Wetland permit from IDEM's Office of Water Quality (OWQ) is required for any activity that results in the discharge of dredged or fill materials into isolated wetlands. To learn more about isolated wetlands, contact the OWQ Wetlands Program at 317-233-8488.
- 4. If your project will involve over a 0.5 acre of wetland impact, stream relocation, or other large-scale alterations to water bodies such as the creation of a dam or a water diversion, you should seek additional input from the OWQ Wetlands Program staff. Consult the Web at: http://www.in.gov/idem/4384.htm (http://www.in.gov/idem/4384.htm) for the appropriate staff contact to further discuss your project.
- 5. Work within the one-hundred year floodway of a given water body is regulated by the Department of Natural Resources, Division of Water. The Division issues permits for activities regulated under the follow statutes:
  - IC 14-26-2 Lakes Preservation Act 312 IAC 11
  - IC 14-26-5 Lowering of Ten Acre Lakes Act No related code
  - IC 14-28-1 Flood Control Act 310 IAC 6-1
  - IC 14-29-1 Navigable Waterways Act 312 IAC 6
  - IC 14-29-3 Sand and Gravel Permits Act 312 IAC 6
  - IC 14-29-4 Construction of Channels Act No related code

For information on these Indiana (statutory) Code and Indiana Administrative Code citations, see the DNR Web site at: http://www.in.gov/dnr/water/9451.htm (http://www.in.gov/dnr/water/9451.htm) . Contact the DNR Division of Water at 317-232-4160 for further information.

The physical disturbance of the stream and riparian vegetation, especially large trees overhanging any affected water bodies should be limited to only that which is absolutely necessary to complete the project. The shade provided by the large overhanging trees helps maintain proper stream temperatures and dissolved oxygen for aquatic life.

- 6. For projects involving construction activity (which includes clearing, grading, excavation and other land disturbing activities) that result in the disturbance of one (1), or more, acres of total land area, contact the Office of Water Quality Watershed Planning Branch (317/233-1864) regarding the need for of a Rule 5 Storm Water Runoff Permit. Visit the following Web page
  - http://www.in.gov/idem/4902.htm (http://www.in.gov/idem/4902.htm)

To obtain, and operate under, a Rule 5 permit you will first need to develop a Construction Plan (http://www.in.gov/idem/4917.htm#constreq (http://www.in.gov/idem/4917.htm#constreq)), and as described in 327 IAC 15-5-6.5

(http://www.in.gov/legislative/iac/T03270/A00150 [PDF]

(http://www.in.gov/legislative/iac/T03270/A00150.PDF), pages 16 through 19). Before you may apply for a Rule 5 Permit, or begin construction, you must submit your Construction Plan to your county Soil and Water Conservation District (SWCD) (http://www.in.gov/isda/soil/contacts/map.html (http://www.in.gov/isda/soil/contacts/map.html)).

Upon receipt of the construction plan, personnel of the SWCD or the Indiana Department of Environmental Management will review the plan to determine if it meets the requirements of 327 IAC 15-5. Plans that are deemed deficient will require re-submittal. If the plan is sufficient you will be notified and instructed to submit the verification to IDEM as part of the Rule 5 Notice of Intent (NOI) submittal. Once construction begins, staff of the SWCD or Indiana Department of Environmental Management will perform inspections of activities at the site for compliance with the regulation.

Please be mindful that approximately 149 Municipal Separate Storm Sewer System (MS4) areas are now being established by various local governmental entities throughout the state as part of the implementation of Phase II federal storm water requirements. All of these MS4 areas will eventually take responsibility for Construction Plan review, inspection, and enforcement. As these MS4 areas obtain program approval from IDEM, they will be added to a list of MS4 areas posted on the IDEM Website at: http://www.in.gov/idem/4900.htm (http://www.in.gov/idem/4900.htm).

If your project is located in an IDEM-approved MS4 area, please contact the local MS4 program about meeting their storm water requirements. Once the MS4 approves the plan, the NOI can be submitted to IDEM.

Regardless of the size of your project, or which agency you work with to meet storm water requirements, IDEM recommends that appropriate structures and techniques be utilized both during the construction phase, and after completion of the project, to minimize the impacts associated with storm water runoff. The use of appropriate planning and site development and appropriate storm water quality measures are recommended to prevent soil from leaving the construction site during active land disturbance and for post construction water quality concerns. Information and assistance regarding storm water related to construction activities are available from the Soil and Water Conservation District (SWCD) offices in each county or from IDEM.

- 7. For projects involving impacts to fish and botanical resources, contact the Department of Natural Resources Division of Fish and Wildlife (317/232-4080) for addition project input.
- 8. For projects involving water main construction, water main extensions, and new public water supplies, contact the Office of Water Quality Drinking Water Branch (317-308-3299) regarding the need for permits.
- 9. For projects involving effluent discharges to waters of the State of Indiana, contact the Office of Water Quality Permits Branch (317-233-0468) regarding the need for a National Pollutant Discharge Elimination System (NPDES) permit.

10. For projects involving the construction of wastewater facilities and sewer lines, contact the Office of Water Quality - Permits Branch (317-232-8675) regarding the need for permits.

# **AIR QUALITY**

The above-noted project should be designed to minimize any impact on ambient air quality in, or near, the project area. The project must comply with all federal and state air pollution regulations. Consideration should be given to the following:

1. Regarding open burning, and disposing of organic debris generated by land clearing activities; some types of open burning are allowed (http://www.in.gov/idem/4148.htm) (http://www.in.gov/idem/4148.htm)) under specific conditions. You also can seek an open burning variance from IDEM.

However, IDEM generally recommends that you take vegetative wastes to a registered yard waste composting facility or that the waste be chipped or shredded with composting on site (you must register with IDEM if more than 2,000 pounds is to be composted; contact 317/232-0066). The finished compost can then be used as a mulch or soil amendment. You also may bury any vegetative wastes (such as leaves, twigs, branches, limbs, tree trunks and stumps) onsite, although burying large quantities of such material can lead to subsidence problems, later on.

Reasonable precautions must be taken to minimize fugitive dust emissions from construction and demolition activities. For example, wetting the area with water, constructing wind barriers, or treating dusty areas with chemical stabilizers (such as calcium chloride or several other commercial products). Dirt tracked onto paved roads from unpaved areas should be minimized.

Additionally, if construction or demolition is conducted in a wooded area where blackbirds have roosted or abandoned buildings or building sections in which pigeons or bats have roosted for 3-5 years precautionary measures should be taken to avoid an outbreak of histoplasmosis. This disease is caused by the fungus Histoplasma capsulatum, which stems from bird or bat droppings that have accumulated in one area for 3-5 years. The spores from this fungus become airborne when the area is disturbed and can cause infections over an entire community downwind of the site. The area should be wetted down prior to cleanup or demolition of the project site. For more detailed information on histoplasmosis prevention and control, please contact the Acute Disease Control Division of the Indiana State Department of Health at (317) 233-7272.

2. The U.S. EPA and the Surgeon General recommend that people not have long-term exposure to radon at levels above 4 pCi/L. (For a county-by-county map of predicted radon levels in Indiana, visit: http://www.in.gov/idem/4145.htm (http://www.in.gov/idem/4145.htm).)

The U.S. EPA further recommends that all homes (and apartments within three stories of ground level) be tested for radon. If in-home radon levels are determined to be 4 pCi/L, or higher, EPA recommends a follow-up test. If the second test confirms that radon levels are 4

pCi/L, or higher, EPA recommends the installation of radon-reduction measures. (For a list of qualified radon testers and radon mitigation (or reduction) specialists visit: http://www.in.gov/isdh/regsvcs/radhealth/pdfs/radon\_testers\_mitigators\_list.pdf (http://www.in.gov/isdh/regsvcs/radhealth/pdfs/radon\_testers\_mitigators\_list.pdf).) It also is recommended that radon reduction measures be built into all new homes, particularly in areas like Indiana that have moderate to high predicted radon levels.

To learn more about radon, radon risks, and ways to reduce exposure visit: http://www.in.gov/isdh/regsvcs/radhealth/radon.htm (http://www.in.gov/isdh/regsvcs/radhealth/radon.htm), http://www.in.gov/idem/4145.htm (http://www.in.gov/idem/4145.htm), or http://www.epa.gov/radon/index.html (http://www.epa.gov/radon/index.html).

3. With respect to asbestos removal: all facilities slated for renovation or demolition (except residential buildings that have (4) four or fewer dwelling units and which will not be used for commercial purposes) must be inspected by an Indiana-licensed asbestos inspector prior to the commencement of any renovation or demolition activities. If regulated asbestos-containing material (RACM) that may become airborne is found, any subsequent demolition, renovation, or asbestos removal activities must be performed in accordance with the proper notification and emission control requirements.

If no asbestos is found where a renovation activity will occur, or if the renovation involves removal of less than 260 linear feet of RACM off of pipes, less than 160 square feet of RACM off of other facility components, or less than 35 cubic feet of RACM off of all facility components, the owner or operator of the project does not need to notify IDEM before beginning the renovation activity.

For questions on asbestos demolition and renovation activities, you can also call IDEM's Lead/Asbestos section at 1-888-574-8150.

However, in all cases where a demolition activity will occur (even if no asbestos is found), the owner or operator must still notify IDEM 10 working days prior to the demolition, using the form found at http://www.in.gov/icpr/webfile/formsdiv/44593.pdf (http://www.in.gov/icpr/webfile/formsdiv/44593.pdf).

Anyone submitting a renovation/demolition notification form will be billed a notification fee based upon the amount of friable asbestos containing material to be removed or demolished. Projects that involve the removal of more than 2,600 linear feet of friable asbestos containing materials on pipes, or 1,600 square feet or 400 cubic feet of friable asbestos containing material on other facility components, will be billed a fee of \$150 per project; projects below these amounts will be billed a fee of \$50 per project. All notification remitters will be billed on a quarterly basis.

For more information about IDEM policy regarding asbestos removal and disposal, visit: http://www.in.gov/idem/4983.htm (http://www.in.gov/idem/4983.htm).

4. With respect to lead-based paint removal: IDEM encourages all efforts to minimize human exposure to lead-based paint chips and dust. IDEM is particularly concerned that young

children exposed to lead can suffer from learning disabilities. Although lead-based paint abatement efforts are not mandatory, any abatement that is conducted within housing built before January 1, 1978, or a child-occupied facility is required to comply with all lead-based paint work practice standards, licensing and notification requirements. For more information about lead-based paint removal visit: http://www.in.gov/isdh/19131.htm (http://www.in.gov/isdh/19131.htm).

- 5. Ensure that asphalt paving plants are permitted and operate properly. The use of cutback asphalt, or asphalt emulsion containing more than seven percent (7%) oil distillate, is prohibited during the months April through October. See 326 IAC 8-5-2, Asphalt Paving Rule (http://www.ai.org/legislative/iac/T03260/A00080.PDF (http://www.ai.org/legislative/iac/T03260/A00080.PDF)).
- 6. If your project involves the construction of a new source of air emissions or the modification of an existing source of air emissions or air pollution control equipment, it will need to be reviewed by the IDEM Office of Air Quality (OAQ). A registration or permit may be required under 326 IAC 2 (View at: www.ai.org/legislative/iac/t03260/a00020.pdf (http://www.ai.org/legislative/iac/t03260/a00020.pdf).) New sources that use or emit hazardous air pollutants may be subject to Section 112 of the Clean Air Act and corresponding state air regulations governing hazardous air pollutants.
- 7. For more information on air permits visit: http://www.in.gov/idem/4223.htm (http://www.in.gov/idem/4223.htm), or to initiate the IDEM air permitting process, please contact the Office of Air Quality Permit Reviewer of the Day at (317) 233-0178 or OAMPROD atdem.state.in.us.

# LAND QUALITY

In order to maintain compliance with all applicable laws regarding contamination and/or proper waste disposal, IDEM recommends that:

- 1. If the site is found to contain any areas used to dispose of solid or hazardous waste, you need to contact the Office of Land Quality (OLQ)at 317-308-3103.
- 2. All solid wastes generated by the project, or removed from the project site, need to be taken to a properly permitted solid waste processing or disposal facility. For more information, visit http://www.in.gov/idem/4998.htm (http://www.in.gov/idem/4998.htm).
- 3. If any contaminated soils are discovered during this project, they may be subject to disposal as hazardous waste. Please contact the OLQ at 317-308-3103 to obtain information on proper disposal procedures.
- 4. If PCBs are found at this site, please contact the Industrial Waste Section of OLQ at 317-308-3103 for information regarding management of any PCB wastes from this site.
- 5. If there are any asbestos disposal issues related to this site, please contact the Industrial Waste Section of OLQ at 317-308-3103 for information regarding the management of asbestos wastes (Asbestos removal is addressed above, under Air Quality).

6. If the project involves the installation or removal of an underground storage tank, or involves contamination from an underground storage tank, you must contact the IDEM Underground Storage Tank program at 317/308-3039. See: http://www.in.gov/idem/4999.htm (http://www.in.gov/idem/4999.htm).

## FINAL REMARKS

Should you need to obtain any environmental permits in association with this proposed project, please be mindful that IC 13-15-8 requires that you notify all adjoining property owners and/or occupants within ten days your submittal of each permit application. However, if you are seeking multiple permits, you can still meet the notification requirement with a single notice if all required permit applications are submitted with the same ten day period.

Should the scope of the proposed project be expanded to the extent that a National Environmental Policy Act Environmental Assessment (EA) or Environmental Impact Statement (EIS) is required, IDEM will actively participate in any early interagency coordination review of the project.

Meanwhile, please note that this letter does not constitute a permit, license, endorsement or any other form of approval on the part of the Indiana Department of Environmental Management regarding any project for which a copy of this letter is used. Also note that is it the responsibility of the project engineer or consultant using this letter to ensure that the most current draft of this document, which is located at http://www.in.gov/idem/5284.htm (http://www.in.gov/idem/5284.htm), is used.

# Signature(s) of the Applicant

I acknowledge that the following proposed roadway project will be financed in part, or in whole, by public monies.

# **Project Description**

The Indiana Department of Transportation (INDOT) and Federal Highway Administration (FHWA) intends to proceed to rehabilitate the structure carrying State Road (SR) 62 over Otter Creek (CV 062-087-48.79) located in Warrick County, Indiana. This project is located on SR 62, approximately 4.79 miles east of SR 61 in Section 33 of Township 5 South, Range 7 West, as shown on the De Gonia Springs USGS 7.5 Minute Topographic Map. The existing culvert is a 14ft. span by 6.2ft. rise slab top that is approximately 30ft. in length. The existing structure is showing signs of exposed rebar, minor section loss, and efflorescence. As the project is currently proposed, there are three replacement options being considered and they are: • Option #1: 14′ x 8′ RCB • Option #2: 14′ x 8′ 3-Sided Flat Top • Option #3: 14′ x 8′ 3-Sided Arch Top In order to maintain a low structure elevation and to avoid a grade raise, these options would need to be sumped 18 inches. Class 1 revetment riprap would need to be placed at the structure outlet as a scour countermeasure. No

tree removal is expected to occur as part of this project. No right-of-way is expected to be required for this project. The project limits will extend approximately 300ft. along SR 62. No relocations will be required to complete this project as it is proposed.

With my signature, I do hereby affirm that I have read the letter from the Indiana Department of Environment that appears directly above. In addition, I understand that in order to complete that project in which I am interested, with a minimum of impact to the environment, I must consider all the issues addressed in the aforementioned letter, and further, that I must obtain any required permits.

Date: 11/27/2018		
Signature of the INDOT Project Engineer or Other Respo	onsible Agent	
Date:11/26/18	Nickolas Meeks	
Signature of the For Hire Consultant	The Il	
	Harlan Ford	



## Indiana Department of Environmental Management

We Protect Hoosiers and Our Environment.

100 N. Senate Avenue • Indianapolis, IN 46204

(800) 451-6027 • (317) 232-8603 • www.idem.IN.gov

Eric J. Holcomb Governor

**Bruno Pigott** Commissioner

September 10, 2019

66-33 **GAI Consultants** Attention: Harlan Ford 201 North Illinois Street, Suite 1700 Indianapolis, Indiana 46204

Dear Harlan Ford,

RE: Wellhead Protection Area

**Proximity Determination** 

Des No 1702071

Replacement of Culvert No. 062-087-48.79 that carries SR 62 over

UNT to Otter Creek in

Warrick County

Upon review of the above referenced project site, it has been determined that the proposed project area is not located within a Wellhead Protection Area. The information is accurate to the best of our knowledge; however, there are in some cases a few factors that could impact the accuracy of this determination. Some Wellhead Protection Area Delineations have not been submitted, and many have not been approved by this office. In these cases we use a 3,000 foot fixed radius buffer to make the proximity determination. To find the status of a Public Water Supply System's (PWSS's) Wellhead Protection Area Delineation please visit our tracking database at http://www.in.gov/idem/cleanwater/2456.htm and scroll to the bottom of the page.

Note: the Drinking Water Branch has launched a new self service feature which allows one to determine wellhead proximity without submitting the application form. Use the following instructions:

- 1. Go to http://idemmaps.idem.in.gov/whpa2/
- 2. Use the search tool located in the upper left hand corner of the application to zoom to your site of interest by way of city, county, or address; or use the mouse to click on the site of interest displayed on the map.
- 3. Once the site of interest has been located and selected, use the print tool to create a .pdf of a wellhead protection area proximity determination response.

In the future please consider using this self service feature if it is suits your needs.

If you have any additional questions please feel free to contact me at the address above or at (317) 233-9158 and aturnbow@idem.in.gov.

Sincerely.

Alisha Turnbow,

Environmental Manager, Ground Water Section, Drinking Water Branch, Office of

Water Quality



## **Organization and Project Information**

**Project ID:** 1702071 Des. ID: 1702071

**Project Title:** Sr 62 over UNT to Otter Creek

Name of Organization: GAI Consultants Inc.

Requested by: Harlan Ford

# **Environmental Assessment Report**

- 1. Geological Hazards:
  - High liquefaction potential
  - 1% Annual Chance Flood Hazard
- 2. Mineral Resources:
  - Bedrock Resource: High Potential
  - Sand and Gravel Resource: None documented in the area
- 3. Active or abandoned mineral resources extraction sites:
  - None documented in the area

#### **DISCLAIMER:**

This document was compiled by Indiana University, Indiana Geological Survey, using data believed to be accurate; however, a degree of error is inherent in all data. This product is distributed "AS-IS" without warranties of any kind, either expressed or implied, including but not limited to warranties of suitability to a particular purpose or use. No attempt has been made in either the design or production of these data and document to define the limits or jurisdiction of any federal, state, or local government. The data used to assemble this document are intended for use only at the published scale of the source data or smaller (see the metadata links below) and are for reference purposes only. They are not to be construed as a legal document or survey instrument. A detailed on-the-ground survey and historical analysis of a single site may differ from these data and this


This information was furnished by Indiana Geological Survey Address: 611 N. Walnut Grove Avenue, Bloomington, IN 47405-2208

Email: IGSEnvir@indiana.edu

Phone: 812 855-7428 Date: November 08, 2018

<sup>\*</sup>All map layers from Indiana Map (maps.indiana.edu)







# Metadata:

- https://maps.indiana.edu/metadata/Geology/Seismic Earthquake Liquefaction Potential.html
- https://maps.indiana.edu/metadata/Hydrology/Floodplains\_FIRM.html
- https://maps.indiana.edu/metadata/Geology/Bedrock\_Geology.html



November 14, 2018

Harlan Ford GAI Consultants 201 North Illinois Street, Suite 1700 Indianapolis, Indiana 46204

Dear Mr. Ford:

The proposed project to replace small structure on State Road 62 over an unnamed tributary to Otter Creek in Warrick County, Indiana, (Des No. 1702071) as referred in your letter received on November 8, 2018 will not cause a conversion of prime farmland.

If you need additional information, please contact Daniel Phillips at 317-295-5871.

Sincerely,

JERRY RAYNOR Digitally signed by JERRY RAYNOR Date: 2018.11.16 17:53:58 -05'00'

JERRY RAYNOR State Conservationist From: Wright, Mary < MWRIGHT@indot.IN.gov>
Sent: Thursday, November 15, 2018 12:24 PM

To: Harlan Ford

**Subject:** RE: Early Coordination Letter for Des No. 1702071

## Early Coordination and Creating a Public Involvement Plan (PIP)

We have received your early coordination notification packet for the above referenced project(s). Our office prefers to be notified at the early coordination stage in order to encourage early and ongoing public involvement aside from the specific legal requirements as outlined in our Public Involvement Manual <a href="http://www.in.gov/indot/2366.htm">http://www.in.gov/indot/2366.htm</a>. Seeking the public's understanding of transportation improvement projects early in the project development stage can allow the opportunity for the public to express their concerns, comments, and to seek buy-in. Early coordination is the perfect opportunity to examine the proposed project and its impacts to the community along with the many ways and or tools to inform the public of the improvements and seek engagement. A good public involvement plan, or PIP, should consider the type, scope, impacts, and the level of public awareness that should, or could, be implemented. In other words, although there are cases where no public involvement is legally required, sometimes it is simply the right thing to do in order to keep the public informed.

The public involvement office is always available to provide support and resources to bolster any public involvement activities you may wish to implement or discuss. Please feel free to contact our office anytime should you have any questions or concerns. Thank you for notifying our office about your proposed project. We trust you will not only analyze the appropriate public involvement required, but also consider the opportunity to do go above and beyond those requirements in creating a good PIP.

Rickie Clark, Manager 100 North Senate Avenue, Room N642 Indianapolis, IN 46204

Phone: 317-232-6601 Email: rclark@indot.in.gov

Mary Wright, Hearing Examiner

Phone: 317-234-0796

Email: mwright@indot.in.gov

From: Harlan Ford [mailto:H.Ford@gaiconsultants.com]

**Sent:** Thursday, November 08, 2018 3:05 PM **To:** Clark, Rickie < <u>RCLARK@indot.IN.gov</u>> **Cc:** Wright, Mary < <u>MWRIGHT@indot.IN.gov</u>>

**Subject:** Early Coordination Letter for Des No. 1702071

Mr. Clark,

I am contacting you today on behalf of INDOT to inform you of a upcoming project proposed by INDOT. Attached you will find an ECL packet with details concerning the project. If you have any questions or concerns with this project, please don't hesitate to contact me.

#### Thank you for your time,

#### Harlan M. Ford

**Environmental Specialist** 

**GAI Consultants**, 201 N. Illinois Street, Suite 1700, Indianapolis, IN 46204 **T** 317.570.6800 **D** 317.436.9142 **M** 423.458.5979

Facebook | LinkedIn | Twitter | YouTube | News & Insights





ENGINEERING, PLANNING, AND ENVIRONMENTAL CONSULTING SINCE 1958

GAI CONSULTANTS CONFIDENTIALITY NOTICE: This communication contains confidential information belonging to the sender and may be legally privileged. This communication is solely for the use of its intended recipient. If you are not the intended recipient, inform the sender of the error and remove this email from your system. If this transmission includes any technical information, design data, and/or recommendations, they are provided only as a matter of convenience and may not be used for final design and/or construction.

# State of Indiana DEPARTMENT OF NATURAL RESOURCES Division of Fish and Wildlife

### Early Coordination/Environmental Assessment

DNR #:

ER-21024

Request Received: November 8, 2018

Requestor:

GAI Consultants, Inc.

Harlan Ford

201 North Illinois Street

Suite 1700

Indianapolis, IN 46204

Project:

SR 62 small structure (CV# 062-087-48.79) replacement over UNT Otter Creek, about

4.79 miles east of SR 61; Des #1702071

County/Site info:

Warrick

The Indiana Department of Natural Resources has reviewed the above referenced project per your request. Our agency offers the following comments for your information and in accordance with the National Environmental Policy Act of 1969.

If our agency has regulatory jurisdiction over the project, the recommendations contained in this letter may become requirements of any permit issued. If we do not

have permitting authority, all recommendations are voluntary.

Regulatory Assessment:

Formal approval by the Department of Natural Resources under the regulatory programs administered by the Division of Water is not required for this project.

Natural Heritage Database:

The Natural Heritage Program's data have been checked.

To date, no plant or animal species listed as state or federally threatened, endangered,

or rare have been reported to occur in the project vicinity.

Fish & Wildlife Comments:

Avoid and minimize impacts to fish, wildlife, and botanical resources to the greatest extent possible, and compensate for impacts. The following are recommendations that

address potential impacts identified in the proposed project area:

1) Crossing Structure:

Option #1 will result in the most impacts to fish, wildlife, and botanical resources as it is a box culvert. We recommend option #2 or #3 as they will result in fewer impacts.

For purposes of maintaining fish and wildlife passage through a crossing structure, the Environmental Unit recommends bridges rather than culverts and bottomless culverts rather than box or pipe culverts. Wide culverts are better than narrow culverts, and culverts with shorter through lengths are better than culverts with longer through lengths. If box or pipe culverts are used, the bottoms should be buried a minimum of 6" (or 20% of the culvert height/pipe diameter, whichever is greater up to a maximum of 2') below the stream bed elevation to allow a natural streambed to form within or under the crossing structure. Crossings should: span the entire channel width (a minimum of 1.2 times the OHWM width); maintain the natural stream substrate within the structure; have a minimum openness ratio (height x width / length) of 0.25; and have stream depth, channel width, and water velocities during low-flow conditions that are approximate to those in the natural stream channel.

The new, replacement, or rehabbed structure, and any bank stabilization under the structure, should not create conditions that are less favorable for wildlife passage under the structure compared to the current conditions. Any riprap placed at the culvert's outlet should match the outlet/invert elevation at the upstream edge of the riprap apron. Smaller stone and fines should be mixed in to match the existing stream substrate particle distribution and provide impermeability of the riprap apron/substrate so the flow

# State of Indiana DEPARTMENT OF NATURAL RESOURCES Division of Fish and Wildlife

### Early Coordination/Environmental Assessment

does not percolate through the voids below the riprap apron's surface. The slope of the riprap should be no steeper than 20:1 from the lip of the culvert pipe to the streambed. Riprap on the inlet side should have a slope no steeper than 5:1. Natural streambed material should be backfilled within the structure where possible as it can provide refuge for species using the culvert. Natural bed materials such as large cobble and boulders should be placed within the structure (anchored if necessary) to provide flow diversity and roughness/energy dissipation.

Sump depth for a pipe or box culvert should be increased/adjusted to match the structure's design life according to the background rate of bed degradation/downcutting so that the culvert does not become perched long before the culvert requires replacement. Culvert width and gradient should be appropriate for the site conditions so that flows do not scour out material from the culvert. Stream simulation design should be applied with any crossing structure. Additional information is available in Publication No. FHWA-HIF-11-008, Federal Highway Administration, Culvert Design for Aquatic Organism Passage, October 2010 (http://www.fhwa.dot.gov/engineering/hydraulics/pubs/11008/hif11008.pdf).

If riprap is placed within the structure to protect the footings, it should not extend from the edge of the structure more than 3 feet on each side.

#### 2) Bank Stabilization:

Minimize the use of riprap in the channel and use alternative erosion protection materials whenever possible. Bioengineered bank stabilization methods should be used on the bank slopes (see

http://directives.sc.egov.usda.gov/OpenNonWebContent.aspx?content=17553.wba). Riprap can be used as stream bank toe protection and placed from the toe of the bank up to the ordinary high water mark (ohwm). From the ohwm to the top of the bank, erosion control blankets or turf reinforcement mats should be used. Erosion control blankets, turf reinforcement mats and other similar materials should be seeded with native plants to allow a natural, vegetated stream bank to develop.

#### 3) Riparian Habitat:

We recommend a mitigation plan be developed for any unavoidable habitat impacts that will occur. The DNR's Floodway Habitat Mitigation guidelines (and plant lists) can be found online at: http://www.in.gov/legislative/iac/20140806-IR-312140295NRA.xml.pdf.

Impacts to non-wetland forest of one (1) acre or more should be mitigated at a minimum 2:1 ratio. If less than one acre of non-wetland forest is removed in a rural setting, replacement should be at a 1:1 ratio based on area. Impacts to non-wetland forest under one (1) acre in an urban setting should be mitigated by planting five trees, at least 2 inches in diameter-at-breast height (dbh), for each tree which is removed that is 10" dbh or greater (5:1 mitigation based on the number of large trees). Impacts to wetland habitat should be mitigated at the appropriate ratio according to the 1991 INDOT/IDNR/USFWS Memorandum of Understanding.

The mitigation site should be located in the floodway, downstream of the one (1) square mile drainage area of that stream (or another stream within the 8-digit HUC, preferably as close to the impact site as possible) and adjacent to existing forested riparian habitat.

The additional measures listed below should be implemented to avoid, minimize, or compensate for impacts to fish, wildlife, and botanical resources:

1. Revegetate all bare and disturbed areas in the floodway with a mixture of native grasses, sedges, wildflowers, and also native hardwood trees and shrubs as soon as possible upon completion. Do not use any varieties of Tall Fescue or other non-native

#### State of Indiana DEPARTMENT OF NATURAL RESOURCES Division of Fish and Wildlife

### Early Coordination/Environmental Assessment

plants (e.g. crown-vetch).

- 2. Minimize and contain within the project limits inchannel disturbance and the clearing of trees and brush.
- 3. Do not work in the waterway from April 1 through June 30 without the prior written approval of the Division of Fish and Wildlife.
- 4. Do not cut any trees suitable for Indiana bat or Northern Long-eared bat roosting (greater than 3 inches dbh, living or dead, with loose hanging bark, or with cracks, crevices, or cavities) from April 1 through September 30.
- 5. Do not excavate in the low flow area except for the placement of piers, foundations, and riprap, or removal of the old structure.
- 6. Do not construct any temporary runarounds, causeways, cofferdams, pump around or stream diversion systems.
- 7. Use minimum average 6 inch graded riprap stone extended below the normal water level to provide habitat for aquatic organisms in the voids.
- 8. Plant native hardwood trees along the top of the bank and right-of-way to replace the vegetation destroyed during construction.
- 9. Post "Do Not Mow or Spray" signs along the right-of-way.
- 10. Appropriately designed measures for controlling erosion and sediment must be implemented to prevent sediment from entering the stream or leaving the construction site; maintain these measures until construction is complete and all disturbed areas are stabilized.
- 11. Seed and protect all disturbed streambanks and slopes not protected by other methods that are 3:1 or steeper with erosion control blankets that are heavy-duty, biodegradable, and net free or that use loose-woven / Leno-woven netting to minimize the entrapment and snaring of small-bodied wildlife such as snakes and turtles (follow manufacturer's recommendations for selection and installation); seed and apply mulch on all other disturbed areas.

**Contact Staff:** 

Christie L. Stanifer, Environ. Coordinator, Fish & Wildlife Our agency appreciates this opportunity to be of service. Please contact the above staff member at (317) 232-4080 if we can be of further assistance.

Christie L. Stanifer Environ. Coordinator

Division of Fish and Wildlife

Date: December 7, 2018

From: McWilliams, Robin < robin\_mcwilliams@fws.gov>
Sent: Wednesday, November 14, 2018 10:25 AM

To: Harlan Ford

Subject: Re: [EXTERNAL] Early Coordination Letter for Des No. 1702071

Attachments: image001.png

Follow Up Flag: Follow up Flag Status: Flagged

Dear Harlan,

This responds to your recent letter, requesting our comments on the aforementioned project.

These comments have been prepared under the authority of the Fish and Wildlife Coordination Act (I6 U.S.C. 661 et. seq.) and are consistent with the intent of the National Environmental Policy Act of I969, the Endangered Species Act of I973, and the U.S. Fish and Wildlife Service's Mitigation Policy.

The project is within the range of the Indiana bat (*Myotis sodalis*) and northern long-eared bat (*Myotis septentrionalis*) and should follow the new Indiana bat/northern long-eared bat programmatic consultation process, if applicable (*i.e.* a federal transportation nexus is established). We will review that information once it is received.

Based on a review of the information you provided, the U.S. Fish and Wildlife Service has no objections to the project as currently proposed. However, should new information arise pertaining to project plans or a revised species list be published, it will be necessary for the Federal agency to reinitiate consultation. Standard recommendations are provided below.

We appreciate the opportunity to comment at this early stage of project planning. If project plans change such that fish and wildlife habitat may be affected, please recoordinate with our office as soon as possible. If you have any questions about our recommendations, please call (812) 334-4261 x. 207.

Sincerely, Robin McWilliams Munson

#### **Standard Recommendations:**

- 1. Do not clear trees or understory vegetation outside the construction zone boundaries. (This restriction is not related to the "tree clearing" restriction for potential Indiana Bat habitat.)
- 2. Restrict below low-water work in streams to placement of culverts, piers, pilings and/or footings, shaping of the spill slopes around the bridge abutments, and placement of riprap.

Culverts should span the active stream channel, should be either embedded or a 3-sided or open-arch culvert, and be installed where practicable on an essentially flat slope. When an open-bottomed culvert or arch is used in a stream, which has a good natural bottom substrate, such as gravel, cobbles and boulders, the existing substrate should be left undisturbed beneath the culvert to provide natural habitat for the aquatic community.

- 3. Restrict channel work and vegetation clearing to the minimum necessary for installation of the stream crossing structure.
- 4. Minimize the extent of hard armor (riprap) in bank stabilization by using bioengineering techniques whenever possible. If rip rap is utilized for bank stabilization, extend it below low-water elevation to provide aquatic habitat.
- 5. Implement temporary erosion and sediment control methods within areas of disturbed soil. All disturbed soil areas upon project completion will be vegetated following INDOT's standard specifications.
- 6. Avoid all work within the inundated part of the stream channel (in perennial streams and larger intermittent streams) during the fish spawning season (April 1 through June 30), except for work within sealed structures such as caissons or cofferdams that were installed prior to the spawning season. No equipment shall be operated below Ordinary High Water Mark during this time unless the machinery is within the caissons or on the cofferdams.
- 7. Evaluate wildlife crossings under bridge/culverts projects in appropriate situations. Suitable crossings include flat areas below bridge abutments with suitable ground cover, high water shelves in culverts, amphibian tunnels and diversion fencing.

Robin McWilliams Munson

U.S. Fish and Wildlife Service 620 South Walker Street Bloomington, Indiana 46403 812-334-4261 x. 207 Fax: 812-334-4273

Monday, Tuesday - 7:30a-3:00p Wednesday, Thursday - telework 8:30a-3:00p

On Thu, Nov 8, 2018 at 3:08 PM Harlan Ford <H.Ford@gaiconsultants.com> wrote:

Robin,

I am contacting you today on behalf of INDOT to inform you of a upcoming project proposed by INDOT. Attached you will find an ECL packet with details concerning the project. If you have any questions or concerns with this project, please don't hesitate to contact me.
Thank you for your time,
Harlan M. Ford Environmental Specialist
GAI Consultants, 201 N. Illinois Street, Suite 1700, Indianapolis, IN 46204
<b>T</b> 317.570.6800 <b>D</b> 317.436.9142 <b>M</b> 423.458.5979
Facebook   LinkedIn   Twitter   YouTube   News & Insights

GAI CONSULTANTS CONFIDENTIALITY NOTICE: This communication contains confidential information belonging to the sender and may be legally privileged. This communication is solely for the use of its intended recipient. If you are not the intended recipient, inform the sender of the error and remove this email from your system. If this transmission includes any technical information, design data, and/or recommendations, they are provided only as a matter of convenience and may not be used for final design and/or construction.



# United States Department of the Interior

#### FISH AND WILDLIFE SERVICE

Indiana Ecological Services Field Office 620 South Walker Street Bloomington, IN 47403-2121

Phone: (812) 334-4261 Fax: (812) 334-4273

http://www.fws.gov/midwest/Endangered/section7/s7process/step1.html



In Reply Refer To: December 19, 2019

Consultation Code: 03E12000-2020-SLI-0446

Event Code: 03E12000-2020-E-02110

Project Name: Des. 1702071: SR-62 over UNT to Otter Creek - Small Structure Replacement

Subject: Updated list of threatened and endangered species that may occur in your proposed

project location, and/or may be affected by your proposed project

#### To Whom It May Concern:

The attached species list identifies any federally threatened, endangered, proposed and candidate species that may occur within the boundary of your proposed project or may be affected by your proposed project. The list also includes designated critical habitat if present within your proposed project area or affected by your project. This list is provided to you as the initial step of the consultation process required under section 7(c) of the Endangered Species Act, also referred to as Section 7 Consultation.

Section 7 of the Endangered Species Act of 1973 requires that actions authorized, funded, or carried out by Federal agencies not jeopardize federally threatened or endangered species or adversely modify designated critical habitat. To fulfill this mandate, Federal agencies (or their designated non-federal representative) must consult with the Service if they determine their project "may affect" listed species or critical habitat.

Under 50 CFR 402.12(e) (the regulations that implement Section 7 of the Endangered Species Act) the accuracy of this species list should be verified after 90 days. This verification can be completed formally or informally. You may verify the list by visiting the ECOS-IPaC website <a href="http://ecos.fws.gov/ipac/">http://ecos.fws.gov/ipac/</a> at regular intervals during project planning and implementation and completing the same process you used to receive the attached list. As an alternative, you may contact this Ecological Services Field Office for updates.

Please use the species list provided and visit the U.S. Fish and Wildlife Service's Region 3 Section 7 Technical Assistance website at - <a href="http://www.fws.gov/midwest/endangered/section7/s7process/index.html">http://www.fws.gov/midwest/endangered/section7/s7process/index.html</a>. This website contains step-by-step instructions which will help you

determine if your project will have an adverse effect on listed species and will help lead you through the Section 7 process.

For all wind energy projects and projects that include installing towers that use guy wires or are over 200 feet in height, please contact this field office directly for assistance, even if no federally listed plants, animals or critical habitat are present within your proposed project or may be affected by your proposed project.

Although no longer protected under the Endangered Species Act, be aware that bald eagles are protected under the Bald and Golden Eagle Protection Act (16 U.S.C. 668 *et seq.*) and Migratory Bird Treaty Act (16 U.S.C. 703 *et seq*), as are golden eagles. Projects affecting these species may require measures to avoid harming eagles or may require a permit. If your project is near an eagle nest or winter roost area, see our Eagle Permits website at <a href="http://www.fws.gov/midwest/midwestbird/EaglePermits/index.html">http://www.fws.gov/midwest/midwestbird/EaglePermits/index.html</a> to help you determine if you can avoid impacting eagles or if a permit may be necessary.

We appreciate your concern for threatened and endangered species. Please include the Consultation Tracking Number in the header of this letter with any request for consultation or correspondence about your project that you submit to our office.

#### Attachment(s):

Official Species List

# **Official Species List**

This list is provided pursuant to Section 7 of the Endangered Species Act, and fulfills the requirement for Federal agencies to "request of the Secretary of the Interior information whether any species which is listed or proposed to be listed may be present in the area of a proposed action".

This species list is provided by:

**Indiana Ecological Services Field Office** 620 South Walker Street Bloomington, IN 47403-2121 (812) 334-4261

## **Project Summary**

Consultation Code: 03E12000-2020-SLI-0446

Event Code: 03E12000-2020-E-02110

Project Name: Des. 1702071: SR-62 over UNT to Otter Creek - Small Structure

Replacement

Project Type: TRANSPORTATION

Project Description: The project is located on SR-62 over UNT to Otter Creek, approximately

4.79 miles east of SR-61 in Skelton Township, Warrick County, Indiana. Specifically, this project is in Section 33, Township 5 South, Range 7 West, within the De Gonia U.S. Geological Survey (USGS) 7.6 Minute Topographic Map. The scope of this project includes the replacement of the of the existing culvert ( CV 062-087-48.79/ Asset Code: 93007552) with a new reinforced concrete box (RCB) culvert (14ft. span by 8 ft. rise). The existing culvert is a 14 ft. span by 6.2 ft. rise concrete slab top. The need for this project stems from the deteriorating condition of the existing culvert, which exhibits signs of delamination and spalling exposing reinforcement and severe section loss in the superstructure, in addition to cracking and efflorescence in the widening beams. The substructure exhibited map cracking and minor efflorescence at the east abutment and southeast wingwall and moderate spalling. The channel displayed minor widespread erosion. The purpose of this project is to address the deteriorating condition of the culvert carrying SR-62 over UNT to Otter Creek. Suitable summer habitat exists within the project area; however, tree trimming/clearing will be kept to the bare minimum to accommodate the new structure and regrade and realign the ditches. Approximately 0.16 acre of tree trimming/clearing is anticipated with the dominant species being cottonwood (Populus deltoids), hackberry (Celtis occidentalis), ash (Fraxinus americana), and box elder (Acer negundo). A review of the USFWS database for bat hibernacula within the 0.5 mile search radius of the project area was completed by INDOT Vincennes District on October 9, 2018. Their review did not indicate the presence of endangered bat species in or within the 0.5 mile search radius of the project area. On October 11, 2018 qualified personnel from GAI Consultants Inc. inspected the culvert for the presence of bats. The inspection did not detect any bats or signs of bats at this structure. No permanent lighting will be installed or replaced as part of this project; however, the use of temporary lighting may be needed. Existing right-ofway (ROW) ends approximately 30 ft. north from the roadway centerline and approximately 30-35 ft. south from the roadway centerline. Approximately 0.53 acre of permanent right-of-way will need to be

acquired to complete this project. Construction for this project is expected to begin in Spring of 2022.

#### **Project Location:**

Approximate location of the project can be viewed in Google Maps: <a href="https://www.google.com/maps/place/38.03979906720883N87.1919189284191W">https://www.google.com/maps/place/38.03979906720883N87.1919189284191W</a>



Counties: Warrick, IN

# **Endangered Species Act Species**

There is a total of 2 threatened, endangered, or candidate species on this species list.

Species on this list should be considered in an effects analysis for your project and could include species that exist in another geographic area. For example, certain fish may appear on the species list because a project could affect downstream species. Note that 1 of these species should be considered only under certain conditions.

IPaC does not display listed species or critical habitats under the sole jurisdiction of NOAA Fisheries<sup>1</sup>, as USFWS does not have the authority to speak on behalf of NOAA and the Department of Commerce.

See the "Critical habitats" section below for those critical habitats that lie wholly or partially within your project area under this office's jurisdiction. Please contact the designated FWS office if you have questions.

NOAA Fisheries, also known as the National Marine Fisheries Service (NMFS), is an
office of the National Oceanic and Atmospheric Administration within the Department of
Commerce.

#### **Mammals**

NAME STATUS

#### Indiana Bat *Myotis sodalis*

Endangered

There is **final** critical habitat for this species. Your location is outside the critical habitat.

Species profile: https://ecos.fws.gov/ecp/species/5949

Species survey guidelines:

https://ecos.fws.gov/ipac/guideline/survey/population/1/office/31440.pdf

#### Northern Long-eared Bat Myotis septentrionalis

Threatened

No critical habitat has been designated for this species.

This species only needs to be considered under the following conditions:

 Incidental take of the NLEB is not prohibited here. Federal agencies may consult using the 4(d) rule streamlined process. Transportation projects may consult using the programmatic process. See www.fws.gov/midwest/endangered/mammals/nleb/index.html

Species profile: https://ecos.fws.gov/ecp/species/9045

#### **Critical habitats**

THERE ARE NO CRITICAL HABITATS WITHIN YOUR PROJECT AREA UNDER THIS OFFICE'S JURISDICTION.

From: Wright, Kristy < KWright@indot.IN.gov>
Sent: Tuesday, October 9, 2018 3:21 PM
To: Harlan Ford; Meeks, Nickolas W

Cc: Falls, Ryan G

**Subject:** RE: USFWS Bat Database Check for Des No. 1702071

October 9, 2018

TO: GAI – Mr. Ford

RE: USFWS Confidential database review SR 62 at RP 48+79 Warrick DES 1702071

The search was negative for endangered bat species within 0.5 mile of the project area. Please use the following statement in your RFI report:

"A review of the USFWS database did not indicate the presence of endangered bat species in or within the 0.5 mile search radius of the project area.

The range-wide programmatic consultation for the Indiana bat and the Northern Long-eared bat will be completed according to "Using the USFWS

IPaC System for Listed Bat Consultation, for INDOT Projects, dated October 25, 2018".

Thank you. kw

#### **Kristy Wright**

Capital Program Management- Environmental Manager II

3650 South U.S. Highway 41 Vincennes, IN 47591 **Office:** (812) 895-7335

Email: kwright@indot.IN.gov



**From:** Harlan Ford [mailto:H.Ford@gaiconsultants.com]

**Sent:** Monday, October 08, 2018 9:56 AM **To:** Stoops, Ernie < <a href="mailto:ESTOOPS@indot.IN.gov">ESTOOPS@indot.IN.gov</a>

Cc: Falls, Ryan G < RFalls@indot.IN.gov >; Wright, Kristy < KWright@indot.IN.gov >

**Subject:** USFWS Bat Database Check for Des No. 1702071

\*\*\*\* This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email. \*\*\*\*

Mr. Stoops,

Per your request, attached you will find a site location topographic map and an aerial map for the project. Can you check the USFWS Database for bats within 0.5 mile of the project area and let me know the results? I have provided some additional information on the project in the below table for your reference. Please let me know if you have any questions or need anything else.

Des No.	Road	Feature Crossed	County	Long.	Lat.	Bats: Y or N
1702071	SR 62	UNT, Otter Creek	Warrick	-87.191953	38.039814	

Thanks for your time,

#### Harlan M. Ford

**Environmental Specialist** 

**GAI Consultants**, 201 N. Illinois Street, Suite 1700, Indianapolis, IN 46204 **T** 317.570.6800 **D** 317.436.9142 **M** 423.458.5979

Facebook | LinkedIn | Twitter | YouTube | News & Insights





ENGINEERING, PLANNING, AND ENVIRONMENTAL CONSULTING SINCE 1958

GAI CONSULTANTS CONFIDENTIALITY NOTICE: This communication contains confidential information belonging to the sender and may be legally privileged. This communication is solely for the use of its intended recipient. If you are not the intended recipient, inform the sender of the error and remove this email from your system. If this transmission includes any technical information, design data, and/or recommendations, they are provided only as a matter of convenience and may not be used for final design and/or construction.



# United States Department of the Interior

#### FISH AND WILDLIFE SERVICE

Indiana Ecological Services Field Office 620 South Walker Street Bloomington, IN 47403-2121

Phone: (812) 334-4261 Fax: (812) 334-4273

http://www.fws.gov/midwest/Endangered/section7/s7process/step1.html



In Reply Refer To: December 20, 2019

Consultation Code: 03E12000-2020-I-0446 Event Code: 03E12000-2020-E-02130

Project Name: Des. 1702071: SR-62 over UNT to Otter Creek - Small Structure Replacement

Subject: Concurrence verification letter for the 'Des. 1702071: SR-62 over UNT to Otter Creek

- Small Structure Replacement' project under the revised February 5, 2018, FHWA, FRA, FTA Programmatic Biological Opinion for Transportation Projects within the

Range of the Indiana Bat and Northern Long-eared Bat.

To whom it may concern:

The U.S. Fish and Wildlife Service (Service) has received your request to verify that the **Des. 1702071: SR-62 over UNT to Otter Creek - Small Structure Replacement** (Proposed Action) may rely on the concurrence provided in the February 5, 2018, FHWA, FRA, FTA Programmatic Biological Opinion for Transportation Projects within the Range of the Indiana Bat and Northern Long-eared Bat (PBO) to satisfy requirements under Section 7(a)(2) of the Endangered Species Act of 1973 (ESA) (87 Stat. 884, as amended; 16 U.S.C 1531 *et seq.*).

Based on the information you provided (Project Description shown below), you have determined that the Proposed Action is within the scope and adheres to the criteria of the PBO, including the adoption of applicable avoidance and minimization measures, and may affect, but is <u>not likely to adversely affect</u> (NLAA) the endangered Indiana bat (*Myotis sodalis*) and/or the threatened Northern long-eared bat (*Myotis septentrionalis*).

The Service has 14 calendar days to notify the lead Federal action agency or designated non-federal representative if we determine that the Proposed Action does not meet the criteria for a NLAA determination under the PBO. If we do <u>not</u> notify the lead Federal action agency or designated non-federal representative within that timeframe, you may proceed with the Proposed Action under the terms of the NLAA concurrence provided in the PBO. This verification period allows Service Field Offices to apply local knowledge to implementation of the PBO, as we may identify a small subset of actions having impacts that were unanticipated. In such instances, Service Field Offices may request additional information that is necessary to verify inclusion of the proposed action under the PBO.

**For Proposed Actions that include bridge/structure removal, replacement, and/or maintenance activities:** If your initial bridge/structure assessments failed to detect Indiana bats, but you later detect bats during construction, please submit the Post Assessment Discovery of Bats at Bridge/Structure Form (User Guide Appendix E) to this Service Office. In these instances, potential incidental take of Indiana bats may be exempted provided that the take is reported to the Service.

If the Proposed Action is modified, or new information reveals that it may affect the Indiana bat and/or Northern long-eared bat in a manner or to an extent not considered in the PBO, further review to conclude the requirements of ESA Section 7(a)(2) may be required. If the Proposed Action may affect any other federally-listed or proposed species, and/or any designated critical habitat, additional consultation between the lead Federal action agency and this Service Office is required. If the proposed action has the potential to take bald or golden eagles, additional coordination with the Service under the Bald and Golden Eagle Protection Act may also be required. In either of these circumstances, please contact this Service Office.

# **Project Description**

The following project name and description was collected in IPaC as part of the endangered species review process.

#### Name

Des. 1702071: SR-62 over UNT to Otter Creek - Small Structure Replacement

#### Description

The project is located on SR-62 over UNT to Otter Creek, approximately 4.79 miles east of SR-61 in Skelton Township, Warrick County, Indiana. Specifically, this project is in Section 33, Township 5 South, Range 7 West, within the De Gonia U.S. Geological Survey (USGS) 7.6 Minute Topographic Map. The scope of this project includes the replacement of the of the existing culvert (CV 062-087-48.79/ Asset Code: 93007552) with a new reinforced concrete box (RCB) culvert (14ft. span by 8 ft. rise). The existing culvert is a 14 ft. span by 6.2 ft. rise concrete slab top. The need for this project stems from the deteriorating condition of the existing culvert, which exhibits signs of delamination and spalling exposing reinforcement and severe section loss in the superstructure, in addition to cracking and efflorescence in the widening beams. The substructure exhibited map cracking and minor efflorescence at the east abutment and southeast wingwall and moderate spalling. The channel displayed minor widespread erosion. The purpose of this project is to address the deteriorating condition of the culvert carrying SR-62 over UNT to Otter Creek. Suitable summer habitat exists within the project area; however, tree trimming/clearing will be kept to the bare minimum to accommodate the new structure and regrade and realign the ditches. Approximately 0.16 acre of tree trimming/clearing is anticipated with the dominant species being cottonwood (Populus deltoids), hackberry (Celtis occidentalis), ash (Fraxinus americana), and box elder (Acer negundo). A review of the USFWS database for bat hibernacula within the 0.5 mile search radius of the project area was completed by INDOT Vincennes District on October 9, 2018. Their review did not indicate the presence of endangered bat species in or within the 0.5 mile search radius of the project area. On October 11, 2018 qualified personnel from GAI Consultants Inc. inspected the culvert for the presence of bats. The inspection did not detect any bats or signs of bats at this structure. No permanent lighting will be installed or replaced as part of this project; however, the use of temporary lighting may be needed. Existing rightof-way (ROW) ends approximately 30 ft. north from the roadway centerline and approximately 30-35 ft. south from the roadway centerline. Approximately 0.53 acre of permanent right-of-way will need to be acquired to complete this project. Construction for this project is expected to begin in Spring of 2022.

# **Determination Key Result**

Based on your answers provided, this project(s) may affect, but is not likely to adversely affect the endangered Indiana bat and/or the threatened Northern long-eared bat, therefore, consultation with the U.S. Fish and Wildlife Service pursuant to Section 7(a)(2) of the Endangered Species Act of 1973 (ESA) (87 Stat. 884, as amended 16 U.S.C. 1531 *et seq.*) is required. However, also based on your answers provided, this project may rely on the concurrence provided in the revised February 5, 2018, FHWA, FRA, FTA Programmatic Biological Opinion for Transportation Projects within the Range of the Indiana Bat and Northern Long-eared Bat.

# **Qualification Interview**

- 1. Is the project within the range of the Indiana bat<sup>[1]</sup>?
  - [1] See Indiana bat species profile

Automatically answered

Yes

- 2. Is the project within the range of the Northern long-eared bat<sup>[1]</sup>?
  - [1] See Northern long-eared bat species profile

Automatically answered

Yes

- 3. Which Federal Agency is the lead for the action?
  - A) Federal Highway Administration (FHWA)
- 4. Are *all* project activities limited to non-construction<sup>[1]</sup> activities only? (examples of non-construction activities include: bridge/abandoned structure assessments, surveys, planning and technical studies, property inspections, and property sales)
  - [1] Construction refers to activities involving ground disturbance, percussive noise, and/or lighting. No
- 5. Does the project include *any* activities that are **greater than** 300 feet from existing road/rail surfaces<sup>[1]</sup>?
  - [1] Road surface is defined as the actively used [e.g. motorized vehicles] driving surface and shoulders [may be pavement, gravel, etc.] and rail surface is defined as the edge of the actively used rail ballast.

No

- 6. Does the project include *any* activities **within** 0.5 miles of a known Indiana bat and/or NLEB hibernaculum<sup>[1]</sup>?
  - [1] For the purpose of this consultation, a hibernaculum is a site, most often a cave or mine, where bats hibernate during the winter (see suitable habitat), but could also include bridges and structures if bats are found to be hibernating there during the winter.

No

7. Is the project located **within** a karst area?

No

- 8. Is there *any* suitable<sup>[1]</sup> summer habitat for Indiana Bat or NLEB **within** the project action area<sup>[2]</sup>? (includes any trees suitable for maternity, roosting, foraging, or travelling habitat)
  - [1] See the Service's summer survey guidance for our current definitions of suitable habitat.
  - [2] The action area is defined as all areas to be affected directly or indirectly by the Federal action and not merely the immediate area involved in the action (50 CFR Section 402.02). Further clarification is provided by the national consultation FAQs.

Yes

- 9. Will the project remove *any* suitable summer habitat<sup>[1]</sup> and/or remove/trim any existing trees **within** suitable summer habitat?
  - [1] See the Service's <u>summer survey guidance</u> for our current definitions of suitable habitat. *Yes*
- 10. Will the project clear more than 20 acres of suitable habitat per 5-mile section of road/rail? *No*

- 11. Have presence/probable absence (P/A) summer surveys<sup>[1][2]</sup> been conducted<sup>[3][4]</sup> **within** the suitable habitat located within your project action area?
  - [1] See the Service's <u>summer survey guidance</u> for our current definitions of suitable habitat.
  - [2] Presence/probable absence summer surveys conducted within the fall swarming/spring emergence home range of a documented Indiana bat hibernaculum (contact local Service Field Office for appropriate distance from hibernacula) that result in a negative finding requires additional consultation with the local Service Field Office to determine if clearing of forested habitat is appropriate and/or if seasonal clearing restrictions are needed to avoid and minimize potential adverse effects on fall swarming and spring emerging Indiana bats.
  - [3] For projects within the range of either the Indiana bat or NLEB in which suitable habitat is present, and no bat surveys have been conducted, the transportation agency will assume presence of the appropriate species. This assumption of presence should be based upon the presence of suitable habitat and the capability of bats to occupy it because of their mobility.
  - [4] Negative presence/probable absence survey results obtained using the <u>summer survey guidance</u> are valid for a minimum of two years from the completion of the survey unless new information (e.g., other nearby surveys) suggest otherwise.

No

- 12. Does the project include activities **within documented Indiana bat habitat**<sup>[1][2]</sup>?
  - [1] Documented roosting or foraging habitat for the purposes of this consultation, we are considering documented habitat as that where Indiana bats and/or NLEB have actually been captured and tracked using (1) radio telemetry to roosts; (2) radio telemetry biangulation/triangulation to estimate foraging areas; or (3) foraging areas with repeated use documented using acoustics. Documented roosting habitat is also considered as suitable summer habitat within 0.25 miles of documented roosts.)
  - [2] For the purposes of this key, we are considering documented corridors as that where Indiana bats and/or NLEB have actually been captured and tracked to using (1) radio telemetry; or (2) treed corridors located directly between documented roosting and foraging habitat.

No

13. Will the removal or trimming of habitat or trees occur within suitable but undocumented Indiana bat roosting/foraging habitat or travel corridors?
Yes

- 14. What time of year will the removal or trimming of habitat or trees **within** suitable but **undocumented Indiana bat** roosting/foraging habitat or travel corridors occur<sup>[1]</sup>?
  - [1] Coordinate with the local Service Field Office for appropriate dates.
  - B) During the inactive season
- 15. Does the project include activities **within documented NLEB habitat**<sup>[1][2]</sup>?
  - [1] Documented roosting or foraging habitat for the purposes of this consultation, we are considering documented habitat as that where Indiana bats and/or NLEB have actually been captured and tracked using (1) radio telemetry to roosts; (2) radio telemetry biangulation/triangulation to estimate foraging areas; or (3) foraging areas with repeated use documented using acoustics. Documented roosting habitat is also considered as suitable summer habitat within 0.25 miles of documented roosts.)
  - [2] For the purposes of this key, we are considering documented corridors as that where Indiana bats and/or NLEB have actually been captured and tracked to using (1) radio telemetry; or (2) treed corridors located directly between documented roosting and foraging habitat.

No

16. Will the removal or trimming of habitat or trees occur within suitable but undocumented NLEB roosting/foraging habitat or travel corridors?
Yes

- 17. What time of year will the removal or trimming of habitat or trees **within** suitable but **undocumented NLEB** roosting/foraging habitat or travel corridors occur?
  - *B)* During the inactive season
- 18. Will *any* tree trimming or removal occur **within** 100 feet of existing road/rail surfaces? *Yes*
- 19. Will the tree removal alter *any* **documented** Indiana bat or NLEB roosts and/or alter any surrounding summer habitat **within** 0.25 mile of a documented roost?
  No
- 20. Will *any* tree trimming or removal occur **between** 100-300 feet of existing road/rail surfaces?

No

21. Are *all* trees that are being removed clearly demarcated? *Yes* 

22. Will the removal of habitat or the removal/trimming of trees include installing new or replacing existing **permanent** lighting?

No

23. Does the project include wetland or stream protection activities associated with compensatory wetland mitigation?

No

24. Does the project include slash pile burning?

No

- 25. Does the project include *any* bridge removal, replacement, and/or maintenance activities (e.g., any bridge repair, retrofit, maintenance, and/or rehabilitation work)? *Yes*
- 26. Is there *any* suitable habitat<sup>[1]</sup> for Indiana bat or NLEB **within** 1,000 feet of the bridge? (includes any trees suitable for maternity, roosting, foraging, or travelling habitat)
  - [1] See the Service's current <u>summer survey guidance</u> for our current definitions of suitable habitat. *Yes*
- 27. Has a bridge assessment<sup>[1]</sup> been conducted **within** the last 24 months<sup>[2]</sup> to determine if the bridge is being used by bats?
  - [1] See <u>User Guide Appendix D</u> for bridge/structure assessment guidance
  - [2] Assessments must be completed no more than 2 years prior to conducting any work below the deck surface on all bridges that meet the physical characteristics described in the Programmatic Consultation, regardless of whether assessments have been conducted in the past. Due to the transitory nature of bat use, a negative result in one year does not guarantee that bats will not use that bridge/structure in subsequent years.

Yes

#### SUBMITTED DOCUMENTS

USFWS\_BridgeStructureAssessmentForm\_1702071 V2.pdf <a href="https://ecos.fws.gov/ipac/project/7C6ZDHS62RBWNIBNUZDLQ7HKXU/">https://ecos.fws.gov/ipac/project/7C6ZDHS62RBWNIBNUZDLQ7HKXU/</a>
 projectDocuments/19551489

28. Did the bridge assessment detect *any* signs of Indiana bats and/or NLEBs roosting in/under the bridge (bats, guano, etc.)<sup>[1]</sup>?

[1] If bridge assessment detects signs of *any* species of bats, coordination with the local FWS office is needed to identify potential threatened or endangered bat species. Additional studies may be undertaken to try to identify which bat species may be utilizing the bridge prior to allowing *any* work to proceed.

Note: There is a small chance bridge assessments for bat occupancy do not detect bats. Should a small number of bats be observed roosting on a bridge just prior to or during construction, such that take is likely to occur or does occur in the form of harassment, injury or death, the PBO requires the action agency to report the take. Report all unanticipated take within 2 working days of the incident to the USFWS. Construction activities may continue without delay provided the take is reported to the USFWS and is limited to 5 bats per project.

No

29. Will the bridge removal, replacement, and/or maintenance activities include installing new or replacing existing **permanent** lighting?

No

30. Does the project include the removal, replacement, and/or maintenance of *any* structure other than a bridge? (e.g., rest areas, offices, sheds, outbuildings, barns, parking garages, etc.)

No

31. Will the project involve the use of **temporary** lighting *during* the active season? *Yes* 

32. Is there *any* suitable habitat **within** 1,000 feet of the location(s) where **temporary** lighting will be used?

Yes

33. Will the project install new or replace existing **permanent** lighting? *No* 

34. Does the project include percussives or other activities (**not including tree removal/ trimming or bridge/structure work**) that will increase noise levels above existing traffic/background levels?

Yes

35. Will the activities that use percussives (**not including tree removal/trimming or bridge/ structure work**) and/or increase noise levels above existing traffic/background levels be conducted *during* the active season<sup>[1]</sup>?

[1] Coordinate with the local Service Field Office for appropriate dates.

Yes

36. Will *any* activities that use percussives (**not including tree removal/trimming or bridge/ structure work**) and/or increase noise levels above existing traffic/background levels be conducted *during* the inactive season<sup>[1]</sup>?

[1] Coordinate with the local Service Field Office for appropriate dates.

Yes

37. Are *all* project activities that are **not associated with** habitat removal, tree removal/ trimming, bridge and/or structure activities, temporary or permanent lighting, or use of percussives, limited to actions that DO NOT cause any additional stressors to the bat species?

Examples: lining roadways, unlighted signage, rail road crossing signals, signal lighting, and minor road repair such as asphalt fill of potholes, etc.

Yes

38. Will the project raise the road profile **above the tree canopy**?

No

39. Are the project activities that use percussives (not including tree removal/trimming or bridge/structure work) consistent with a Not Likely to Adversely Affect determination in this key?

#### Automatically answered

Yes, because the activities are within 300 feet of the existing road/rail surface, greater than 0.5 miles from a hibernacula, and conducted during the active season within undocumented habitat.

40. Are the project activities that use percussives (not including tree removal/trimming or bridge/structure work) and/or increase noise levels above existing traffic/background levels consistent with a No Effect determination in this key?

#### Automatically answered

Yes, because the activities are within 300 feet of the existing road/rail surface, greater than 0.5 miles from a hibernacula, and conducted during the inactive season

41. Is the habitat removal portion of this project consistent with a Not Likely to Adversely Affect determination in this key?

#### Automatically answered

Yes, because the tree removal/trimming that occurs outside of the Indiana bat's active season occurs greater than 0.5 miles from the nearest hibernaculum, is less than 100 feet from the existing road/rail surface, includes clear demarcation of the trees that are to be removed, and does not alter documented roosts and/or surrounding summer habitat within 0.25 miles of a documented roost.

42. Is the habitat removal portion of this project consistent with a Not Likely to Adversely Affect determination in this key?

#### Automatically answered

Yes, because the tree removal/trimming that occurs outside of the NLEB's active season occurs greater than 0.5 miles from the nearest hibernaculum, is less than 100 feet from the existing road/rail surface, includes clear demarcation of the trees that are to be removed, and does not alter documented roosts and/or surrounding summer habitat within 0.25 miles of a documented roost.

43. Is the bridge removal, replacement, or maintenance activities portion of this project consistent with a No Effect determination in this key?

#### Automatically answered

Yes, because the bridge has been assessed using the criteria documented in the BA and no signs of bats were detected

#### 44. General AMM 1

Will the project ensure *all* operators, employees, and contractors working in areas of known or presumed bat habitat are aware of *all* FHWA/FRA/FTA (Transportation Agencies) environmental commitments, including all applicable Avoidance and Minimization Measures?

Yes

#### 45. Tree Removal AMM 1

Can *all* phases/aspects of the project (e.g., temporary work areas, alignments) be modified, to the extent practicable, to avoid tree removal<sup>[1]</sup> in excess of what is required to implement the project safely?

Note: Tree Removal AMM 1 is a minimization measure, the full implementation of which may not always be practicable. Projects may still be NLAA as long as Tree Removal AMMs 2, 3, and 4 are implemented and LAA as long as Tree Removal AMMs 3, 5, 6, and 7 are implemented.

[1] The word "trees" as used in the AMMs refers to trees that are suitable habitat for each species within their range. See the USFWS' current summer survey guidance for our latest definitions of suitable habitat.

Yes

#### 46. Tree Removal AMM 3

Can tree removal be limited to that specified in project plans and ensure that contractors understand clearing limits and how they are marked in the field (e.g., install bright colored flagging/fencing prior to any tree clearing to ensure contractors stay within clearing limits)?

Yes

#### 47. Tree Removal AMM 4

Can the project avoid cutting down/removal of *all* (1) **documented**<sup>[1]</sup> Indiana bat or NLEB roosts<sup>[2]</sup> (that are still suitable for roosting), (2) trees **within** 0.25 miles of roosts, and (3) documented foraging habitat any time of year?

- [1] The word documented means habitat where bats have actually been captured and/or tracked.
- [2] Documented roosting or foraging habitat for the purposes of this consultation, we are considering documented habitat as that where Indiana bats and/or NLEB have actually been captured and tracked using (1) radio telemetry to roosts; (2) radio telemetry biangulation/triangulation to estimate foraging areas; or (3) foraging areas with repeated use documented using acoustics. Documented roosting habitat is also considered as suitable summer habitat within 0.25 miles of documented roosts.)

Yes

#### 48. Lighting AMM 1

Will *all* **temporary** lighting be directed away from suitable habitat during the active season?

Yes

# **Project Questionnaire**

1. Have you made a No Effect determination for *all* other species indicated on the FWS IPaC generated species list?

N/A

2. Have you made a May Affect determination for *any* other species on the FWS IPaC generated species list?

N/A

3. How many acres<sup>[1]</sup> of trees are proposed for removal between 0-100 feet of the existing road/rail surface?

[1] If described as number of trees, multiply by 0.09 to convert to acreage and enter that number.

0.16

4. Please describe the proposed bridge work:

Scope of work for this project includes the replacement of the existing culvert (CV 062-087-48.79). In addition, the project will include the regrading and realignment of the ditches in all four quadrants and the widening of the roadway to accommodate 4 ft. paved shoulders.

5. Please state the timing of all proposed bridge work:

Spring of 2022

6. Please enter the date of the bridge assessment:

October 11, 2018

# **Avoidance And Minimization Measures (AMMs)**

This determination key result includes the committment to implement the following Avoidance and Minimization Measures (AMMs):

**GENERAL AMM 1** 

Ensure all operators, employees, and contractors working in areas of known or presumed bat habitat are aware of all FHWA/FRA/FTA (Transportation Agencies) environmental commitments, including all applicable AMMs.

**LIGHTING AMM 1** 

Direct temporary lighting away from suitable habitat during the active season.

#### TREE REMOVAL AMM 1

Modify all phases/aspects of the project (e.g., temporary work areas, alignments) to avoid tree removal.

#### TREE REMOVAL AMM 2

Apply time of year restrictions for tree removal when bats are not likely to be present, or limit tree removal to 10 or fewer trees per project at any time of year within 100 feet of existing road/rail surface and **outside of documented** roosting/foraging habitat or travel corridors; visual emergence survey must be conducted with <u>no bats observed</u>.

#### TREE REMOVAL AMM 3

Ensure tree removal is limited to that specified in project plans and ensure that contractors understand clearing limits and how they are marked in the field (e.g., install bright colored flagging/fencing prior to any tree clearing to ensure contractors stay within clearing limits).

#### **TREE REMOVAL AMM 4**

Do not remove **documented** Indiana bat or NLEB roosts that are still suitable for roosting, or trees within 0.25 miles of roosts, or **documented** foraging habitat any time of year.

# Determination Key Description: FHWA, FRA, FTA Programmatic Consultation For Transportation Projects Affecting NLEB Or Indiana Bat

This key was last updated in IPaC on December 02, 2019. Keys are subject to periodic revision.

This decision key is intended for projects/activities funded or authorized by the Federal Highway Administration (FHWA), Federal Railroad Administration (FRA), and/or Federal Transit Administration (FTA), which may require consultation with the U.S. Fish and Wildlife Service (Service) under Section 7 of the Endangered Species Act (ESA) for the endangered **Indiana bat** (*Myotis sodalis*) and the threatened **Northern long-eared bat** (NLEB) (*Myotis septentrionalis*).

This decision key should <u>only</u> be used to verify project applicability with the Service's <u>February 5, 2018, FHWA, FRA, FTA Programmatic Biological Opinion for Transportation Projects</u>. The programmatic biological opinion covers limited transportation activities that may affect either bat species, and addresses situations that are both likely and not likely to adversely affect either bat species. This decision key will assist in identifying the effect of a specific project/activity and applicability of the programmatic consultation. The programmatic biological opinion is <u>not</u> intended to cover all types of transportation actions. Activities outside the scope of the programmatic biological opinion, or that may affect ESA-listed species other than the Indiana bat or NLEB, or any designated critical habitat, may require additional ESA Section 7 consultation.

#### **Raquel Walker**

**From:** Falls, Ryan G <RFalls@indot.IN.gov> **Sent:** Friday, December 20, 2019 9:11 AM

To: Harlan Ford

**Cc:** Wright, Kristy; Raquel Walker

**Subject:** RE: IPaC Review Request for Des No. 1702071 - nlaa

#### EXTERNAL E-MAIL MESSAGE

The document's finding of May Effect, NLAA-With AMMs for DES 1702071 has been deemed sufficient. It has been verified and submitted to USFWS for their 14 working calendar day review period. The NEPA document submittal may not occur until this review period has ended. The Official Species List, Consistency Letter, and Concurrence Verification Letter are all now immediately available for your use. It is suggested that these documents be downloaded at this time. This concludes the IPaC phase of coordination with the Vincennes environmental office.

#### **Ryan Falls**

#### Capital Program Management-Senior Environmental Manager Supervisor

Indiana Department of Transportation 3650 South US Highway 41 Vincennes, IN 47591

Office: 812-895-7326 Cell: 812-582-1387 Fax: 812-895-7474 Cisco: 14605

Email: rfalls@indot.IN.gov



From: Harlan Ford [mailto:H.Ford@gaiconsultants.com]

**Sent:** Friday, December 20, 2019 7:02 AM **To:** Falls, Ryan G <RFalls@indot.IN.gov>

Cc: Wright, Kristy <KWright@indot.IN.gov>; Raquel Walker <R.Walker@gaiconsultants.com>

Subject: RE: IPaC Review Request for Des No. 1702071 & 1st Comments

\*\*\*\* This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email. \*\*\*\*

Mr. Falls,

Thank you for your comments! I have revised the determination key based on the revisions you requested. The revised IPaC determination key is ready for your review. The IPaC record locator ID is: **168-19506815** 

Thank you!

Harlan M. Ford

**D** 317.436.9142 **M** 423.458.5979

GAI CONSULTANTS CONFIDENTIALITY NOTICE: This communication contains confidential information belonging to the sender and may be legally privileged. This communication is solely for the use of its intended recipient. If you are not the intended recipient, inform the sender of the error and remove this email from your system. If this transmission includes any technical information, design data, and/or recommendations, they are provided only as a matter of convenience and may not be used for final design and/or construction.

From: Falls, Ryan G < RFalls@indot.IN.gov > Sent: Thursday, December 19, 2019 2:33 PM
To: Harlan Ford < H.Ford@gaiconsultants.com >

Cc: Wright, Kristy <<u>KWright@indot.IN.gov</u>>; Raquel Walker <<u>R.Walker@gaiconsultants.com</u>>

Subject: RE: IPaC Review Request for Des No. 1702071 & 1st Comments

### **EXTERNAL E-MAIL MESSAGE**

Harlan Ford.

Per "Using USFWS's IPaC System for Listed Bat Consultation for INDOT Projects" (<a href="https://www.in.gov/indot/files/Using%20USFWS%20IPaC%20-%20Final.pdf">https://www.in.gov/indot/files/Using%20USFWS%20IPaC%20-%20Final.pdf</a>) available on the INDOT Policy webpage (<a href="https://www.in.gov/indot/2523.htm">https://www.in.gov/indot/2523.htm</a>) Step 3:

-Describe any temporary or permanent lighting. (if none please note for each) (must have checked with the project manager/project designer if 'No')

Your project questionnaire's tree clearing acreage does not match your description's acreage. Correct as appropriate.

Please note that IPaC will auto-generate questions based on how you answer them. Corrections will cause new or delete questions and new numbering that may differ from above. Also, the Official Species List and Consistency Letter will need to be regenerated as changes to the title and/or description do not automatically update. Once these corrections have been made, please alert me, and I can approve this project.

Thank you,

#### **Ryan Falls**

Capital Program Management-Senior Environmental Manager Supervisor

Indiana Department of Transportation 3650 South US Highway 41 Vincennes, IN 47591

Office: 812-895-7326 Cell: 812-582-1387 Fax: 812-895-7474 Cisco: 14605

Email: rfalls@indot.IN.gov



855-463-6848

From: Harlan Ford [mailto:H.Ford@gaiconsultants.com]

**Sent:** Thursday, December 19, 2019 2:02 PM **To:** Falls, Ryan G <RFalls@indot.IN.gov>

Cc: Wright, Kristy <<u>KWright@indot.IN.gov</u>>; Raquel Walker <<u>R.Walker@gaiconsultants.com</u>>

Subject: IPaC Review Request for Des No. 1702071

\*\*\*\* This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email. \*\*\*\*

Mr. Falls,

IPaC gave me a NLAA finding which I believe to be appropriate for this project. When you get the chance, can I please get you to review this determination key and let me know if you concur with the NLAA finding? You have been added as a project member in IPaC and the IPaC Record locator ID is: **168-19506815**.

Please let me know if you have any questions or need any additional information.

Thank you for your time,

#### Harlan M. Ford

**Environmental Specialist** 

**GAI Consultants**, 201 N. Illinois Street, Suite 1700, Indianapolis, IN 46204 **T** 317.570.6800 **D** 317.436.9142 **M** 423.458.5979

Facebook | LinkedIn | Twitter | YouTube | News & Insights



GAI CONSULTANTS CONFIDENTIALITY NOTICE: This communication contains confidential information belonging to the sender and may be legally privileged. This communication is solely for the use of its intended recipient. If you are not the intended recipient, inform the sender of the error and remove this email from your system. If this transmission includes any technical information, design data, and/or recommendations, they are provided only as a matter of convenience and may not be used for final design and/or construction.

# **APPENDIX D: Bridge/Structure Assessment Form**

This form will be completed and submitted to the District Environmental Manager by the Contractor prior to conducting any work below the deck surface either from the underside; from activities above that bore down to the underside; from activities that could impact expansion joints; from deck removal on bridges; or from structure demolition for bridges/structures within 1000 feet of suitable bat habitat.

DOT Project #	Water Body	Date/Time of Inspection	Within 1,000ft of suitable bat habitat (circle
Des. 1702071	UNT to Otter Creek	October 11, 2018	one) Yes No

Route	County	Federal Structure ID
SR-62	Warrick County	CV 062-087-48.79 (93007552)

If the bridge/structure is 1,000 feet or more from suitable bat habitat (e.g., an urban or agricultural area without suitable foraging habitat or corridors linking the bridge to suitable foraging habitat), check box and STOP HERE. No assessment required. 

Please submit to the U.S. Fish and Wildlife Service.

#### Areas Inspected (Check all that apply)

Bridges	Culverts/Other Structures	res Summary Info (circle all that apply)				
All vertical crevices sealed at the top and 0.5-1.25" wide & ≥4" deep	Crevices, rough surfaces or imperfections in concrete	x	Human disturbance or traffic under bridge/in culvert or at the structure	High	Low	None
All crevices >12" deep & not sealed	Spaces between walls, ceiling joists	х	Possible corridors for netting	None/poor	Marginal	Excellent
All guardrails						
All expansion joints						
Spaces between concrete end walls and the bridge deck						

Last Revised May 31, 2017

Vertical surfaces on concrete					
Ibeams					
vidence of Bats (Circle all that apply)	Presence of one or more in	ndicators is sufficient evidence that	at bats may be using the str	ucture.	
None					
/isual (e.g. survey, thermal, emergent	etc.) Guano	Staining d	lefinitively from bats		
<ul><li>Livenumber seen</li></ul>	Odor Y/N	Photo doc	cumentation Y/N		
• Deadnumber seen	Photo documenta	ation Y/N			
Photo documentation Y/N					
Audible					
		The T			
Assessment Conducted By:	Harlan Ford	Signature(s):			

#### **DOT Bat Assessment Form Instructions**

- 1. Assessments must be completed no more than 2 years prior to conducting any work below the deck surface on all bridges, regardless of whether assessments have been conducted in the past.
- 2. Any bridge/structure suspected of providing habitat for any species of bat will be removed from work schedules until such time that the DOT has coordinated with the USFWS. Additional studies may be undertaken by the DOT to determine what species may be utilizing each structure identified as supporting bats prior to allowing any work to proceed.
- 3. Any questions should be directed to the District Environmental Manager.

District Environmental Use Only: Date Received by District Environmental Manager:

Last Revised June 2017

# Appendix D

# Section 106 Consultation

Item	Appendix Page
MPPA Determination Form	D1 to D4
INDOT CRO Email Correspondence	D5 to D6
Phase 1a Archaeological Report	D7 to D8



#### Minor Projects PA Project Assessment Form - Category B Projects with Archaeology Work

**Date:** 3/26/20

**Project Designation Number:** 1702071

Route Number: SR 62

**Project Description:** Small Structure Replacement on SR62 over UNT to Otter Creek, 4.79 miles E of SR

61

The Indiana Department of Transportation (INDOT) and Federal Highway Administration (FHWA) intends to proceed to rehabilitate the structure carrying State Road (SR) 62 over UNT to Otter Creek (CV 062-087-48.79) located in Warrick County, Indiana. This project is located on SR 62, approximately 4.79 miles east of SR 61 in Section 33 of Township 5 South, Range 7 West, as shown on the De Gonia Springs USGS 7.5 Minute Topographic Map. Culvert No. 062-087-48.79 is an 14ft. span by 8ft. rise concrete slab-top box culvert that is approximately 30ft. in length. The existing culvert is showing signs of exposed rebar, minor section loss, and efflorescence and will be replaced with a new 14ft. span by 8ft. rise reinforced concrete box culvert. In addition to the culvert replacement, the project will include replacing the existing guardrails, widening of the roadway shoulders, milling and resurfacing of the existing travel lanes, placement of riprap for scour protection, and the new culvert will be sumped 18 in. The purpose of this project is to address the deteriorating conditions exhibited by the culvert carrying SR-62 over UNT to Otter Creek.

In order to maintain a low structure elevation and to avoid a grade raise, these options would need to be sumped 18 inches. Class 1 revetment riprap would need to be placed at the structure outlet as a scour countermeasure. No tree removal is expected to occur as part of this project. Approximately 0.49 acre of right-of-way is anticipated to be acquired. The project limits will extend approximately 400ft. along SR 62. No relocations will be required to complete this project as it is proposed.

Feature crossed (if applicable): UNT Otter Creek			
Township: Skelton			
City/County: Tennyson, Warrick County			
Information reviewed (please check all that apply):			
▼ General project location map ▼ USGS map ▼ Aerial photograph ▼ Interim Report			
✓ Written description of project area  ✓ General project area photos  ✓ Soil survey data			
Previously completed historic property reports  Previously completed archaeology reports			
☐ Bridge Inspection Information			

Other (please specify): SHAARD GIS; SHAARD; Google online street-view imagery; Indiana Historic Building, Bridges, and Cemeteries (IHBBC) map; Bridge Inspection Application System (BIAS); County GIS data (accessed via <a href="https://whitein.elevatemaps.io/">https://whitein.elevatemaps.io/</a>); 2010 INDOT-sponsored *Historic Bridge Inventory* (HBI); project information provided by GAI Consultant, Inc. & NS Services., dated 12/19/2019 and on file at INDOT-CRO;

Jeffery Plunkett & Stacy N. Bennet

2020 A Phase Ia Archaeological Field Reconnaissance Survey and Records Review for the Proposed Small Structure Replacement on SR 62 over UNT to Otter Creek that is approximately Located 0.29 miles West of the SR 62/SR 161 West Juncture in Skelton Civil Township, Warrick County, Indiana Des. No. 1702071. Report on file, Indiana Department of Transportation, Cultural Resources Office, Indianapolis, IN.

#### **Results of the Records Review for Above-Ground Resources:**

With regard to above-ground resources, an INDOT Cultural Resources Office (CRO) historian, who meets the Secretary of the Interior's Professional Qualification Standards as per 36 CFR Part 61, first performed a desktop review, checking the Indiana Register of Historic Sites and Structures (State Register) and National Register of Historic Places (National Register) lists for Warrick County. No listed resources are present within 0.25 mile of the project area, a distance that would serve as an adequate area of potential effects (APE), given the scope of the project and the surrounding terrain.

Warrick County does not have a hard-copy of the Indiana Historic Sites and Structures Inventory (IHSSI) available. Originally surveyed for the IHSSI in 1984--along with neighboring Gibson County--Warrick was re-surveyed in 2010. The 2010 records are only available in the Indiana State Historic Architectural and Archaeological Research Database (SHAARD) and the Indiana Historic Buildings, Bridges, and Cemeteries (IHBBC) map, as are the National Register records for the county. The information contained in these databases supersede the Interim Report hard copies. No IHSSI sites are recorded within 0.25 mile of the project.

According to the IHSSI rating system, generally properties rated "contributing" do not possess the level of historical or architectural significance necessary to be considered individually National Register eligible, although they would contribute to a historic district. If they retain material integrity, properties rated "notable" might possess the necessary level of significance after further research. Properties rated "outstanding" usually possess the necessary level of significance to be considered National Register eligible, if they retain material integrity. Historic districts identified in the IHSSI are usually considered eligible for the National Register.

Land surrounding the project area is rural, consisting of agricultural fields, a few residences, and one commercial business. Above-ground resources near the project location have approximate dates of construction that range from mid-to-late twentieth century to early twenty-first. Based on a review of online street-view imagery and aerial photography, none of these resources possess the requisite levels of material integrity or historic significance for listing in the National Register.

The subject structure (Culvert (CV) No. 062-087-48.7/NBI No. 93007552) is a concrete slabtop culvert. Based on an examination of BIAS reports and photos provided from GAI Consultants/NS Services, the structure exhibits no wood, stone, or brick structures or parts therein. In addition, there is no evidence to suggest that it possesses historical or engineering significance. Based on the available information, as summarized above, no above-ground concerns exist.

#### **Archaeology Report Author/Date:**

Stacy N. Bennet and Jeffery A. Plunkett//March 24, 2020

#### **Summary of Archaeology Investigation Results:**

An archaeological records check and Phase Ia reconnaissance survey of the project area were conducted by NS Services (Plunkett 2020). The records check found that the project area had not been previously examined for archaeological resources and that no previously recorded sites have been identified within or adjacent to it. A 1.2 acre survey area was examined through the excavation of 10 shovel probes, pedestrian survey and visual inspection of disturbed areas. No evidence for archaeological deposits was identified.

The report was reviewed by INDOT Cultural Resources personnel who meet the Secretary of the Interior's Professional Qualification Standards as per 36 CFR Part 61. It is our opinion that the report is acceptable, and we concur with the evaluations and recommendations made by NS Services (Plunkett 2020). Therefore, there are no archaeological concerns.

Does the project appear to fall under the Minor Projects PA?	yes 🖂	no 🗌
--	-------	------

#### If yes, please specify category and number (applicable conditions are highlighted):

- A-6. Repair, replacement, or upgrade of existing safety appurtenances such as guardrails, barriers, glare screens, and crash attenuators in previously disturbed soils.
- A-9. Installation, repair, or replacement of erosion control measures along roadways, waterways and bridge piers within previously disturbed soils.
- B-9. Installation, replacement, repair, lining, or extension of culverts and other drainage structures under the conditions listed below [BOTH Condition A, which pertains to Archaeological Resources, and Condition B, which pertains to Above-Ground Resources, must be satisfied]:

#### **Condition A (Archaeological Resources)**

One of the two conditions listed below must be met (EITHER Condition i or Condition ii must be satisfied):

- i. Work occurs in previously disturbed soils; OR
- ii. Work occurs in undisturbed soils and an archaeological investigation conducted by the applicant and reviewed by INDOT Cultural Resources Office determines that no National Register-listed or potentially National Register-eligible archaeological resources are present within the project area. If the archaeological investigation locates National Register-listed or potentially National Register-eligible archaeological resources, then full Section 106 review will be required. Copies of any archaeological reports prepared for the project will be provided to the DHPA and any archaeological site form information will be entered directly into the SHAARD by the applicant. The archaeological reports will also be available for viewing (by Tribes only) on INSCOPE.

#### **Condition B (Above-Ground Resources)**

One of the conditions below must be met (EITHER Condition i or Condition ii must be satisfied):

i. Work does not involve installation of a new culvert and other drainage structure, and there are no impacts to unusual features, including but not limited to historic brick or stone sidewalks, curbs or curb ramps, stepped or elevated sidewalks and retaining walls, under one of the following conditions

(Condition a, Condition b, or Condition c must be satisfied):

- a. The structure exhibits no wood, stone, or brick structures or parts therein; OR
- b. The structure exhibits only modern wood, stone, or brick structures or parts therein; OR
- c. The structure exhibits non-modern wood, stone, or brick structures or parts therein and the following conditions are met (BOTH Condition 1 AND Condition 2 must be met):
  - 1. Work does not occur adjacent to or within a National Register-listed or National Register eligible district or individual above-ground resource; *AND*
  - 2. The structure lacks sufficient integrity and/or a context that suggests it might have engineering or historical significance. Under this condition, a qualified professional (meeting the Secretary of Interior's Professional Qualification standards [48 Federal Register (FR) 44716]) must prepare an analysis and justification that the structure lacks sufficient integrity and/or a context that suggests it might have engineering or historical significance. This documentation must be reviewed and approved by INDOT Cultural Resources Office.
- ii. Work involves the installation of a new culvert and other drainage structures AND/OR there may be impacts to unusual features, including historic brick or stone sidewalks, curbs or curb ramps,

stepped or elevated sidewalks and retaining walls, under the following conditions (BOTH Condition a and Condition b must be satisfied):

- a. Work does not occur adjacent to or within a National Register-listed or National Register-eligible district or individual above-ground resource; *AND*
- b. The subject structure exhibits one of the characteristics described below (Condition 1, Condition 2 or Condition 3 must be satisfied).
  - 1. The structure exhibits no wood, stone, or brick structures or parts therein; OR
  - 2. The structure exhibits only modern wood, stone, or brick structures or parts therein; OR
  - 3. The structure exhibits non-modern wood, stone, or brick structures or parts therein but lacks sufficient integrity and/or a context that suggests it might have engineering or historical significance. Under this condition, a qualified professional (meeting the Secretary of Interior's Professional Qualification standards [48 Federal Register (FR) 44716]) must prepare an analysis and justification that the structure lacks sufficient integrity and/or a context that suggests it might have engineering or historical significance. This documentation must be reviewed and approved by INDOT Cultural Resources Office.

#### If no, please explain:

**Additional comments:** If any archaeological artifacts or human remains are uncovered during construction, demolition, or earthmoving activities, construction in the immediate area of the find will be stopped, and the INDOT Cultural Resources Office and the Division of Historic Preservation and Archaeology will be notified immediately.

#### INDOT Cultural Resources staff reviewer(s): Patricia Jo Korzeniewski and Clint Kelly

\*\*\*Be sure to attach this form to the National Environmental Policy Act documentation for this project. Also, the NEPA documentation shall reference and include the description of the specific stipulation in the PA that qualifies the project as exempt from further Section 106 review.

From: Korzeniewski, Patricia J < PKorzeniewski@indot.IN.gov>

Sent: Thursday, March 26, 2020 2:27 PM

To: Howder, Aubrey; Harlan Ford; Falls, Ryan G; Jeff Plunkett

Cc:Miller, Shaun (INDOT); Branigin, SusanSubject:RE: MPPA Submittal for Des No. 1702071Attachments:MPPA\_B-9\_A-6,A-9\_1702071\_2020\_3\_26.pdf

Follow Up Flag: Follow up Flag Status: Flagged

### **EXTERNAL E-MAIL MESSAGE**

#### Good Afternoon,

Thank you for submitting the revised archaeological short report which has been reviewed by INDOT Cultural Resources personnel who meet the Secretary of the Interior's Professional Qualification Standards as per 36 CFR Part 61. It is our opinion that the report is acceptable, and we concur with the evaluations and recommendations made by Plunkett. Please forward one hard copy and PDF of the report to DHPA, indicating in the cover letter that the project qualified as a Minor Project and therefore the report is for their records only and no formal review is required under Section 106.

Please submit both electronic and paper copies of the approved report to SHPO for review and also post a copy of the report to INSCOPE for tribal review. In addition, we ask that a copy of the SHPO submittal be sent to INDOT CRO care of <a href="Months:PKorzeniewski@indot.in.gov">PKorzeniewski@indot.in.gov</a> during the time of submission. If there are any questions or concerns regarding this matter, please contact me by email or at 317-233-2093. Thank you very much.

Patricia Jo Korzeniewski
Archaeologist and Environmental Manager
INDOT, Cultural Resources Office
PKorzeniewski@indot.in.gov
(317) 233-2093

From: Miller, Shaun (INDOT) < <a href="mailto:smiller@indot.IN.gov">smiller@indot.IN.gov</a>>

Sent: Wednesday, March 25, 2020 3:34 PM

To: Korzeniewski, Patricia J < <a href="mailto:PKorzeniewski@indot.IN.gov">PKorzeniewski@indot.IN.gov</a>>

**Cc:** Branigin, Susan < <u>SBranigin@indot.IN.gov</u>>; Howder, Aubrey < <u>AHowder@indot.IN.gov</u>>; Harlan Ford

< H.Ford@gaiconsultants.com >; Falls, Ryan G < RFalls@indot.IN.gov >; Jeff Plunkett

<j.plunkett@nsenvservices.com>

Subject: FW: MPPA Submittal for Des No. 1702071

Patty Jo,

Attached is the revised ASR for this small structure replacement project. I don't think any aspect of the project has changed since the previous submission.

Thank you,

Shaun Miller INDOT, Cultural Resources Office Archaeology Team Lead (317)233-6795

From: Harlan Ford < <a href="mailto:H.Ford@gaiconsultants.com">H.Ford@gaiconsultants.com</a> Sent: Wednesday, March 25, 2020 8:14 AM

To: Branigin, Susan < SBranigin@indot.IN.gov>

Cc: Kumar, Anuradha <a href="mailto:kumar@indot.IN.gov">akumar@indot.IN.gov">kumar, Anuradha <a href="mailto:kumar@indot.IN.gov">akumar@indot.IN.gov</a>>; Miller, Shaun (INDOT) <a href="mailto:kumar@indot.IN.gov">smiller@indot.IN.gov</a>>

Subject: MPPA Submittal for Des No. 1702071

\*\*\*\* This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email. \*\*\*\*

Good Morning Susan,

I am submitting a request to have the above mentioned project reviewed under Category B: Type 9 and Category A: Types 6 & 9. I have attached a shapefile for the project location, as well as some maps and photos for your convenience. As this project will take place in undisturbed soils, I have also attached the archeological short report that was prepared for this project.

**Please note:** This project was previously submitted to your office on December 12, 2019 and it was determined that the area would need to be re-surveyed by NS Services due to the ROW. We are now re-submitting this project for your review.

Please let me know if you need anything else!

Thanks for your time,

#### Harlan M. Ford

**Environmental Specialist** 

**GAI Consultants**, 201 N. Illinois Street, Suite 1700, Indianapolis, IN 46204 **T** 317.570.6800 **D** 317.436.9142 **M** 423.458.5979

Facebook | LinkedIn | Twitter | YouTube | News & Insights



GAI CONSULTANTS CONFIDENTIALITY NOTICE: This communication contains confidential information belonging to the sender and may be legally privileged. This communication is solely for the use of its intended recipient. If you are not the intended recipient, inform the sender of the error and remove this email from your system. If this transmission includes any technical information, design data, and/or recommendations, they are provided only as a matter of convenience and may not be used for final design and/or construction.



# INDIANA DEPARTMENT OF NATURAL RESOURCES DIVISION OF HISTORIC PRESERVATION AND ARCHAEOLOGY

402 West Washington Street, Room W274 Indianapolis, Indiana 46204-2739 Telephone Number: (317) 232-1646 Fax Number: (317) 232-0693 E-mail: dhpa@dnr.IN.gov

Where applicable, the use of this form is recommended but not required by the Division of Historic Preservation and Archaeology.

Author: Stacy N. Bennett and Jeffrey A. Plunkett				
Date (month, day, year): March 24, 2020				
Project Title: UNT to	Phase Ia Archaeological Field Reconnaissance for a Small Structure Replacement on SR 62 over UNT to Otter Creek, Located 4.79 miles east of SR 61 in Skelton Civil Township, Warrick County, Indiana (Des. No. 1702071)			
	PROJECT OVERVIEW			
The Indiana Department of Transportation (INDOT) and Federal Highway Administration (FHWA) intends to proceed to rehabilitate the structure carrying State Road (SR) 62 over UNT to Otter Creek (CV 062-087-48.79) located in Warrick County, Indiana. This project is located on SR 62, approximately 4.79 miles east of SR 61 in Section 33 of Township 5 South, Range 7 West, as shown on the De Gonia Springs USGS 7.5-Minute Topographic Map. The existing culvert is a 14 ft. span by 6.2 ft. rise slab top that is approximately 30 ft. in length. The existing structure is showing signs of exposed rebar, minor section loss, and efflorescence. The existing culvert will be replaced with a new 14 ft. span by 8 ft. rise reinforced concrete box culvert. In addition to the culvert replacement, the project will include replacing the existing guardrails, widening of the roadway shoulders, milling and resurfacing of the existing travel lanes, placement of riprap for scour protection, and the new culvert will be sumped 18 in. The purpose of this project is to address the deteriorating conditions exhibited by the culvert carrying SR 62 over UNT to Otter Creek.				
INDOT Designation N	INDOT Designation Number/ Contract Number: 1702071 Project Number: 19357			
DHPA Number:	Approved DHPA Plan Number:			
Prepared For: GAI C	onsultants			
Contact Person: Davi	d Bourff			
Address: 201 N. Illinois Street, Suite 1700				
City: Indianapolis State: IN ZIP Code: 46204				
Telephone Number: (317) 436-4841 Email Address: D.Bourff@gaiconsultants.com				
Principal Investigator: Jeffrey A. Plunkett				
Signature: Jeffrey A. Plunkett    Digitally signed by Jeffrey A. Plunkett   Dictarial for A Plunkett				
Company/Institution: NS Services, LLC				

4974 S. Cobblestone Drive

Address:

Actual Area	rveyed hectares: 00.5 acres: 01.2				
Comments:	One shovel probe was excavated within an area of Markland silt loam located on the north side of SR 62 towards the west end of the project area. Soils in this probe consisted of brown (10YR5/3) silt loam excavated to a depth of 22 cm where a buried cable was encountered.  Soils within the remainder of the project area consisted of approximately 30 cm of brown (10YR5/3) silt loam over a brown (10YR5/3) silt loam with 40% light yellowish brown (10YR6/4) silt loam mottles excavated to a maximum depth of 40 cm below surface.				
	RECOMMENDATION				
	cological records check has determined that the project area has the potential to contical resources and a Phase Ia archaeological reconnaissance is recommended.	ntain			
	cological records check has determined that the project area does not have the pote gical resources and no further work is recommended before the project is allowed to				
	Ia archaeological reconnaissance has located no archaeological sites within the proded that the project be allowed to proceed as planned.	oject area and it is			
The Phase Ia archaeological reconnaissance has determined that the project area includes landforms which have the potential to contain buried archaeological deposits. It is recommended that Phase Ic archaeological subsurface reconnaissance be conducted before the project is allowed to proceed.					
	The Phase Ia archaeological reconnaissance has determined that the project area is within 100 feet of a cemetery and a Cemetery Development Plan is required per IC-14-21-1-26.5.				
Cemetery Na	ne:				
Other Recon	nendations/Commitments:				
Pursuant to IC-14-21-1, if any archaeological artifacts or human remains are uncovered during construction, demolition, or earthmoving activities, state law (Indiana Code 14-21-1-27 and 29) requires that the discovery must be reported to the Department of Natural Resources within two (2) business days. In that event, please call (317) 232-1646.					
	ATTACHMENTS				
∑ Figure s	☐ Figure showing project location within Indiana.				
⊠ USGS to	☑ USGS topographic map showing the project area (1:24,000 scale).				
Aerial photograph showing the project area, land use, and survey methods.					
Project p	ns (if available)				
Other Attach	Other Attachments:				
	DeRegnaucourt, Robert A. 1979 Archaeological Survey of Project RS-3887(), Replacement of the Bridgereek on S.R. 62 near Degonia Springs in Warrick County, Indiana. Ball State Muncie, Indiana. Prepared for the Indiana State Highway Commission, Indianal	e University,			

# Appendix E

# Red Flag and Hazardous Materials

Item	Appendix Page
Red Flag Investigation	E1 to E9





### INDIANA DEPARTMENT OF TRANSPORTATION

100 North Senate Avenue Room N642 Indianapolis, Indiana 46204 PHONE: (317) 232-5113 FAX: (317) 233-4929 Eric Holcomb, Governor Joe McGuinness, Commissioner

Date: August 5, 2019

To: Site Assessment & Management

Environmental Policy Office - Environmental Services Division

Indiana Department of Transportation 100 N Senate Avenue, Room N642

Indianapolis, IN 46204

From: Harlan Ford

GAI Consultants Inc. 201 N. Illinois Street Indianapolis, IN

H.Ford@gaiconsultants.com

Re: RED FLAG INVESTIGATION

1702071, State Project

Small Structure Replacement

SR-62

Warrick County, Indiana

#### PROJECT DESCRIPTION

Brief Description of Project: INDOT is proposing to replace the existing Culvert structure (CV # 062-087-48.79) located on SR-62 in Warrick County. This project is located approximately 4.79 miles east of SR-61 in Section 33 of Township 5 South, Range 7 West, as shown on the De Gonia Springs USGS 7.5 Minute Topographic Map. The existing culvert is a 14ft. span by 6.2ft. rise slab top that is approximately 30ft. in length. The existing structure is exhibiting exposed rebar, minor section loss, and efflorescence. As the project is currently proposed, there are three replacement options being considered and they are:

- Option #1: 14' x 8' Reinforced Concrete Box (RCB)
- Option #2: 14' x 8' 3-Sided Flat Top
- Option #3: 14' x 8' 3-Sided Arch Top

In order to maintain a low structure elevation and to avoid a grade raise, these options would need to be sumped 18 inches. Class 1 revetment riprap would need to be placed at the structure outlet as a scour countermeasure. No tree removal is expected to occur as part of this project. No right of way is expected to be acquired for this project.

Bridge and/or Culvert Project: Yes 🗵 No 🗆 S	Structure # <u>CV 062-087-48.79</u>
If this is a bridge project, is the bridge H	Historical? Yes $\square$ No $\boxtimes$ , Select $\square$ Non-Select $\square$
(Note: If the project involves a historica	<u>al</u> bridge, please include the bridge information in the Recommendations
Section of the report).	

www.in.gov/dot/ **An Equal Opportunity Employer** 

Proposed right of way: Temporary $\boxtimes$ # Acres <u>0.20</u> Permanent $\boxtimes$ # Acres <u>0.10</u> , Not Applicable $\square$
Type of excavation: Excavation will be required to remove the old structure and properly sump the new structure. The
new structure will match the existing flowline and it is expected that excavation will not extend deeper than previous
construction limits.
Maintenance of traffic: A Maintenance of Traffic plan has not yet been determined for this project. MOT options will
examined as part of the design process and the most feasible and prudent option will be selected.
Work in waterway: Yes $oxtimes$ No $oxtimes$ Below ordinary high water mark: Yes $oxtimes$ No $oxtimes$
State Project: ⊠ LPA: □
Any other factors influencing recommendations: N/A

#### **INFRASTRUCTURE TABLE AND SUMMARY**

Infrastructure Indicate the number of items of concern found within the 0.5 mile search radius. If there are no items, please indicate N/A:				
Religious Facilities	N/A	Recreational Facilities	N/A	
Airports <sup>1</sup>	N/A	Pipelines	N/A	
Cemeteries	N/A	Railroads	N/A	
Hospitals	N/A	Trails	N/A	
Schools	N/A	Managed Lands	N/A	

<sup>&</sup>lt;sup>1</sup>In order to complete the required airport review, a review of public airports within 3.8 miles (20,000 feet) is required.

Explanation: No infrastructure resources were identified within the 0.5 mile search radius.

#### WATER RESOURCES TABLE AND SUMMARY

Water Resources Indicate the number of items of please indicate N/A:	concern found wit	hin the 0.5 mile search radius. If the	ere are no items,
NWI - Points	N/A	Canal Routes - Historic	N/A
Karst Springs	N/A	NWI - Wetlands	25
Canal Structures – Historic	N/A	Lakes	8
NPS NRI Listed	N/A	Floodplain - DFIRM	1
NWI-Lines	3	Cave Entrance Density	N/A
IDEM 303d Listed Streams and Lakes (Impaired)	N/A	Sinkhole Areas	N/A
Rivers and Streams	3	Sinking-Stream Basins	N/A

#### Explanation:

*NWI Lines:* A total of three (3) NWI lines were identified within 0.5 mile of the project area. The nearest NWI line is located approximately 0.43 mile south of the project area. No impact is expected.

Rivers and Streams: A total of three (3) stream segments were identified within 0.5 mile of the project area. The nearest stream, UNT to Otter Creek, is located within the project area but is not mapped as flowing through the project area. Due to the proximity of the UNT to Otter Creek it is likely that additional water resources, such as unnamed tributaries,

www.in.gov/dot/

regulated drains, wetlands, and roadside ditches are located in the project area. A Waters of the U.S. Report will be prepared and coordination with INDOT ES Ecology and Waterway Permitting will occur.

*NWI Wetlands*: A total of twenty-five (25) NWI wetlands was identified within 0.5 mile of the project area. The nearest mapped NWI wetland is located approximately 0.06 mile southeast of the project area. No impact is expected.

*Lakes:* A total of eight (8) lakes were identified within 0.5 mile of the project area. The nearest mapped lake is located approximately 0.11 mile southeast of the project area. No impact is expected.

Floodplain: One (1) floodplain polygon is located within the 0.5 mile search radius. The mapped floodplain is located within the project area. Coordination with INDOT Ecology and Waterway Permitting will occur.

#### **URBANIZED AREA BOUNDARY SUMMARY**

Explanation: N/A

#### MINING AND MINERAL EXPLORATION TABLE AND SUMMARY

Mining/Mineral Exploration Indicate the number of items of please indicate N/A:	concern found with	in the 0.5 mile search radius. If tl	here are no items,
Petroleum Wells	N/A	Mineral Resources	N/A
Mines – Surface	N/A	Mines – Underground	N/A

Explanation: No mining/mineral resources were identified within the 0.5 mile search radius.

### **HAZARDOUS MATERIAL CONCERNS TABLE AND SUMMARY**

	ern found wit	hin the 0.5 mile search radius. If there	are no items,
please indicate N/A:  Superfund	N/A	Manufactured Gas Plant Sites	N/A
RCRA Generator/ TSD	N/A	Open Dump Waste Sites	N/A
RCRA Corrective Action Sites	N/A	Restricted Waste Sites	N/A
State Cleanup Sites	N/A	Waste Transfer Stations	N/A
Septage Waste Sites	N/A	Tire Waste Sites	N/A
Underground Storage Tank (UST) Sites	N/A	Confined Feeding Operations (CFO)	N/A
Voluntary Remediation Program	N/A	Brownfields	N/A
Construction Demolition Waste	N/A	Institutional Controls	N/A
Solid Waste Landfill	N/A	NPDES Facilities	N/A
Infectious/Medical Waste Sites	N/A	NPDES Pipe Locations	N/A
Leaking Underground Storage (LUST) Sites	N/A	Notice of Contamination Sites	N/A

Explanation: No hazardous material concerns were identified within the 0.5 mile search radius.

www.in.gov/dot/ **An Equal Opportunity Employer** 

#### **ECOLOGICAL INFORMATION SUMMARY**

The Warrick County listing of the Indiana Natural Heritage Data Center information on endangered, threatened, or rare (ETR) species and high quality natural communities is attached with ETR species highlighted. A preliminary review of the Indiana Natural Heritage Database by INDOT Environmental Services did not indicate the presence of ETR species within the 0.5 mile search radius. Coordination with the USFWS and IDNR will occur.

Bats: A review of the USFWS database did not indicate the presence of endangered bat species in or within 0.5 mile of the project area. The project area is located in a rural area surrounded primarily by farm fields. The August 23, 2018 inspection report for CV 062-087-48.79 states that no evidence of bats was seen or heard under the bridge. The rangewide programmatic consultation for the Indiana Bat and Northern Long-eared Bat will be completed according to "Using the USFWS's IPaC System Listed Bat Consultation for INDOT Projects."

Rusty Patched Bumble Bee: An inquiry using the USFWS Information for Planning and Consulting (IPaC) website did not indicate the presence of the federally endangered species, the Rusty Patched Bumble Bee, in or within 0.5 miles of the project area. No impact is expected.

#### RECOMMENDATIONS SECTION

Include recommendations from each section. If there are no recommendations, please indicate N/A:

INFRASTRUCTURE: N/A

WATER RESOURCES: A Waters of the U.S. Report will be prepared and coordination with INDOT ES Ecology and Waterway Permitting will occur due to the presence of the following water resources:

- One (1) floodplain polygon is mapped within the project area. (coordination only)
- Due to the proximity of the UNT to Otter Creek it is likely that additional water resources, such as unnamed tributaries, regulated drains, wetlands, and roadside ditches are located in the project area.

URBANIZED AREA BOUNDARY: N/A

MINING/MINERAL EXPLORATION: N/A

HAZMAT CONCERNS: N/A

ECOLOGICAL INFORMATION: Coordination with the USFWS and IDNR will occur. The range-wide programmatic consultation for the Indiana Bat and Northern Long-eared Bat will be completed according to "Using the USFWS's IPaC

System Listed Bat Consultation for INDOT Projects."

Digitally signed by Nicole Fohey Nicole Fohey-Breting Date: 2019.09.19 Breting

INDOT Environmental Services concurrence:

22:14:24 -04'00' (Signature)

Prepared by: Harlan M. Ford **Project Environmental Specialist** GAI Consultants Inc.

> www.in.gov/dot/ An Equal Opportunity Employer

### **Graphics**:

A map for each report section with a 0.5 mile search radius buffer around all project area(s) showing all items identified as possible items of concern is attached. If there is not a section map included, please change the YES to N/A:

SITE LOCATION: YES

INFRASTRUCTURE: N/A

WATER RESOURCES: YES


URBANIZED AREA BOUNDARY: N/A

MINING/MINERAL EXPLORATION: N/A

HAZMAT CONCERNS: N/A

www.in.gov/dot/ **An Equal Opportunity Employer** 

# Red Flag Investigation - Site Location Map SR 62 over UNT Otter Creek, 4.79 miles E of SR 61 Des. No. 1702071, Small Structure Replacement Warrick County, Indiana



Sources: 0.6 0.3 0 0.6

Non Orthophotography

Data - Obtained from the State of Indiana Geographical

<u>Data</u> - Obtained from the State of Indiana Geographical

Information Office Library


<u>Orthophotography</u> - Obtained from Indiana Map Framework Data (www.indianamap.org)

Map Projection: UTM Zone 16 N Map Datum: NAD83

This map is intended to serve as an aid in graphic representation only. This information is not warranted for accuracy or other purposes.


DE GONIA SPRINGS QUADRANGLE INDIANA 7.5 MINUTE SERIES

# Red Flag Investigation - Water Resources SR 62 over UNT Otter Creek, 4.79 miles E of SR 61 Des. No. 1702071, Small Structure Replacement Warrick County, Indiana



0.075 0 0.15 0.15 Sources: ■ Miles Non Orthophotography **Data** - Obtained from the State of Indiana Geographical Information Office Library Orthophotography - Obtained from Indiana Map Framework Data (www.indianamap.org) Map Projection: UTM Zone 16 N Map Datum: NAD83 This map is intended to serve as an aid in graphic

representation only. This information is not warranted for accuracy or other purposes.



## **Indiana County Endangered, Threatened and Rare Species List**

County: Warrick

Species Name		Common Name	FED	STATE	GRANK	SRANK
Mollusk: Bivalvia (Mussels)						
Lampsilis ovata		Pocketbook			G5	S2
Ligumia recta		Black Sandshell			G4G5	S2
Plethobasus cyphyus		Sheepnose	LE	SE	G3	S1
Pleurobema cordatum		Ohio Pigtoe		SSC	G4	S2
Fish Etheostoma squamiceps		Spottail Darter			G4G5	S2S3
Reptile  Nerodia erythrogaster neglecta		Copperbelly Water Snake	PS:LT	SE	G5T3	<b>S2</b>
Opheodrys aestivus		Rough Green Snake		SSC	G5	S3
Bird		S				
Ammodramus henslowii		Henslow's Sparrow		SE	G4	S3B
Asio flammeus		Short-eared Owl		SE	G5	<u>S2</u>
Botaurus lentiginosus		American Bittern		SE	G5	S2B
Buteo lineatus		Red-shouldered Hawk		SSC	G5	S3
Circus hudsonius		Northern Harrier		SE	G5	<b>S2</b>
Cistothorus platensis		Sedge Wren		SE	G5	S3B
Haliaeetus leucocephalus		Bald Eagle		SSC	G5	S2
Helmitheros vermivorus		Worm-eating Warbler		SSC	G5	S3B
Ictinia mississippiensis		Mississippi Kite		SSC	G5	S1B
(xobrychus exilis)		Least Bittern		SE	G5	S3B
Lanius Iudovicianus		Loggerhead Shrike		SE	G4	S3B
Nyctanassa violacea		Yellow-crowned Night-heron		SE	G5	S2B
Pandion haliaetus		Osprey		SE	G5	S1B
Rallus limicola		Virginia Rail		SE	G5	S3B
Setophaga cerulea		Cerulean Warbler		SE	G4	S3B
Tyto alba		Barn Owl		SE	G5	S2
Mammal Lasiurus borealis		Eastern Red Bat		SSC	G3G4	S4
Myotis sodalis		Indiana Bat or Social Myotis	LE	SE	G2	S1
Nycticeius humeralis		Evening Bat	LL)	SE	G5	S1
Sylvilagus aquaticus		Swamp Rabbit		SE	G5	S1
Taxidea taxus		American Badger		SSC	G5	S2
		American Badger		bbc	30	S <b>-</b>
Vascular Plant  Bacopa rotundifolia		Roundleaf Water-hyssop		ST	G5	<u>S1</u>
Carex bushii				ST	G4	S1 S1
Carex socialis		Bush's Sedge		SR	G4 G4	S2
Catalpa speciosa		Social Sedge		SR	G4?	S2 S2
Clematis pitcheri		Northern Catalpa			G4?	S2 S2
Croton willdenowii		Pitcher Leather-flower		SR		S1
- Williagnowii		Elliptical Rushfoil		SE	G5	<u>01</u>
Indiana Natural Heritage Data Center Division of Nature Preserves	Fed: State:	LE = Endangered; LT = Threatened; C = candid SE = state endangered; ST = state threatened; S		-		ern:
Indiana Department of Natural Resources		SX = state extirpated; SG = state significant; W	L = watch list	-	-	
This data is not the result of comprehensive county surveys.	GRANK:	Global Heritage Rank: G1 = critically imperiled globally; G4 = widespread and abundant global			-	
5·Cy5.		globally; $G$ ? = unranked; $GX$ = extinct; $Q$ = un				na aounaant
	SRANK:	State Heritage Rank: S1 = critically imperiled in G4 = widespread and abundant in state but with				
		state; SX = state extirpated; B = breeding status	_			

unranked

Page 2 of 2 02/05/2018

### Indiana County Endangered, Threatened and Rare Species List

County: Warrick

Species Name	Common Name	FED	STATE	GRANK	SRANK
Dicliptera brachiata	Wild Mudwort		SE	G5	<u>S1</u>
Didiplis diandra	Water-purslane		SE	G5	S2
Eleocharis wolfii	Wolf Spikerush		SR	G3G5	S2
Festuca paradoxa	Cluster Fescue		ST	G5	<u>S1</u>
Hypericum denticulatum	Coppery St. John's-wort		ST	G5	S2
Iresine rhizomatosa	Eastern Bloodleaf		SR	G5	<b>S2</b>
Nothoscordum bivalve	Crow-poison		SR	G4	<b>S2</b>
Orobanche riparia	<b>Bottomland Broomrape</b>		SE	G4?	<b>S2</b>
Perideridia americana	Eastern Eulophus		SE	G4	<u>S1</u>
Poa wolfii	Wolf Bluegrass		SR	G4	S2
Rudbeckia fulgida var. fulgida	Orange Coneflower		WL	G5T4?	S2
Scutellaria parvula var. australis	Southern Skullcap		WL	G4T4?	S2
Stenanthium gramineum	Eastern Featherbells		ST	G4G5	S1
Strophostyles leiosperma	Slick-seed Wild-bean		ST	G5	S2
Styrax americanus	American Snowbell		WL	G5	S3
Taxodium distichum	Bald Cypress		ST	G5	S2)
Thalictrum pubescens	Tall Meadowrue		ST	G5	S2
Trachelospermum difforme	Climbing Dogbane		SR	G4G5	<b>S2</b>
Trifolium reflexum var. glabrum	Buffalo Clover		SE	G5T2T4Q	S1
High Quality Natural Community					
Forest - flatwoods dry	Dry Flatwoods		SG	G2?	S2
Forest - floodplain wet	Wet Floodplain Forest		SG	G3?	S3
Forest - upland dry-mesic Southern Bottomlands	Southern Bottomlands Dry-mesic Upland Forest			GNR	S1
Other Significant Feature					
Freshwater Mussel Concentration Area	Mussel Bed		SG	G3	SNR

Indiana Natural Heritage Data Center Division of Nature Preserves Indiana Department of Natural Resources This data is not the result of comprehensive county surveys.

LE = Endangered; LT = Threatened; C = candidate; PDL = proposed for delisting Fed: State:

SE = state endangered; ST = state threatened; SR = state rare; SSC = state species of special concern;

 $SX = state \ extirpated$ ;  $SG = state \ significant$ ;  $WL = watch \ list$ 

GRANK:

Global Heritage Rank: G1 = critically imperiled globally; G2 = imperiled globally; G3 = rare or uncommon

globally; G4 = widespread and abundant globally but with long term concerns; G5 = widespread and abundant

globally; G? = unranked; GX = extinct; Q = uncertain rank; T = taxonomic subunit rank

SRANK:

State Heritage Rank: S1 = critically imperiled in state; S2 = imperiled in state; S3 = rare or uncommon in state; G4 = widespread and abundant in state but with long term concern; SG = state significant; SH = historical in state; SX = state extirpated; B = breeding status; S? = unranked; SNR = unranked; SNA = nonbreeding status unranked

# Appendix F

## Water Resources

Item	Appendix Page
Wetland Delineation and Stream Identification Report	F1 to F19
INDOT EWPO Approval Email	F20



## Waters of the U.S. Determination

SR 62 over UNT to Otter Creek Small Structure Replacement Project Des. No.: 1702071

Warrick County, Indiana Asset ID #: CV 062-087-48.79

Prepared for:
Indiana Department of Transportation (INDOT)
Vincennes District
3650 South U.S. Highway 41
Vincennes, IN 47591

Prepared by:
GAI Consultants, Inc.
Indianapolis Office
201 N. Illinois Street, Suite 1700
Indianapolis, Indiana 46204

Author:

Harlan M. Ford Project Environmental Specialist

> Report Completed: June 12, 2019

INDOT EWPO Approval Date:

#### **Table of Contents**

1.0	Introd	uction		1
2.0	Method	ds		1
3.0	Backgr 3.1 3.2 3.3	National W Watershed	etland Inventorys	
4.0	Results 4.1 4.2 4.3	Waterbodie Wetlands	es	
5.0	Conclu	sions		4
6.0	Acknow	wledgement	t	4
7.0	Refere	nces		5
Table Table		NRCS Soil Waterbod	s ies Identified Within the	Project Study Area
Attac	hments			
	Proj	Figure 2	State Location Map- USGS Topo Map- Aerial Location Map- NWI Wetlands Map NRCS Soils Map	Duplicate project maps and photos have been removed and included in Appendix B to avoid duplication.

Figure 7 LiDAR Map

Figure 6

Figure 8 Waters of the US Investigation Map

FEMA Floodzone Map

Figure 9 Photo Location Map

## **Photographs**

Preliminary Jurisdictional Determination Form

### © 2018 GAI CONSULTANTS



### 1.0 Introduction

The Indiana Department of Transportation (INDOT) and Federal Highway Administration (FHWA) intends to proceed to rehabilitate the structure carrying State Road (SR) 62 over a UNT to Otter Creek (CV 062-087-48.79) located in Warrick County, Indiana. (Figure 1). The project is located on SR 62, approximately 0.30 miles west of SR 161 in Sections 33 of Township 5 South, Range 7 West, as shown on the De Gonia Springs USGS 7.5 Minute Topographic Map. The existing culvert is a 14ft. span by 6.2ft. rise slab top that is approximately 30ft. in length. The existing structure is showing signs of exposed rebar, minor section loss, and efflorescence. As the project is currently proposed, there are three replacement options being considered and they are:

• Option #1: 14' x 8' RCB

• Option #2: 14' x 8' 3-Sided Flat Top

• Option #3: 14' x 8' 3-Sided Arch Top

In order to maintain a low structure elevation and to avoid a grade raise, these options would need to be sumped 18 inches. Class 1 revetment riprap would need to be placed at the structure inlet and outlet as a scour countermeasure. This project is located within a regulatory floodplain as shown on the FEMA Floodzone Map.

GAI Consultants, Inc. (GAI), on behalf of INDOT, conducted wetland delineations and waterbody investigations of the project study area on October 11, 2018. GAI identified approximate boundaries of waterbodies and wetlands located within the project study area. This study area was determined in the field by GAI based upon likely work areas and impacts to regulated Waters of the U.S. as a result of construction activities. This report describes the methods and results of the environmental field survey.

### 2.0 Methods

Wetland delineations were conducted in accordance with the 1987 United States Army Corps of Engineers (USACE) Corps of Engineers Wetlands Delineation Manual (Environmental Laboratory, 1987) and the Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Midwest Region (Version 2.0) (USACE, 2012). Wetlands were classified using the Classification of Wetlands and Deepwater Habitats of the United States (Cowardin et al., 1979). Classification of the indicator status of vegetation is based on The National Wetland Plant List: 2016 wetland ratings (Lichvar et al. 2016).

The USACE will assert jurisdiction over traditionally navigable waters (TNW), adjacent wetlands, and non-navigable tributaries of TNW that have "relatively permanent" flow, and wetlands that border these waters, regardless of whether or not they are separated by roads, berms, and similar barriers. The USACE will use a case-by-case "significant nexus" analysis to determine whether waters and their adjacent wetlands are jurisdictional. A "significant nexus" can be found where waters, including adjacent wetlands, alter the physical, biological, or chemical integrity of the TNW based on consideration of several factors.

Each wetland and waterbody feature was given a unique map designation and each boundary flag location was recorded using a SX Blue II<sup>+</sup> GNSS model global positioning system mapping grade unit with the capability of sub-meter accuracy. Judgmental upland and wetland soil test pits were taken within the study corridor at the discretion of the delineator to confirm the presence or absence of wetlands in areas with exhibiting wetland indicators. Wetland boundaries and other waterbody centerlines and/or perimeters were mapped including ordinary high water mark (OHWM) and top-of-bank (TOB). Waterbody data collected included general morphological characteristics, flow regime, substrate, jurisdictional connection, and significant nexus determination.



All likely jurisdictional streams, waterbodies, and wetlands were evaluated for quality using the 2018 *INDOT Waters of the United States Documentation* three tier classification system (i.e., poor, average, or excellent). Determinations of quality for streams were based on the substrate, riffle and pools, overhead cover, presence of aquatic organisms or potential habitat value, opacity, sinuosity, and riparian width. In instances where mitigation is likely to be required, federal or state aquatic endangered or threatened species are present, or the stream has a designation as a state wild or scenic river, a Headwaters Habitat Evaluation Index (HHEI) or Qualitative Habitat Evaluation Index (QHEI) is used. Wetland quality was derived from metrics in the Indiana Wetland Rapid Assessment Protocol (In-WRAP 2005) and the wetland quality descriptions on the basis of disturbance, native plant diversity and cover, and content of exotic or invasive species.

## 3.0 Background Information

Prior to the fieldwork, background information and existing mapping was reviewed to establish the probability and potential location of wetlands on the site. Available information from government agency documents and private sources were collected and reviewed in order to characterize the project area, as well as identify potential wetlands and other regulated features located within the project study area.

The growing season in the project area is generally between April and October in Warrick County, Indiana [United States Department of Agriculture, Natural Resource Conservation Service (USDA-NRCS)] (USDA-NRCS, 2016). Field observations were supplemented with an intensive review of United States Fish and Wildlife Service (USFWS) National Wetlands Inventory (NWI) mapping, USDA soils mapping, historical aerial photography (ArcGIS and Google Earth), and local landscape topography/morphology.

The project study area topography is mostly flat, with elevations ranging from 390 to 400 ft. Drainage patterns were identified via topographic elevation contours to drain towards the UNT to Otter Creek. The project study area is within the Booneville Hills physiographic region of the Southern Hills and Lowlands Region (Gray, 2000). Land use in the vicinity of the project is primarily rural residential and agriculture.

### 3.1 National Wetland Inventory

The USFWS' NWI Wetlands Mapper was reviewed for potential wetland locations. The NWI data of the area (Figure 4) identified one NWI wetlands within the project study area. This NWI mapped wetland is located approximately .01 miles southwest of the structure and is confined to the channel of the UNT to Otter Creek. This wetland is classified as a R4SBC wetland and impacts are anticipated. There are four additional mapped NWI Wetlands close to the project area. All four of these mapped NWI Wetlands are classified as PUBGx wetlands. Out of these four wetlands, the nearest is located 0.05 miles east of the project area and no impacts are anticipated.

### **Watersheds**

The project study area is in the Lower Ohio-Little Pigeon, Lower Ohio Basin, and Lower Ohio sub-region, of the Ohio region, 12 digit hydrologic unit code (HUC12) 051402011002.

### 3.2 NRCS Soil Survey

The NRCS Soil Survey of Warrick County identified two soil series within the project study area (Figure 5, Table 1). One soil series was identified as being hydric.

Table 1. NRCS Soil Survey Area of Interest Results

Map Unit Name (Map Symbol)	Drainage Properties	Hydrology	Hydric Status
Wakeland Silt Loam (Wa)	Somewhat Poorly Drained	No Ponding, Frequent Flooding	Yes (1-32%)
Markland Silt Loam (MkB2)	Moderately Well Drained	No Ponding, No Flooding	No (0%)



### 4.0 Results

Two likely jurisdictional streams were identified within the study area (Figure 8).

#### 4.1 Waterbodies

Detailed descriptions of the delineated streams and other waterbodies are discussed below. Stream features and other waterbodies are described by morphological characteristics, flow regime, substrate, jurisdictional connection and significant nexus determination. Waterbodies identified within the project study area are represented in Table 2.

The identified stream features are not State Waters Designated for Special Protection in Indiana (Designated Salmonid Waters, Outstanding State Resource Waters, or Exceptional Use Streams). The identified stream features are not on the Indiana Department of Natural Resources Listing of State Natural and Scenic Rivers. The identified streams are not listed on Indiana Department of Natural Resources for Outstanding Rivers in Indiana. The streams are not a USACE Section 10 Waters listed as navigable.

### **UNT To Otter Creek (approximately 256 feet onsite)**

UNT to Otter Creek is an intermittent stream that should be considered a Waters of the U.S. UNT to Otter Creek flows north to south at the structure through the project area and has an upstream drainage area of 0.681 square miles. UNT to Otter Creek is a channelized stream with a substrate comprised primarily of cobble, silt, and artificial (rip-rap). UNT to Otter Creek has a defined bed, bank, and ordinary high water mark (OHWM). The average OHWM is 6 ft. wide and 6 in. deep. There was one large pool area just north of the structure that measured 14 ft. wide and 6 in. deep. The riparian zone consists of maintained lawn in the northern quadrants but is forested in both southern quadrants. The quality of the stream would be considered average due to the amount of instream cover, the composition of the substrate, forested riparian zone, and the presence of riffle and pool complexes. Sinuosity was moderate within the study area sampling reach with three outside bends at the structure. UNT to Otter Creek would likely receive a QHEI score of 45 to 55 due to the above mentioned factors. UNT to Otter Creek discharges to Otter Creek, which then connects with Little Pigeon Creek, then the Ohio River (RPW and TNW). Due to the connection with a TNW, UNT to Otter Creek would be considered a Waters of the U.S.

#### **UNT 1** (approximately 129 feet onsite)

UNT 1 is an ephemeral stream that flows towards UNT to Otter Creek. UNT 1 meets the definition of a tributary by having an OHWM and indirectly flowing through another water to a TNW. UNT 1 has a OHWM of 3 ft. wide and 3 in. deep. The substrate consists primarily of artificial (rip-rap) within the study area. The riparian zone is well vegetated and consisted primarily of spotted lady's thumb (*Polygonum persicaria*, FACW), asiatic dayflower, (*Commelina communis*, FACU) and reed canary grass (*Phalaris arundinacea*, FACW) along the banks. Outside of the banks the vegetation of the riparian zone consisted of cottonwood (*Populus deltoids*, FAC), hackberry (*Celtis occidentalis*, FAC), and pokeweed (*Phytolacca americana*, FACU). UNT 1 would be considered poor quality due to the amount of instream cover, the substrate composition, the riparian zone, low turbidity, no sinuosity, and lack of riffle and pool complexes. UNT 1 would likely receive a QHEI score of 35 to 45 due to the above mentioned factors. UNT 1 discharges into UNT to Otter Creek, which discharges to Otter Creek, which then connects with Little Pigeon Creek, then the Ohio River (RPW and TNW). Due to the connection with a TNW, UNT 1 would be considered a Waters of the U.S.

### 4.2 Wetlands

No wetland features that met all three of the USACE wetland criteria was observed within the project area. No hydrophytic vegetation or hydrology indicators were observed in conjunction with each other that warranted the collection of a sample data point within the project area.



### 4.3 Roadside Ditches and Other Drainages

All roadside ditches and other surface drainages within the study area were also evaluated for consideration as jurisdictional Waters of the U.S. with respect to the Clean Water Act Rule [40 CFR 230.3(3)(iii)]. Jurisdictional ditches must meet the definition of tributary, have an OHWM, and flow directly or indirectly through another water to a TNW. Likely jurisdictional ditches include: ditches with perennial flow; ditches with intermittent flow that drain wetlands; or ditches, regardless of flow, that are excavated in or relocate a tributary. Jurisdictional wetlands may be present within, or connected to another jurisdictional Waters of the U.S. in regard to significant nexus analysis through, non-jurisdictional ditches or surface drainages.

Roadside ditches were observed in the northwest and southwest quadrants of the study area. These roadside ditches drain towards the UNT to Otter Creek. The roadside ditch in the northwest quadrant was riprap lined while the roadside ditch in the southwest quadrant exhibited a vegetated substrate. Both roadside ditches connect to the UNT to Otter Creek. These roadside ditches would not likely be considered jurisdictional within the study area. These features were excavated in upland soils to convey upland drainage and had no defined bed and bank or flow regime to establish a Waters of the U.S. designation.

### 5.0 Conclusions

Wetland delineations and stream investigations for the SR 62 over UNT to Otter Creek small structure replacement project were conducted on October 11, 2018. Two likely jurisdictional streams were identified within the study area.

These waterways are likely Waters of the U.S. Every effort should be taken to avoid and minimize impacts to the waterway and wetlands. If impacts are necessary, then mitigation may be required. The INDOT Environmental Services Division should be contacted immediately if impacts will occur. The final determination of jurisdictional waters is ultimately made by the U.S. Army Corps of Engineers. This report is our best judgment based on the guidelines set forth by the Corps.

## 6.0 Acknowledgement

This waters determination has been prepared based on the best available information, interpreted in the light of the investigator's training, experience, and professional judgement in conformance with the 1987 *Corps of Engineers Wetland Delineation Manual*, the appropriate regional supplement, the USACE *Jurisdictional Determination Form Instructional Guidebook*, and other appropriate agency guidelines.

Harlan Ford

Project Environmental Specialist

GAI Consultants Inc./INDOT Vincennes District



### 7.0 References

- Cowardin, D.M., Carter, V., Golet, F.C., and La Roe, E.T. 1979. *Classification of Wetlands and Deepwater Habitats of the United States*. Publication No. FWS/OBS-79/31. United States Department of the Interior, Fish and Wildlife Service, Washington, D.C.
- Environmental Laboratory. 1987. *Corps of Engineers Wetlands Delineation Manual*. Technical Report Y-87-1. United States Department of the Army, United States Army Engineer Waterways Experiment Station, Vicksburg, Mississippi.
- Indiana Department of Transportation (INDOT). 2018. *Waters of the United States Documentation.*Available at https://www.in.gov/indot/2522.htm. Accessed December 2018.
- Lichvar, R.W., D.L. Banks, W.N. Kirchner, and N.C. Melvin. 2016. *The National Wetland Plant List*: 2016 wetland ratings. Phytoneuron 2016-30: 1-17. Published 28 April 2016. ISSN 2153 733X.
- Taylor University Environmental Research Group. 2005. *Indiana Wetland Rapid Assessment Protocol, InWRAP. Version 2.5.* Taylor University, Upland, Indiana.
- United States Army Corps of Engineers (USACE). 2012. Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Midwest Region, Version 2.0. August of 2010.
- United States Department of Agriculture, Natural Resources Conservation Service (USDA-NRCS). 2006. Land Resource Regions and Major Land Resource Areas of the United States, the Caribbean, and the Pacific. U.S. Department of Agriculture Handbook, 296.



Table 2
Waterbodies Identified within the Project Study Area

Feature Name	Photo No.	Latitude, Longitude	Туре	OHWM Width (ft)	OHWM Depth (ft)	Length or Acres Within Study Area (ft)	USGS Blue- Line Stream	Riffles and Pools	Substrate	Quality	Waters of the U.S.
UNT to Otter Creek	3, 5, 8, 13, 14, 15, 16, 17	38.039752°, - 87.192071°	Int.	6	0.5	256	Yes	Yes	Cobble, Artificial, Silt	Average	Yes
UNT 1	9, 11, 12, 18	38.039783°, -87.191939°	Eph.	3	0.25	129	No	No	Artificial	Poor	Yes



Wetland Determination and Waters of the US Report Indiana Department of Transportation (INDOT) SR 62 over UNT to Otter Creek, Des. No.: 1702071 Warrick County, Indiana

## **Project Figures**

Duplicate project figures have been removed and included in Appendix B to avoid duplication.



## **NWI Wetlands Map**

SR 62 over UNT Otter Creek
Small Structure Replacement Project
Warrick County, Indiana
Des 1702071









0 80 160 320 Feet

Service Layer Credits: INDOT @ 2018 Microsoft Corporation @ 2018 DigitalGlobe @ CNES (2018) Distribution Airbus DS , U.S. Fish and Wildlife Serivce, National Wetlands Inventory F10 of 20







Service Layer Credits: INDOT

© 2018 Microsoft Corporation © 2018 DigitalGlobe ©CNES (2018)
Distribution Airbus DS , Indiana Department of Natural Resources FIRM Floodplain \$1200f(200) Hazards of Indiana, FEMA NFHL





## **LiDAR Map**

SR 62 over UNT Otter Creek
Small Structure Replacement Project
Warrick County, Indiana
Des 1702071

## Legend



Study Area



0 120 240 480 Feet

Service Layer Credits: INDOT IGIC, IOT, UITS, IGS, Woolpert

F13 of 20





## Waters of U.S. Investigation Map

SR 62 over UNT Otter Creek
Small Structure Replacement Project
Warrick County, Indiana
Des 1702071







0 25 50 100 Feet

Service Layer Credits: INDOT
Indiana Office of Information Technology, Indiana University Spatial Data
Portal, UITS, Woolpert Inc.,
F14 of 20



Wetland Determination and Waters of the US Report Indiana Department of Transportation (INDOT) SR 62 over UNT to Otter Creek, Des. No.: 1702071 Warrick County, Indiana

## **Photographs**

Photographs have been removed and included in Appendix B to avoid duplication.

Wetland Determination and Waters of the US Report Indiana Department of Transportation (INDOT) SR 62 over UNT to Otter Creek, Des. No.: 1702071 Warrick County, Indiana

# **Preliminary Jurisdictional Determination Form**

### Appendix 2 - PRELIMINARY JURISDICTIONAL DETERMINATION (PJD) FORM

### **BACKGROUND INFORMATION**

A. REPORT COMPLETION DATE FOR PJD: June 12, 2019

B. NAME AND ADDRESS OF PERSON REQUESTING PJD: Harlan M. Ford; 201 N. Illinois Street, Suite 1700, Indianapolis In, 46204

C. DISTRICT OFFICE, FILE NAME, AND NUMBER:

D. PROJECT LOCATION(S) AND BACKGROUND INFORMATION: Des No. 1702071 (USE THE TABLE BELOW TO DOCUMENT MULTIPLE AQUATIC RESOURCES AND/OR AQUATIC RESOURCES AT DIFFERENT SITES)

State: IN County/parish/borough: Warrick County City: Boonville

Center coordinates of site (lat/long in degree decimal format):

Lat.: 38.039863° Long.: -87.191993°

Universal Transverse Mercator: NAD83

Name of nearest waterbody: UNT Otter Creek

### E. REVIEW PERFORMED FOR SITE EVALUATION (CHECK ALL THAT APPLY):

Ш	Office (Desk) Determ	ination.	Date:
	Field Determination.	Date(s)	:

# TABLE OF AQUATIC RESOURCES IN REVIEW AREA WHICH "MAY BE" SUBJECT TO REGULATORY JURISDICTION.

Site number	Latitude (decimal degrees)	Longitude (decimal degrees)	Estimated amount of aquatic resource in review area (acreage and linear feet, if applicable)	Type of aquatic resource (i.e., wetland vs. non-wetland waters)	Geographic authority to which the aquatic resource "may be" subject (i.e., Section 404 or Section 10/404)
UNT Otter Creek	38.039752°	-87.192071°	256 ft.	Non-wetland water	Section 404
UNT 1	38.039783°	-87.191939°	129 ft.	Non-wetland water	Section 404

- 1) The Corps of Engineers believes that there may be jurisdictional aquatic resources in the review area, and the requestor of this PJD is hereby advised of his or her option to request and obtain an approved JD (AJD) for that review area based on an informed decision after having discussed the various types of JDs and their characteristics and circumstances when they may be appropriate.
- 2) In any circumstance where a permit applicant obtains an individual permit, or a Nationwide General Permit (NWP) or other general permit verification requiring "preconstruction notification" (PCN), or requests verification for a non-reporting NWP or other general permit, and the permit applicant has not requested an AJD for the activity, the permit applicant is hereby made aware that: (1) the permit applicant has elected to seek a permit authorization based on a PJD, which does not make an official determination of jurisdictional aquatic resources; (2) the applicant has the option to request an AJD before accepting the terms and conditions of the permit authorization, and that basing a permit authorization on an AJD could possibly result in less compensatory mitigation being required or different special conditions; (3) the applicant has the right to request an individual permit rather than accepting the terms and conditions of the NWP or other general permit authorization; (4) the applicant can accept a permit authorization and thereby agree to comply with all the terms and conditions of that permit, including whatever mitigation requirements the Corps has determined to be necessary; (5) undertaking any activity in reliance upon the subject permit authorization without requesting an AJD constitutes the applicant's acceptance of the use of the PJD; (6) accepting a permit authorization (e.g., signing a proffered individual permit) or undertaking any activity in reliance on any form of Corps permit authorization based on a PJD constitutes agreement that all aquatic resources in the review area affected in any way by that activity will be treated as jurisdictional, and waives any challenge to such jurisdiction in any administrative or judicial compliance or enforcement action, or in any administrative appeal or in any Federal court; and (7) whether the applicant elects to use either an AJD or a PJD, the JD will be processed as soon as practicable. Further, an AJD, a proffered individual permit (and all terms and conditions contained therein), or individual permit denial can be administratively appealed pursuant to 33 C.F.R. Part 331. If, during an administrative appeal, it becomes appropriate to make an official determination whether geographic jurisdiction exists over aquatic resources in the review area, or to provide an official delineation of jurisdictional aquatic resources in the review area, the Corps will provide an AJD to accomplish that result, as soon as is practicable. This PJD finds that there "may be" waters of the U.S. and/or that there "may be" navigable waters of the U.S. on the subject review area, and identifies all aquatic features in the review area that could be affected by the proposed activity, based on the following information:

### SUPPORTING DATA. Data reviewed for PJD (check all that apply)

Checked items should be included in subject file. Appropriately reference sources below where indicated for all checked items: Maps, plans, plots or plat submitted by or on behalf of the PJD requestor: Map: Delineation report dated June 12, 2019 Data sheets prepared/submitted by or on behalf of the PJD requestor. Office concurs with data sheets/delineation report. Office does not concur with data sheets/delineation report. Rationale: Data sheets prepared by the Corps: □ Corps navigable waters' study: U.S. Geological Survey Hydrologic Atlas: ☐ USGS NHD data. USGS 8 and 12 digit HUC maps. ■ U.S. Geological Survey map(s). Cite scale & quad name: <sup>24k</sup> De Gonia Springs, IN Natural Resources Conservation Service Soil Survey. Citation: ■ National wetlands inventory map(s). Cite name: NWI accessed 2019 State/local wetland inventory map(s): FEMA/FIRM maps: FEMA accessed 2019 100-year Floodplain Elevation is: \_\_\_\_\_.(National Geodetic Vertical Datum of 1929) Photographs: Aerial (Name & Date): ESRI World Imagery, 2014 Other (Name & Date): Site photos dated 10/11/18 Previous determination(s). File no. and date of response letter: ☐ Other information (please specify): IMPORTANT NOTE: The information recorded on this form has not necessarily been verified by the Corps and should not be relied upon for later jurisdictional determinations.

Harlan M. Ford Only September 1 Signature and date of Signature and date of Signature and date of Person requesting PJD (REQUIRED, unless obtaining the signature is impracticable)<sup>1</sup>

<sup>&</sup>lt;sup>1</sup> Districts may establish timeframes for requestor to return signed PJD forms. If the requestor does not respond within the established time frame, the district may presume concurrence and no additional follow up is necessary prior to finalizing an action.

### Raquel Walker

From: Cooper, Nicholas <NCooper5@indot.IN.gov>

**Sent:** Thursday, July 18, 2019 1:45 PM

To: Harlan Ford Cc: Howder, Aubrey

**Subject:** RE: Draft Env. WOUS Report for Des No. 1702071

Follow Up Flag: Follow up Flag Status: Flagged

## EXTERNAL E-MAIL MESSAGE

Harlan,

Thank you for submitting the waters report for **SR 62 over UNT to Otter Creek, Des. No. 1702071**. Your most recent submission has been reviewed and approved. For the INDOT PM, the approved report can be found on Projectwise through this link: **Des. No. 1702071 Waters Report - Final**. It is the responsibility of the Project Manager to forward a copy of this report to the Project Designer.

The information in this report should be used by the Project Designer to determine if waters of the U.S. will be impacted by the project. Avoidance and minimization of impacts must occur before mitigation will be considered. If mitigation is required, the Project Manager or Project Designer must coordinate with the Ecology and Waterway Permitting Office to discuss how adequate compensatory mitigation will be provided.

The Project Manager should notify the Ecology and Waterway Permitting Office if there is any change to the project footprint presented in this report. Such changes may require additional fieldwork and submittal of an updated waters report covering areas not previously investigated. This report is only valid for a period of five years from the date of earliest fieldwork. If the report expires prior to waterway permit application submittal, additional fieldwork and a revised waters report will be required.

It will not be sent to the United States Army Corps of Engineers (USACE) or the Indiana Department of Environmental Management (IDEM) until the waterways permit applications are submitted to these agencies.

#### **Nick Cooper**

Ecology and Waterway Permitting Specialist Indiana Department of Transportation Ph. (317) 233-3698

From: Harlan Ford [mailto:H.Ford@gaiconsultants.com]

**Sent:** Thursday, July 18, 2019 9:32 AM

**To:** Cooper, Nicholas <NCooper5@indot.IN.gov> **Cc:** Howder, Aubrey <AHowder@indot.IN.gov>

Subject: RE: Draft Env. WOUS Report for Des No. 1702071

\*\*\*\* This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email. \*\*\*\*

Hey Nick,

# Appendix G

# Air Quality

Item	Appendix Page
Statewide Transportation Improvement Plan (STIP)	G1
Evansville Metropolitan Planning Organization	G2



This project is part of a group of projects under Contract # 40551. The lead Des No. for this contract is Des. 1700170. Des No. 1702071 is included by reference.

Indiana Department of Transportation (INDOT)

	CONTR	STIP	ROUTE	WORK TYPE	LOCATION	DISTRICT	MILES	FEDERAL	Estimated	PROGRAM	PHASE	FEDERAL	MATCH	2020	2021	2022	2023	2024
	ACT#/ LEAD DES	NAME						CATEGORY	Cost left to Complete Project*					1010	2021	2022	2020	2024
diana Department Transportation	39418 / 1593067	Init.	SR 68	Bridge Replacement, Other Construction	Over Pigeon Creek Overflow, 2 .08 miles E of SR-57	Vincennes	0	STPBG		Bridge Construction	CN	\$1,608,980.80	\$402,245.20		\$2,011,226.00			
arrick County	39837 / 1600739	Init.	IR 1010	Bridge Replacement, Other Construction	Shilo Road Bridge # 113	Vincennes	.5	STPBG		Local Bridge Program	CN	\$1,075,000.00	\$0.00		\$40,000.00	\$1,035,000.00		
				•	•	•			1	Local Funds	CN	\$0.00	\$268,750.00		\$10,000.00	\$258,750.00		
arrick County	39837 / 1600739	A 05	IR 1010	Bridge Replacement, Other Construction	Shilo Road Bridge # 113	Vincennes	.5	STBG	\$1,393,750.00	Local Bridge Program	RW	\$40,000.00	\$0.00	\$40,000.00				
										Local Funds	RW	\$0.00	\$10,000.00	\$10,000.00				
omments:Amend 20	)20-2024 ST	IP. Addin	g FY20 RW	V Federal \$40,000.00, FY2	20 RW Local \$10,000.00. EMPO TIP	Letter 8-2-2019.												
oonville	39840 / 1600891	Init.	ST 1025	Road Rehabilitation (3 R/4R Standards)	3rd Street (formerly SR 61)	Vincennes	1	STPBG		Local Funds	CN	\$0.00	\$620,000.00			\$620,000.00		
		ı		•	1	1		I		Local Funds	RW	\$0.00	\$109,650.00	\$109,650.00				
										Group III Program	CN	\$2,480,000.00	\$0.00			\$2,480,000.00		
										Group III Program	RW	\$438,600.00	\$0.00	\$438,600.00				
	39921 / 1400195	Init.	SR 66	Other Intersection Improvement	At Epworth Road, 0.16 mile E I-	Vincennes	1.081	NHPP		Group III Program  Mobility  Construction	RW	\$438,600.00 \$3,268,456.80	\$0.00 \$817,114.20	\$438,600.00 \$175,000.00	\$3,910,571.00			
f Transportation		Init.	SR 66		At Epworth Road, 0.16 mile E I- 69 Over Old Pigeon Creek, 1.56 miles E SR-57	Vincennes Vincennes		NHPP STPBG		Mobility					\$3,910,571.00			
ndiana Department f Transportation ndiana Department f Transportation ndiana Department f Transportation	1400195 40051 /			Improvement Bridge Thin Deck	69 Over Old Pigeon Creek, 1.56		0			Mobility Construction Bridge	CN	\$3,268,456.80	\$817,114.20	\$175,000.00	\$3,910,571.00			
Transportation  diana Department Transportation  diana Department	1400195 40051 / 1602256 40541 /	Init.	SR 68	Improvement  Bridge Thin Deck Overlay  Bridge Replacement,	69  Over Old Pigeon Creek, 1.56 miles E SR-57  Over Wallace Creek, 00.95	Vincennes	0	STPBG		Mobility Construction Bridge Construction	CN	\$3,268,456.80 \$2,629,128.80	\$817,114.20 \$657,282.20	\$175,000.00 \$3,286,411.00	\$3,910,571.00	\$828,646.00		
Transportation  diana Department Transportation  diana Department Transportation	1400195 40051 / 1602256 40541 /	Init.	SR 68	Improvement  Bridge Thin Deck Overlay  Bridge Replacement,	69  Over Old Pigeon Creek, 1.56 miles E SR-57  Over Wallace Creek, 00.95	Vincennes	0	STPBG		Mobility Construction Bridge Construction Bridge ROW	CN CN RW	\$3,268,456.80 \$2,629,128.80 \$24,000.00	\$817,114.20 \$657,282.20 \$6,000.00	\$175,000.00 \$3,286,411.00	\$3,910,571.00	\$828,646.00		
Transportation  diana Department Transportation  diana Department Transportation	1400195 40051 / 1602256 40541 / 1700167	Init.	SR 68	Improvement  Bridge Thin Deck Overlay  Bridge Replacement, Concrete  Small Structure	69  Over Old Pigeon Creek, 1.56 miles E SR-57  Over Wallace Creek, 00.95 miles E SR-161	Vincennes	0	STPBG		Mobility Construction Bridge Construction Bridge ROW Bridge Construction	CN CN RW	\$3,268,456.80 \$2,629,128.80 \$24,000.00 \$662,916.80	\$817,114.20 \$657,282.20 \$6,000.00 \$165,729.20	\$175,000.00 \$3,286,411.00 \$30,000.00	\$3,910,571.00	\$828,646.00 \$2,024,438.00		
Transportation  diana Department Transportation  diana Department Transportation  diana Department Transportation	1400195 40051 / 1602256 40541 / 1700167	Init.	SR 68	Improvement  Bridge Thin Deck Overlay  Bridge Replacement, Concrete  Small Structure	69  Over Old Pigeon Creek, 1.56 miles E SR-57  Over Wallace Creek, 00.95 miles E SR-161	Vincennes	0	STPBG		Mobility Construction  Bridge Construction  Bridge ROW  Bridge ROW  Bridge Bridge ROW  Bridge ROW	CN CN RW	\$3,268,456.80 \$2,629,128.80 \$24,000.00 \$662,916.80 \$14,400.00	\$657,282.20 \$657,282.20 \$6,000.00 \$165,729.20 \$3,600.00	\$175,000.00 \$3,286,411.00 \$30,000.00	\$3,910,571.00			
Transportation  diana Department Transportation  diana Department	1400195 40051 / 1602256 40541 / 1700167 40551 / 1700170	Init.	SR 68	Improvement  Bridge Thin Deck Overlay  Bridge Replacement, Concrete  Small Structure Replacement  HMA Overlay, Preventive	69  Over Old Pigeon Creek, 1.56 miles E SR-57  Over Wallace Creek, 00.95 miles E SR-161  10.46 miles N Jct SR-66  From I-69 to Ellerbusch Road, 1	Vincennes  Vincennes  Vincennes	0 0 1.555	STPBG STPBG		Mobility Construction  Bridge Construction  Bridge ROW  Bridge Construction  Bridge ROW  Bridge Construction  Bridge ROW	CN CN RW CN CN CN	\$3,268,456.80 \$2,629,128.80 \$24,000.00 \$662,916.80 \$14,400.00 \$1,619,550.40	\$817,114.20 \$657,282.20 \$6,000.00 \$165,729.20 \$3,600.00 \$404,887.60	\$175,000.00 \$3,286,411.00 \$30,000.00 \$18,000.00	\$3,910,571.00			

Page 348 of 367 Report Created:11/27/2019 2:41:57PM

<sup>\*</sup>Estimated Costs left to Complete Project column is for costs that may extend beyond the four years of a STIP. This column is not fiscally constrained and is for information purposes.

## **Table 5.4**: **TIP Projects Listing Cont.**

Sponsor: India	na Department of Transpor	tation										
Route	Project Limits				All amo	ounts in thous	ands					
Des#	Planning Reference	Map ID	Dhooo						Planning/	Fodoral Char	Cto	to Chara
Length:	Federal Funding Source	Amendment/	Phase	2020	2021	2022	2023	2024	Cost to Complete	Federal Share	Sta	te Share
Description:		Modification Date							Complete			
Warrick County										•		
SR 68	0.08 mi. W of SR 61		PE							\$ -	\$	-
1400157			RW	\$134						\$ 107	\$	27
n/a	STBG, NHPP	9/12/2019	CN	\$310						\$ 248	\$	62
Contract 38721;	Small structure replacement.											
I-64	Over Plum Creek, 3.92 mi W of	SR 61, EBL & WBL	PE	\$289						\$ 231	. \$	58
1593068			RW							\$ -	\$	-
n/a	NHPP	10/10/2019	CN				\$3,646			\$ 3,281	. \$	365
Contract 39367;	Replace Superstructure.											
SR 61	From 0.17 mi E of W Jct SR-62	to E Jct SR-62	PE							\$ -	\$	-
1592969			RW							\$ -	\$	-
	STBG		CN	\$1,762						\$ 1,410	\$	352
Contract 39377;	HMA Overlay, preventative mainte	nance.										
SR 161	From E jct with SR 62 to W jct		PE							\$ -	\$	-
1592941			RW	\$40							\$	8
10.129 mi.	STBG	11/14/2019	CN	\$4,047						\$ 3,238	\$	809
Contract 39380;	Pavement HMA Overlay, structural	l.										
SR 68	Over Pigeon Creek Overflow, 2.		PE							\$ -	\$	-
1593067			RW							\$ -	\$	-
n/a	STBG		CN		\$2,011					\$ 1,609	\$	402
Contract 39418; I	Bridge replacement, other constru	uction										
SR 66	0.16 mi. E of I-69 at Epworth R	d.	PE							\$ -	\$	-
1400195			RW							\$ -	\$	-
1.081 mi.	NHPP		CN	\$175	\$3,910					\$ 3,268	\$	817
Contract 39921;	Other intersection improvement											
SR 68	Over Old Pigeon Creek, 1.56 m	i. E of SR 57	PE							\$ -	\$	-
1602256			RW							\$ -	\$	-
n/a	STBG		CN	\$3,286						\$ 2,629	\$	657
Contract 40051; I	Bridge thin deck overlay.											
SR 68	Over Wallace Creek, 0.95 mi E	of SR 161	PE							\$ -	\$	-
1700167			RW	\$30						\$ 24	\$	6
n/a	STBG		CN			\$829				\$ 663	\$	166
Contract 40541; I	Bridge replacement											
SR 161	10.46 mi. N Jct. SR 66		PE							\$ -	\$	-
1700170			RW	\$18						\$ 14	\$	4
n/a	STBG		CN			\$2,025				\$ 1,620	\$	405
Contract 40551:	Small structure replacement.											
SR 662	From I-69 to Ellerbusch Rd.		PE							\$ -	\$	-
1701206			RW							\$ -	\$	-
1.55 mi.	STBG		CN	\$877							\$	175
Contract 40626; I	HMA Overlay, preventative mainte	nance.										
SR 61	From 0.14 mi S of I-64 to 0.88		PE							\$ -	\$	-
1800176			RW			\$30					\$	6
0.88	STBG		CN				\$721			\$ 577		144
	HMA Overlay, preventative mainte	nance.										
I-64	CCTV Cameras/Detection from		PE				\$155			\$ 140	) \$	16
1802047	,		RW							\$ -	\$	-
n/a	NHPP		CN					\$1,725		\$ 1,553		173
	ITS Traffic management systems.							•				
SR 61 & SR 68	Various locations		PE							\$ -	\$	-
Various			RW							\$ -	\$	-
n/a	STBG		CN		\$1,438					\$ 1,150		288
	Bridge Thin Deck Overlays. Includ	les locations outside MP			, _, .00						-	_00
I-64 & SR 68	Various locations		PE PE							\$ -	\$	-
Various			RW							\$ -	\$	_
n/a	NHPP, STBG		CN		\$3,258					\$ 2,606		652
	Bridge Deck Overlays. Includes to	neations outside MDO TII			ψ3,236					φ 2,000	, φ	032
SR 66	From 2.2 mi, E of SR 61 to US		PE							\$ -	\$	
1592783	FIUIII 2.2 IIII. E 01 5K 01 (0 US	231									\$	-
	NHPP		RW CN	¢6.070						\$ - \$ 5,023		1 050
15.91 mi.		o maintananaa Inaliida		\$6,279	ID area					φ 5,023	• •	1,256
CONTRACT 39357; I	Pavement HMA Overlay, preventiv	e maintenance. Include	ร เบเสนิบกิริ (	outside EMPO I	ır area.							

# Appendix H

## Environmental Justice

Item	Appendix Page
EJ Analysis	H1 to H4



## **Environmental Justice (EJ) Analysis**

Small Structure Replacement, SR-62 over UNT Otter Creek Warrick County, Indiana Des. No. 1702071

	Community of Concern (COC)	Affected Community (AC 1)
	Warrick County, Indiana	Census Tract 301
Income		
Total population for the purpose of surveying poverty income:	60,540	3,728
Population with income in the past 12 months below poverty level:	4,656	343
Percent Low Income	7.69%	9.20%
125% of COC	9.61%	
Potential Low-income EJ Concern?		No
Race		
Total Population for the purpose of surveying race:	61,581	3,731
Total population non-hispanic/latino; white alone:	57,148	3,721
Number of Minorities	4433	10
Percent of Minorities	7.20%	0.27%
125% of COC	9.00%	
Potential Minority EJ Concern?		No

# B17001: POVERTY STATUS IN THE PAST 12 MONTHS BY SEX BY AGE - Universe: Population for whom poverty status is determined 2013-2017 American Community Survey 5-Year Estimates

Note: This is a modified view of the original table.

Supporting documentation on code lists, subject definitions, data accuracy, and statistical testing can be found on the American Community Survey website in the Technical Documentation section.

Sample size and data quality measures (including coverage rates, allocation rates, and response rates) can be found on the American Community Survey website in the Methodology section.

Although the American Community Survey (ACS) produces population, demographic and housing unit estimates, it is the Census Bureau's Population Estimates Program that produces and disseminates the official estimates of the population for the nation, states, counties, cities, and towns and estimates of housing units for states and counties.

	Warrick County, Indiana		Census Tract 30	I, Warrick	
	Estimate	Margin of Error	Estimate	Margin of Error	
Total:	60,540	+/-239	3,728	+/-272	
Income in the past 12 months below poverty level:	4,656	+/-822	343	+/-166	
Male:	1,787	+/-417	179	+/-126	
Under 5 years	65	+/-51	0	+/-11	
5 years	32	+/-39	0	+/-11	
6 to 11 years	314	+/-184	5	+/-5	
12 to 14 years	59	+/-45	0	+/-11	
15 years	5	+/-8	5	+/-8	
16 and 17 years	99	+/-63	0	+/-11	
18 to 24 years	224	+/-107	69	+/-74	
25 to 34 years	201	+/-108	3	+/-4	
35 to 44 years	181	+/-112	16	+/-17	
45 to 54 years	167	+/-85	32	+/-48	
55 to 64 years	257	+/-111	14	+/-14	
65 to 74 years	93	+/-57	9	+/-14	
75 years and over	90	+/-58	26	+/-40	
Female:	2,869	+/-538	164	+/-90	
Under 5 years	170	+/-103	2	+/-4	
5 years	0	+/-27	0	+/-11	
6 to 11 years	294	+/-124	0	+/-11	
12 to 14 years	111	+/-91	2	+/-3	
15 years	118	+/-93	0	+/-11	
16 and 17 years	219	+/-134	28	+/-40	
18 to 24 years	208	+/-98	4	+/-5	
25 to 34 years	212	+/-112	2	+/-3	
35 to 44 years	374	+/-167	6	+/-5	
45 to 54 years	323	+/-109	44	+/-35	
55 to 64 years	314	+/-123	7	+/-7	
65 to 74 years	195	+/-101	47	+/-46	
75 years and over	331	+/-124	22	+/-21	
Income in the past 12 months at or above poverty		+/-866	3,385	+/-284	

Data are based on a sample and are subject to sampling variability. The degree of uncertainty for an estimate arising from sampling variability is represented through the use of a margin of error. The value shown here is the 90 percent margin of error. The margin of error can be interpreted roughly as providing a 90 percent probability that the interval defined by the estimate minus the margin of error and the estimate plus the margin of error (the lower and upper confidence bounds) contains the true value. In addition to sampling variability, the ACS estimates are subject to nonsampling error (for a discussion of nonsampling variability, see Accuracy of the Data). The effect of nonsampling error is not represented in these tables.

While the 2013-2017 American Community Survey (ACS) data generally reflect the February 2013 Office of Management and Budget (OMB) definitions of metropolitan and micropolitan statistical areas; in certain instances the names, codes, and boundaries of the principal cities shown in ACS tables may differ from the OMB definitions due to differences in the effective dates of the geographic entities.

Estimates of urban and rural populations, housing units, and characteristics reflect boundaries of urban areas defined based on Census 2010 data. As a result, data for urban and rural areas from the ACS do not necessarily reflect the results of ongoing urbanization.

Source: U.S. Census Bureau, 2013-2017 American Community Survey 5-Year Estimates

#### Explanation of Symbols:

- 1. An "\*\* entry in the margin of error column indicates that either no sample observations or too few sample observations were available to compute a standard error and thus the margin of error. A statistical test is not appropriate.
- 2. An '-' entry in the estimate column indicates that either no sample observations or too few sample observations were available to compute an estimate, or a ratio of medians cannot be calculated because one or both of the median estimates falls in the lowest interval or upper interval of an open-ended distribution.
- 3. An '-' following a median estimate means the median falls in the lowest interval of an open-ended distribution.
- 4. An '+' following a median estimate means the median falls in the upper interval of an open-ended distribution.
- 5. An "\*\*" entry in the margin of error column indicates that the median falls in the lowest interval or upper interval of an open-ended distribution. A statistical test is not appropriate.
- 6. An '\*\*\*\*\*' entry in the margin of error column indicates that the estimate is controlled. A statistical test for sampling variability is not appropriate.
- 7. An 'N' entry in the estimate and margin of error columns indicates that data for this geographic area cannot be displayed because the number of sample cases is too small.
- 8. An '(X)' means that the estimate is not applicable or not available.

# B03002: HISPANIC OR LATINO ORIGIN BY RACE - Universe: Total population 2013-2017 American Community Survey 5-Year Estimates

Note: This is a modified view of the original table.

Supporting documentation on code lists, subject definitions, data accuracy, and statistical testing can be found on the American Community Survey website in the Technical Documentation section.

Sample size and data quality measures (including coverage rates, allocation rates, and response rates) can be found on the American Community Survey website in the Methodology section.

Although the American Community Survey (ACS) produces population, demographic and housing unit estimates, it is the Census Bureau's Population Estimates Program that produces and disseminates the official estimates of the population for the nation, states, counties, cities, and towns and estimates of housing units for states and counties.

	Warrick County, Indiana		Census Tract 301, Warr	
	Estimate	Margin of	Estimate	Margin of
Total:	61,581	****	3,731	+/-272
Not Hispanic or Latino:	60,491	****	3,729	+/-272
White alone	57,148	+/-79	3,721	+/-271
Black or African American alone	968	+/-120	0	+/-11
American Indian and Alaska Native	108	+/-68	0	+/-11
Asian alone	1,519	+/-94	8	+/-14
Native Hawaiian and Other Pacific	14	+/-24	0	+/-11
Some other race alone	32	+/-34	0	+/-11
Two or more races:	702	+/-187	0	+/-11
Two races including Some other race	50	+/-54	0	+/-11
Two races excluding Some other	652	+/-184	0	+/-11
Hispanic or Latino:	1,090	****	2	+/-3
White alone	793	+/-174	2	+/-3
Black or African American alone	0	+/-27	0	+/-11
American Indian and Alaska Native	0	+/-27	0	+/-11
Asian alone	0	+/-27	0	+/-11
Native Hawaiian and Other Pacific	0	+/-27	0	+/-11
Some other race alone	197	+/-160	0	+/-11
Two or more races:	100	+/-81	0	+/-11

Data are based on a sample and are subject to sampling variability. The degree of uncertainty for an estimate arising from sampling variability is represented through the use of a margin of error. The value shown here is the 90 percent margin of error. The margin of error can be interpreted roughly as providing a 90 percent probability that the interval defined by the estimate minus the margin of error and the estimate plus the margin of error (the lower and upper confidence bounds) contains the true value. In addition to sampling variability, the ACS estimates are subject to nonsampling error (for a discussion of nonsampling variability, see Accuracy of the Data). The effect of nonsampling error is not represented in these tables.

While the 2013-2017 American Community Survey (ACS) data generally reflect the February 2013 Office of Management and Budget (OMB) definitions of metropolitan and micropolitan statistical areas; in certain instances the names, codes, and boundaries of the principal cities shown in ACS tables may differ from the OMB definitions due to differences in the effective dates of the geographic entities.

Estimates of urban and rural populations, housing units, and characteristics reflect boundaries of urban areas defined based on Census 2010 data. As a result, data for urban and rural areas from the ACS do not necessarily reflect the results of ongoing urbanization.

Source: U.S. Census Bureau, 2013-2017 American Community Survey 5-Year Estimates

#### Explanation of Symbols:

- 1. An '\*\* entry in the margin of error column indicates that either no sample observations or too few sample observations were available to compute a standard error and thus the margin of error. A statistical test is not appropriate.
- 2. An '-' entry in the estimate column indicates that either no sample observations or too few sample observations were available to compute an estimate, or a ratio of medians cannot be calculated because one or both of the median estimates falls in the lowest interval or upper interval of an open-ended distribution.
- 3. An '-' following a median estimate means the median falls in the lowest interval of an open-ended distribution.
- 4. An '+' following a median estimate means the median falls in the upper interval of an open-ended distribution.
- 5. An "\*\*\* entry in the margin of error column indicates that the median falls in the lowest interval or upper interval of an open-ended distribution. A statistical test is not appropriate.
- 6. An '\*\*\*\*\* entry in the margin of error column indicates that the estimate is controlled. A statistical test for sampling variability is not appropriate.
- 7. An 'N' entry in the estimate and margin of error columns indicates that data for this geographic area cannot be displayed because the number of sample cases is too small.
- 8. An '(X)' means that the estimate is not applicable or not available





Des No. 1702071

### Legend:

### **Your Selections**


2017 boundaries were used to map 'Your Selections'

### **Selection Results**

No Legend

#### 2018 Boundaries

- ☐ Census Tract
- □ Block Group



# Appendix I

## Additional Studies

Item	Appendix Page
Land & Water Conservation Funds Grants	I1
IDNR-DOR LWCF Property List	I2



## Land and Water Conservation Fund Grants: Indiana

The Park Service is finding out about more closures and conversions of federally protected parks than ever before. But no one knows just how many, so InvestigateWest compiled this database, which lists every LWCF grant between 1965 and 2011, as a starting point. Click a column header to re-sort the table. Click-shift to add a secondary sort.

RETURN TO THE PROJECT PAGE

FILTER THE LIST: Warrick

Grant ID & Element	Grant Name	Sponsor	County	State	Grant Amount	Year Approved	Year Completed	Туре
82 - XXX	NEWBURGH PARK AND SWIMMING POOL	NEWBURGH PARK BOARD	WARRICK	IN	\$111,076.39	1971	1973	Combination
383 - XXX	AMAX ATHLETIC FIELD	NEWBURGH PARK	WARRICK	IN	\$50,000.00	1981	1985	Development

AN
INVESTIGATEWEST
DATA PROJECT

Land and Water Conservation Fund (LWCF) County Property List for Indiana (Last Updated December 2019)

ProjectNumber	SubProjectCode	County	Property		
1800082	1800082	Warrick	Newburgh Community Park and Newburgh Community Poo		
1800383	1800383	Warrick	Newburgh-Amax Athletic Park, Ed Gesser Soccer,		
1800405	1800405O	Warrick	Little Pigeon Creek Wetland Conservation Area		

Please note, some of the property names are cut off on the ends due to character limits Also, park names may have changed and is not reflected on the list.

<sup>\*</sup>Various - this may include multiple sites in multiple counties and should always be included in your searches by county.